






6375 (D,E,F)

THE VALENCIA
NAPA SERIES

60'0 X 74'0

REVISION SCHEDULE			
NO.	DATE	DESCRIPTION	BY
	08-26-19	-THESE PLANS CREATED USING 6215 MONTICELLO PLANS DATED 190813 PROVIDED BY PSH	MF
	04-01-20	-ADD FRAME WALK CHANGES	ME
	02-16-21	UPDATE TO CODE 2020 - ELEV E	ME
	02-22-21	UPDATE TO CODE 2020 - ELEV D & F	ME
			

SHEET INDEX- ELEVATION "D"

- 00 COVER SHEET
- 01D.0 FOUNDATION PLAN
- 02D.0 FLOOR PLAN W/ DIMENSIONS
- 03D.0 FLOOR PLAN W/ NOTES
- 04D.0 UPPER FLOOR PLAN W/ DIMENSIONS
- 05D.0 UPPER FLOOR PLAN W/ NOTES
- 06D.0 EXTERIOR ELEVATIONS- FRONT/ REAR
- 07D.0 EXTERIOR ELEVATIONS- LEFT/ RIGHT
- 08 CROSS SECTION AND INTERIOR ELEVATIONS
- 09.0 ELECTRICAL PLAN
- 10.0 UPPER ELECTRICAL PLAN
- 11D.0 TRUSS LAYOUT
- 12D.0 UPPER TRUSS LAYOUT
- 13D.0 PRECAST LINTEL LAYOUT
- 14 TYPICAL DETAILS/CONNECTOR SCHEDULE
- 15 TYPICAL DETAILS
- 16 TYPICAL DETAILS
- 17 TYPICAL DETAILS
- D1 TYPICAL STRUCTURAL DETAILS
- D2.0 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 TYPICAL STRUCTURAL DETAILS
- D5 TYPICAL STRUCTURAL DETAILS

SHEET INDEX- ELEVATION "E"

- 00 COVER SHEET
- 01E.0 FOUNDATION PLAN
- 02E.0 FLOOR PLAN W/ DIMENSIONS
- 03E.0 FLOOR PLAN W/ NOTES
- 04E.0 UPPER FLOOR PLAN W/ DIMENSIONS
- 05E.0 UPPER FLOOR PLAN W/ NOTES
- 06E.0 EXTERIOR ELEVATIONS- FRONT/ REAR
- 07E.0 EXTERIOR ELEVATIONS- LEFT/ RIGHT
- 08 CROSS SECTION AND INTERIOR ELEVATIONS
- 09.0 ELECTRICAL PLAN
- 10.0 UPPER ELECTRICAL PLAN
- 11E.0 TRUSS LAYOUT
- 12E.0 UPPER TRUSS LAYOUT
- 13E.0 PRECAST LINTEL LAYOUT
- 14 TYPICAL DETAILS/CONNECTOR SCHEDULE
- 15 TYPICAL DETAILS
- 16 TYPICAL DETAILS
- 17 TYPICAL DETAILS
- D1 TYPICAL STRUCTURAL DETAILS
- D2.0 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 TYPICAL STRUCTURAL DETAILS
- D5 TYPICAL STRUCTURAL DETAILS

SHEET INDEX- ELEVATION "F"

- 00 COVER SHEET
- 01F.0 FOUNDATION PLAN
- 02F.0 FLOOR PLAN W/ DIMENSIONS
- 03F.0 FLOOR PLAN W/ NOTES
- 04F.0 UPPER FLOOR PLAN W/ DIMENSIONS
- 05F.0 UPPER FLOOR PLAN W/ NOTES
- 06F.0 EXTERIOR ELEVATIONS- FRONT/ REAR
- 07F.0 EXTERIOR ELEVATIONS- LEFT/ RIGHT
- 08 CROSS SECTION AND INTERIOR ELEVATIONS
- 09.0 ELECTRICAL PLAN
- 10.0 UPPER ELECTRICAL PLAN
- 11F.0 TRUSS LAYOUT
- 12F.0 UPPER TRUSS LAYOUT
- 13F.0 PRECAST LINTEL LAYOUT
- 14 TYPICAL DETAILS/CONNECTOR SCHEDULE
- 15 TYPICAL DETAILS
- 16 TYPICAL DETAILS
- 17 TYPICAL DETAILS
- D1 TYPICAL STRUCTURAL DETAILS
- D2.0 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 TYPICAL STRUCTURAL DETAILS
- D5 TYPICAL STRUCTURAL DETAILS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS

BY

Engineering By:
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

COVER SHEET

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19


SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET 00

OF SHEETS




SIDEWALK LAYOUT

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WWF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- ⊗ STANDARD FOOTING
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.402 FLORIDA BUILDING CODE.
- TYP. TUB/SHUR. VALVE & DRAIN LOCATIONS



FOUNDATION PLAN "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

REVISIONS BY
Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

FOUNDATION PLAN

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19


SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET

01D.0
OF SHEETS





SIDEWALK LAYOUT

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WWF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- STANDARD FOOTING
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.402 FLORIDA BUILDING CODE.
- TYP. TUB/SHUR. VALVE & DRAIN LOCATIONS



FOUNDATION PLAN "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

THE VALENCIA

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET 01E.0

OF SHEETS

FOUNDATION PLAN

NAPA SERIES


NAPA SERIES

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

REVISIONS	BY




SIDEWALK LAYOUT

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WWF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- STANDARD FOOTING
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.402 FLORIDA BUILDING CODE.
- TYP. TUB/SHUR. VALVE & DRAIN LOCATIONS



FOUNDATION PLAN "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

FOUNDATION PLAN

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET

01F.0
OF SHEETS

TABULATION	
UPPER LIVING	3,324 SF.
LOWER LIVING	3,051 SF.
TOTAL LIVING	6,375 SF.
GARAGE	567 SF.
ENTRY	208 SF.
LANAI	365 SF.
TOTAL UNDER ROOF	7,515 SF.


GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE $3\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE $1\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

- ### GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
 2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
 3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE $3\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
 4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE $7\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
 5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

FLOOR PLAN W/ DIMENSIONS "D"

FLOOR PLAN W/ DIMENSIONS "D"



© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-1

SCALE AS NOTED

DRAWN RD

JOB 637

SHEET

02DC

OF SHEET:

NAPA
SERIES

Engineering By:	BY
DBE and C	
MICHAEL A. THOMPSON	
PE 47509	
PHONE 407-721-2292	

**A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000**

**Park
Square
HOMES**

FLOOR PLAN W/ DIMENSIONS

THE VALENCIA


NAPA SERIES

TABULATION	
UPPER LIVING	3,324 SF.
LOWER LIVING	3,051 SF.
TOTAL LIVING	6,375 SF.
GARAGE	567 SF.
ENTRY	208 SF.
LANAI	365 SF.
TOTAL UNDER ROOF	7,515 SF.

- GENERAL NOTES
- CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
 - DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
 - ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3½" UNLESS NOTED OTHERWISE.
 - ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1½" UNLESS NOTED OTHERWISE.
 - PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

FLOOR PLAN W/ DIMENSIONS "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1ST EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

THE VALENCIA

FLOOR PLAN W/ DIMENSIONS

NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET 02E.0

OF SHEETS

Engineering By

DBE and C

MICHAEL A. THOMPSON

PE 47509

PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC.

5200 Vineland Road, Suite 200

Orlando, Florida 32811

Phone: (407) 529 - 3000

© COPYRIGHT 2015

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.


REVISIONS

BY

TABULATION		
UPPER LIVING	3,324	SF.
LOWER LIVING	3,051	SF.
TOTAL LIVING	6,375	SF.
GARAGE	567	SF.
ENTRY	208	SF.
LANAI	363	SF.
TOTAL UNDER ROOF	7,515	SF.

GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE $3\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE $1\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.



FLOOR PLAN W/ DIMENSIONS "F"

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

NAPA SERIES

© COPYRIGHT 2015
or changed in any manner or form whatsoever, nor are they to be assigned to any third party without the express written permission from Park Square Homes.
Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and designs. These plans, ideas and designs are not to be copied

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

OB 6375

HEET



02F0

OF SHEETS


LOAD INFORMATION
PER 1TH EDITION, 2020 FLORIDA BUILDING
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF
FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 PSF
ROOMS OTHER THAN SLEEPING ROOM:	40 PSF
SLEEPING ROOM:	30 PSF
STAIR LIVE LOAD:	40 PSF
BALCONIES:	40 PSF
PASSANGER VEHICLE GARAGE:	50 PSF
ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (PSF) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER	
ROOF SLOPE	0-200 201-600 OVER 600
0:12 < 4:12	20 16 12
≥ 4:12 < 12:12	16 14 12
≥ 12:12	12 12 12

WIND INFORMATION	
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE	
1. BASIC WIND SPEED:	140 MPH
2. RISK CATEGORY	II
3. WIND EXPOSURE:	B
4. BUILDING TYPE:	V B
5. ENCLOSURE	+/- 18, INCLUDED CLASSIFICATION INTERNAL IN NOTE #6 PRESSURE COEFFICIENT:
6. COMPONENT / CLADDING	SEE PLAN DESIGN WIND PRESSURE:
+ XXX	DESIGN WIND PRESSURE IAW FLA
- XXX	RESIDENTIAL CODE, SECTION R301
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.	

GENERAL NOTES	
1. PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.	
2. VENT DRYER THRU ROOF.	
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.	
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.	
5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.	
6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.	
 DENOTES CONC. BLOCK WALL HGT. @ 11'-4" AFF.	
7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS	
8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES	
9. ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2	
10. ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.	
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.	

NOTE: DOOR FROM HOUSE TO GARAGE MUST
BE SOLID WOOD DOORS NO LESS 1 3/8"
IAW R302.5.1



FLOOR PLAN W/ NOTES "D"
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ALL INTERIOR DOORS ON THIS
FLOOR TO BE: 6'-8" UNO.

NAPA SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

Copyright 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS BY
Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park
Square
HOMES

FLOOR PLAN W/ NOTES

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET

03D.0
OF SHEETS

LOAD INFORMATION
PER 1TH EDITION, 2020 FLORIDA BUILDING
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF
ROOF: SHEATHING	
STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
TOTAL	20 PSF

FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 PSF
ROOMS OTHER THAN	
SLEEPING ROOM:	40 PSF
SLEEPING ROOM:	30 PSF
STAIR LIVE LOAD:	40 PSF
BALCONIES:	40 PSF
PASSANGER VEHICLE GARAGE:	50 PSF

ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (PSF) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER	
ROOF SLOPE	0-200 201-600 OVER 600
0:12 < 4:12	20 16 12
≥ 4:12 < 12:12	16 14 12
≥ 12:12	12 12 12


WIND INFORMATION
PER 1TH EDITION, 2020 FLORIDA BUILDING
RESIDENTIAL CODE

- BASIC WIND SPEED: 140 MPH
- RISK CATEGORY: II
- WIND EXPOSURE: B
- BUILDING TYPE: V-B
- ENCLOSURE: +/-18, INCLUDED CLASSIFICATION INTERNAL IN NOTE #6 PRESSURE COEFFICIENT:
- COMPONENT / CLADDING: SEE PLAN DESIGN WIND PRESSURE:
+ XXX DESIGN WIND PRESSURE IAW FLA
- XXX RESIDENTIAL CODE, SECTION R301
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.

GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.
- DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.
 DENOTES CONC. BLOCK WALL HGT. @ 11'-4" AFF.
- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2
- ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOORS NO LESS 1 3/8" IAW R302.5.1



FLOOR PLAN W/ NOTES "E"
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" UNO.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

REVISIONS		BY
FLOOR PLAN W/ NOTES		
THE VALENCIA		
NAPA SERIES		
6375		
DATE	08-26-19	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	6375	
SHEET	03E.0	
OF	3 SHEETS	

LOAD INFORMATION
PER 1TH EDITION, 2020 FLORIDA BUILDING
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF
ROOF: SHEATHING	
STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
TOTAL	20 PSF

FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 PSF
ROOMS OTHER THAN	
SLEEPING ROOM:	40 PSF
SLEEPING ROOM:	30 PSF
STAIR LIVE LOAD:	40 PSF
BALCONIES:	40 PSF
PASSANGER VEHICLE GARAGE:	50 PSF
ROOF LIVE LOADS	

MINIMUM ROOF LIVE LOAD (PSF)	
TRIBUTARY LOADED AREA (SQ. FT.)	FOR ANY STRUCTURAL MEMBER
ROOF SLOPE	0-200 201-600 OVER 600
0:12 < 4:12	20 16 12
≥ 4:12 < 12:12	16 14 12
≥ 12:12	12 12 12


WIND INFORMATION
PER 1TH EDITION, 2020 FLORIDA BUILDING
RESIDENTIAL CODE

- BASIC WIND SPEED: 140 MPH
 - RISK CATEGORY II
 - WIND EXPOSURE: B
 - BUILDING TYPE: V-B
 - ENCLOSURE: +/-18, INCLUDED CLASSIFICATION INTERNAL IN NOTE #6 PRESSURE COEFFICIENT:
 - COMPONENT / CLADDING: SEE PLAN DESIGN WIND PRESSURE:
- + XXX DESIGN WIND PRESSURE IAW FLA
- XXX RESIDENTIAL CODE, SECTION R301
- NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.

GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.
- DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.
 DENOTES CONC. BLOCK WALL HGT. @ 11'-4" AFF.
- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2
- ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOORS NO LESS 1 3/8" IAW R302.5.1



FLOOR PLAN W/ NOTES "F"
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" UNO.

NAPA SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

FLOOR PLAN W/ NOTES

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19


SCALE AS NOTED

DRAWN RDC

JOB 6375


SHEET 03F.0

OF SHEETS


$$\overline{1/8'' = 1' - \emptyset'' (11 \times 17) \quad 1/4'' = 1' - \emptyset'' (22 \times 34)}$$


- ### GENERAL NOTES

OF SHEETS


$$1/8^{\circ}=1'-0'' \text{ (11} \times 17) \quad 1/4^{\circ}=1'-0'' \text{ (22} \times 34)$$
$$1/8'' = 1' - \emptyset' \quad (11 \times 17) \quad 1/4'' = 1' - \emptyset'' \quad (22 \times 34)$$


1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE $3\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE $1\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
5. ALL INTERIOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.
6. MECHANICAL EQUIPMENT LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.

These are not to be copied from Park Square Homes.

THE VALENCIA

NAPA SERIES

UPPER FLOOR PLAN W/ DIMENSIONS

**A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000**


Engineering By:
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

REVISIONS	BY
-----------	----


$$1/8'' = 1' - \emptyset'' \quad (11 \times 17) \quad 1/4'' = 1' - \emptyset'' \quad (22 \times 34)$$

UPPER FLOOR PLAN WITH
DIMENSIONS "F"

$1/8^{\circ} = 1^{\circ} - \emptyset^{\circ}$ (11X17) $1/4^{\circ} = 1^{\circ} - \emptyset^{\circ}$ (22X34)



GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE $3\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE $1\frac{1}{2}"$ UNLESS NOTED OTHERWISE.
5. ALL INTERIOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.
6. MECHANICAL EQUIPMENT LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.

NAPA SERIES

Park Square HOMES

UPPER FLOOR PLAN WITH DIMENSIONS

THE VALLEY

NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

OB 6375

04F.0

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.



Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	REVISIONS	B

**A DIVISION OF PARK SQUARE
ENTERPRISES, INC.**
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square HOMES

LOAD INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
DEAD LOADS		
FLOOR: STRUCTURE	-----	1 PSF
CEILINGS	-----	3 PSF
MECH/ELEC	-----	5 PSF
PARTITIONS	-----	5 PSF
TOTAL	-----	20 PSF
FLOOR LIVE LOADS		
RESIDENTIAL FLOOR:	-----	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	-----	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	-----	20 PSF
ROOMS OTHER THAN SLEEPING ROOM:	-----	40 PSF
SLEEPING ROOM:	-----	30 PSF
STAIR LIVE LOAD:	-----	40 PSF
BALCONIES:	-----	40 PSF
PASSANGER VEHICLE GARAGE:	-----	50 PSF
ROOF LIVE LOADS		
MINIMUM ROOF LIVE LOAD (PSF) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER		
ROOF SLOPE	0-200	201-600
0:12 < 4:12	20	16
≥ 4:12 < 12:12	16	14
≥ 12:12	12	12


WIND INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
1. BASIC WIND SPEED:	-----	140 MPH
2. RISK CATEGORY	-----	II
3. WIND EXPOSURE:	-----	B
4. BUILDING TYPE:	-----	V B
5. ENCLOSURE CLASSIFICATION -- +/- .18, INCLUDED INTERNAL PRESSURE	-----	IN NOTE #6
6. COMPONENT / CLADDING	-----	SEE PLAN DESIGN WIND PRESSURE:
+ XXX DESIGN WIND PRESSURE IAW FLA		
- XXX RESIDENTIAL CODE, SECTION R301		
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.		

GENERAL NOTES		
1. PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.		
2. VENT DRYER THRU ROOF.		
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.		
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.		
5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.		
6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.		
 DENOTES CONC. BLOCK WALL HGT. @ 11'-4" AFF.		
7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS		
8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES		
9. ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2		
10. ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.		
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.		

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOORS NO LESS 1 3/8" IAW R302.5.1

WET BAR OPTION @ BONUS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" U.N.O. - VERIFY WITH COLOR SHEET.

UPPER FLOOR PLAN NOTES "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NAPA SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH


REVISIONS		BY
Engineering By: DBE and C		
MICHAEL A. THOMPSON		
PE 47509		
PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC.		
5200 Vineland Road, Suite 200		
Orlando, Florida 32811		
Phone: (407) 529 - 3000		
Park Square HOMES		
FLOOR PLAN W/ NOTES		
THE VALENCIA		
NAPA SERIES		
6375		
DATE 08-26-19		
SCALE AS NOTED		
DRAWN RDC		
JOB 6375		
SHEET 05D.0		
OF SHEETS		

LOAD INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
DEAD LOADS		
FLOOR: STRUCTURE	-----	1 PSF
CEILINGS	-----	3 PSF
MECH/ELEC	-----	5 PSF
PARTITIONS	-----	5 PSF
TOTAL	-----	20 PSF
ROOF: SHEATHING		
STRUCTURE	-----	5 PSF
CEILINGS	-----	1 PSF
MECH/ELEC	-----	3 PSF
TOTAL	-----	5 PSF
FLOOR LIVE LOADS	-----	20 PSF
RESIDENTIAL FLOOR:	-----	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	-----	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	-----	20 PSF
ROOMS OTHER THAN SLEEPING ROOM:	-----	40 PSF
SLEEPING ROOM:	-----	30 PSF
STAIR LIVE LOAD:	-----	40 PSF
BALCONIES:	-----	40 PSF
PASSENGER VEHICLE GARAGE:	-----	50 PSF
ROOF LIVE LOADS		
MINIMUM ROOF LIVE LOAD (PSF) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER		
ROOF SLOPE	0-200	201-600
0:12 < 4:12	20	16
≥ 4:12 < 12:12	16	14
≥ 12:12	12	12

WIND INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
1. BASIC WIND SPEED:	-----	140 MPH
2. RISK CATEGORY	-----	II
3. WIND EXPOSURE:	-----	B
4. BUILDING TYPE:	-----	V B
5. ENCLOSURE CLASSIFICATION -- +/- .18, INCLUDED INTERNAL PRESSURE	-----	IN NOTE #6
6. COMPONENT / CLADDING	-----	SEE PLAN DESIGN WIND PRESSURE:
+ XXX DESIGN WIND PRESSURE IAW FLA		
- XXX RESIDENTIAL CODE, SECTION R301		
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.		

GENERAL NOTES		
1. PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.		
2. VENT DRYER THRU ROOF.		
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.		
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.		
5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.		
6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.		
 DENOTES CONC. BLOCK WALL HGT. @ 11'-4" AFF.		
7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS		
8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES		
9. ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2		
10. ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.		
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.		

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOORS NO LESS 1 3/8" IAW R302.5.1




WET BAR OPTION @ BONUS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

UPPER FLOOR PLAN NOTES "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" U.N.O. - VERIFY WITH COLOR SHEET.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH


NAPA SERIES

Copyright 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and designs. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C		
MICHAEL A. THOMPSON		
PE 47509		
PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC.		
5200 Vineland Road, Suite 200		
Orlando, Florida 32811		
Phone: (407) 529 - 3000		
Park Square HOMES		
FLOOR PLAN W/ NOTES		
THE VALENCIA		
NAPA SERIES		
6375		
DATE 08-26-19		
SCALE AS NOTED		
DRAWN RDC		
JOB 6375		
SHEET 05F.0		
OF SHEETS		


EXTERIOR FINISH NOTES

- LATH TO BE ATTACHED IAW R103.11 OF THE 11TH EDITION, FBCR 2020
- PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.12 OF THE 11TH EDITION, FBCR 2020
- WEEP SCREED TO BE INSTALLED IAW R103.121 OF THE 11TH EDITION, FBCR 2020
- WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.13 OF THE 11TH EDITION, FBCR 2020
- 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



FRONT ELEVATION "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



REAR ELEVATION


1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NAPA SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
Park Square HOMES	
EXTERIOR ELEVATION "D" FRONT AND REAR	
THE VALENCIA	NAPA SERIES
6375	
DATE	08-26-19
SCALE	AS NOTED
DRAWN	RDC
JOB	6375
SHEET	06D.0
OF	SHEETS




EXTERIOR FINISH NOTES

1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020
2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020
4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020
5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



FRONT ELEVATION "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



REAR ELEVATION

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.



REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 528 - 3000		
THE VALENCIA		EXTERIOR ELEVATION "F" FRONT AND REAR
NAPA SERIES		
6375		
DATE 08-26-19		
SCALE AS NOTED		
DRAWN RDC		
JOB 6375		
SHEET 06F.0		
OF SHEETS		

- EXTERIOR FINISH NOTES
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 1TH EDITION, FBCR, 2020
 2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 1TH EDITION, FBCR, 2020
 3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 1TH EDITION, FBCR, 2020
 4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 1TH EDITION, FBCR, 2020
 5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.

EL. 20'-0 3/4" /PLT. HGT.
EL. 18'-8 3/4" /HDR. HGT.
EL. 11'-0 3/4" /2ND. FF.
EL. 9'-4" /PLT. HGT.
EL. 8'-0" /HDR. HGT.
EL. 0'-0" /FIN. FLR.
TEXTURED CEMENTITIOUS FINISH

RIGHT ELEVATION "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



LEFT ELEVATION "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 528 - 3000	
Park Square HOMES	
EXTERIOR ELEVATIONS "F" LEFT AND RIGHT	
THE VALENCIA	NAPA SERIES
6375	
DATE	08-26-19
SCALE	AS NOTED
DRAWN	RDC
JOB	6375
SHEET	07F.0
OF	SHEETS



OF SHEETS

**A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000**

**Park
Square
HOMES**

LEDGER SCHEDULE

L4

2X4 LEDGER BOARD CONTINUOUS
W/(2) LAG SCREWS @ EA. FLOOR TRUSS
OR 24"O.C. MAX

L6

2X6 LEDGER BOARD CONTINUOUS
W/(2) LAG SCREWS @ EA. FLOOR TRUSS
OR 24"O.C. MAX

L8

2X8 LEDGER BOARD CONTINUOUS
W/(2) LAG SCREWS @ EA. FLOOR TRUSS
OR 24"O.C. MAX

NOTES

1.

TYPICAL ROOF GABLE OVERHANG
TO BE 12" UNLESS OTHERWISE NOTED.

2.

TYPICAL ROOF EAVES OVERHANG
TO BE 12" UNLESS OTHERWISE NOTED.

3.

PROVIDE AND INSTALL FLASHING AND
ROOFING AS PER NATIONAL ROOFING
AND SHEET METAL ASSOC. STANDARDS
AND/ OR ACCEPTABLE INDUSTRY
PRACTICE AND IN ACCORDANCE WITH
THE 1TH EDITION (2020) FLORIDA
RESIDENTIAL CODE.

4.

ALL ROOF TRUSSES, GIRDERS, BEAMS,
HEADERS, ETC. TO BE SIZED BY TRUSS
MANUFACTURER OR FL. REG. ENG.

5.

TRUSSES SHALL BE BRACED TO PRE-
VENT ROTATION & PROVIDE LATERAL
STABILITY IN ACCORDANCE WITH THE
REQUIREMENTS SPECIFIED IN THE
CONSTRUCTION DOCUMENTS FOR
BUILDING & ON THE INDIVIDUAL TRUSS
DESIGN DRAWINGS. IN THE ABSENCE OF
SPECIFIC BRACING REQUIREMENTS,
TRUSSES SHALL BE BRACED IN
ACCORDANCE WITH TPI/WTCA BC91.1.

6.

REFER TO TRUSS MANUFACTURER'S
DRAWINGS FOR TRUSS PLACEMENT &
TRUSS TO TRUSS CONNECTIONS.


7.

TILE ROOF: UNDERLAYMENT TO BE
INSTALLED IAW FBCR 2020,
7TH EDITION R905.3.3.
Underlayment materials required to
comply with ASTM D226, D1970, D4869
and D6757 shall bear a label indicating
compliance to the standard designation
and, if applicable, type classification
indicated in Table R905.1.1. Underlayment
shall be applied and attached in
accordance with Table R905.1.1.

8.

OFF RIDGE VENTS MAXIMUM OPENING
SIZES :
• O-HAGIN - 1' X 19" HOLE

TRUSS LAYOUT "D"
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

TRUSS LAYOUT "D"

Park Square HOMES

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET 11D.0


OF SHEETS

[L4]	2X4 LEDGER BOARD CONTINUOUS W(12) LAG SCREWS @ EA. FLOOR TRUSS OR 24"O.C. MAX
[L6]	2X6 LEDGER BOARD CONTINUOUS W(12) LAG SCREWS @ EA. FLOOR TRUSS OR 24"O.C. MAX
[L8]	2X8 LEDGER BOARD CONTINUOUS W(12) LAG SCREWS @ EA. FLOOR TRUSS OR 24"O.C. MAX

1. TYPICAL ROOF GABLE OVERHANG TO BE **12'** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12'** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 1TH EDITION (2020) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/UTCA BC51 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.

7. **TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 7TH EDITION R305.3.3.**
Underlayment materials required to comply with ASTM D226, D1910, D4869 and D6757 shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R305.1.1. Underlayment shall be applied and attached in accordance with Table R305.1.1.
8. **OFF RIDGE VENTS MAXIMUM OPENING SIZES :**
- O-HAGIN - 1' x 19" HOLE

1/8" = 1'-0" (11X17) 1/4" = 1'-0" (22X34)



Park Square HOMES

TRUSS LAYOUT "E"

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19

DRAWN RDC

JOB 6375

SHEET

11E.0

LEDGER SCHEDULE

L4

2X4 LEDGER BOARD CONTINUOUS
W/(2) LAG SCREWS @ EA. FLOOR TRUSS
OR 24"O.C. MAX

L6

2X6 LEDGER BOARD CONTINUOUS
W/(2) LAG SCREWS @ EA. FLOOR TRUSS
OR 24"O.C. MAX

L8

2X8 LEDGER BOARD CONTINUOUS
W/(2) LAG SCREWS @ EA. FLOOR TRUSS
OR 24"O.C. MAX

NOTES

1.

TYPICAL ROOF GABLE OVERHANG
TO BE 12" UNLESS OTHERWISE NOTED.

2.

TYPICAL ROOF EAVES OVERHANG
TO BE 12" UNLESS OTHERWISE NOTED.

3.

PROVIDE AND INSTALL FLASHING AND
ROOFING AS PER NATIONAL ROOFING
AND SHEET METAL ASSOC. STANDARDS
AND/ OR ACCEPTABLE INDUSTRY
PRACTICE AND IN ACCORDANCE WITH
THE 1TH EDITION (2020) FLORIDA
RESIDENTIAL CODE.

4.

ALL ROOF TRUSSES, GIRDERS, BEAMS,
HEADERS, ETC. TO BE SIZED BY TRUSS
MANUFACTURER OR FL. REG. ENG.

5.

TRUSSES SHALL BE BRACED TO PRE-
VENT ROTATION & PROVIDE LATERAL
STABILITY IN ACCORDANCE WITH THE
REQUIREMENTS SPECIFIED IN THE
CONSTRUCTION DOCUMENTS FOR
BUILDING & ON THE INDIVIDUAL TRUSS
DESIGN DRAWINGS. IN THE ABSENCE OF
SPECIFIC BRACING REQUIREMENTS,
TRUSSES SHALL BE BRACED IN
ACCORDANCE WITH TPI/WTCA BC61 1.

6.


REFER TO TRUSS MANUFACTURER'S
DRAWINGS FOR TRUSS PLACEMENT &
TRUSS TO TRUSS CONNECTIONS.

7.

TILE ROOF: UNDERLAYMENT TO BE
INSTALLED IAW FBCR 2020,
1TH EDITION R305.3.3.
Underlayment materials required to
comply with ASTM D226, D1970, D4869
and D6757 shall bear a label indicating
compliance to the standard designation
and, if applicable, type classification
indicated in Table R305.1.1. Underlayment
shall be applied and attached in
accordance with Table R305.1.1.

8.

OFF RIDGE VENTS MAXIMUM OPENING
SIZES :
• O-HAGIN - 1' X 19" HOLE



TRUSS LAYOUT "F"
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NAPA SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

TRUSS LAYOUT "E"

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET 11F.0

OF SHEETS

PER FBC2020 7TH EDITION R806: MIN. 40% - MAX. 50%
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF
ATTIC SPACE AND THE BALANCE TO BE IN LOWER
PORTION (EAVES).

TOTAL VENTED SPACE: $\frac{3,559 \text{ S.F.}}{300} = \underline{11.87 \text{ S.F.}}$ NET FREE VENT.
REQUIRED

UPPER PORTION VENTILATION TOTAL:----- **544 S.F.**
 PROVIDED W/OFF RIDGE VENTS: **8** VENTS @ **.68 S.F. /VENT.**
 (VENT TYPE: O'HAGIN MODEL 'S')

LOWER PORTION VENTILATION TOTAL:----- 25.83 S.F.
 PROVIDED W/ VENTILATED SOFFITS @ EAVE:
 (297 L.F. @ .087 S.F. VENTING PER L.F.)


UPPER PORTION PERCENTAGE:	46%
LOWER PORTION PERCENTAGE:	54%

1. TYPICAL ROOF GABLE OVERHANG
TO BE **12"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG
TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND
ROOFING AS PER NATIONAL ROOFING
AND SHEET METAL ASSOC. STANDARDS
AND/ OR ACCEPTABLE INDUSTRY
PRACTICE AND IN ACCORDANCE WITH
THE 1TH EDITION (2020) FLORIDA
RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS,
HEADERS, ETC. TO BE SIZED BY TRUSS
MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PRE-
VENT ROTATION & PROVIDE LATERAL
STABILITY IN ACCORDANCE WITH THE
REQUIREMENTS SPECIFIED IN THE
CONSTRUCTION DOCUMENTS FOR
BUILDING & ON THE INDIVIDUAL TRUSS
DESIGN DRAWINGS. IN THE ABSENCE OF
SPECIFIC BRACING REQUIREMENTS,
TRUSSES SHALL BE BRACED IN
ACCORDANCE WITH TPI/WTCA BC91.1.
6. REFER TO TRUSS MANUFACTURER'S
DRAWINGS FOR TRUSS PLACEMENT &
TRUSS TO TRUSS CONNECTIONS.

7. **TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 7TH EDITION R305.3.3.**
Underlayment materials required to comply with ASTM D226, D1910, D4869 and D6157 shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R305.1.1. Underlayment shall be applied and attached in accordance with Table R305.1.1.

8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :

- O-HAGIN - 7" X 19" HOLE



UPPER TRUSS LAYOUT "D"

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

NAPA SERIES

REVISIONS	BY

Engineering By:
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

**A DIVISION OF PARK SQUARE
ENTERPRISES, INC.**
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

**Park
Square
HOMES**

UPPER TRUSS LAYOUT "D"

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET

12D.0

OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH


PER FBC2020 7TH EDITION R806: MIN. 40% - MAX. 50%
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF
ATTIC SPACE AND THE BALANCE TO BE IN LOWER
PORTION (EAVES).

TOTAL VENTED SPACE: $\frac{3559 \text{ S.F.}}{300} = \frac{11.87 \text{ S.F.}}{\text{REQUIRED}}$ NET FREE VENT.

LOWER PORTION VENTILATION TOTAL: ----- 25.83 S.F.
 PROVIDED W/ VENTILATED SOFFITS @ EAVE:
 (297 L.F. @ .087 S.F. VENTING PER L.F.)

UPPER PORTION PERCENTAGE:	<u>46%</u>
LOWER PORTION PERCENTAGE:	<u>54%</u>

1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 11TH EDITION (2020) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC51 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R905.3.3.
Underlayment materials required to comply with ASTM D226, D1910, D4869 and D6751 shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
 - O-HAGIN - 7" X 19" HOLE



UPPER TRUSS LAYOUT "E"

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

These are not to be copied from Park Square Homes.

REVISIONS	BY

Engineering By:
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

**A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000**

Park Square HOMES

UPPER TRUSS LAYOUT "E"

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19

SALE AS NOTED

RAWN RDC

3 6375

EET

2E.0

SHEETS

PER FBC2020 7TH EDITION R806: MIN. 40% - MAX. 50%
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF
ATTIC SPACE AND THE BALANCE TO BE IN LOWER
PORTION (EAVES).


TOTAL VENTED SPACE: $\frac{3,559 \text{ S.F.}}{300} = \frac{11.87 \text{ S.F.}}{\text{REQUIRED}}$ NET FREE VENT.

LOWER PORTION VENTILATION TOTAL:----- 25.83 S.F.
 PROVIDED W/ VENTILATED SOFFITS @ EAVE:
 (297 L.F. @ .087 S.F. VENTING PER L.F.)

NOTES

1. TYPICAL ROOF GABLE OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 11TH EDITION (2020) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC91 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R905.3.3.
Underlayment materials required to comply with ASTM D226, D1970, D4869 and D6757 shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
 - O-HAGIN - 1" X 19" HOLE

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NAPA SERIES

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19


SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET


12F.3
OF SHEETS



CAST CRETE / LOTTS / WEKIWA / FLORIDA ROCK PRE CAST LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F34-1B/1T	GARAGE DOOR
L-2	9'-4"	8F34-1B/1T	GARAGE DOOR
L-3	4'-6"	8F12-0B/1T	3/0X1/0 F.G.
L-4	4'-6"	8F16-0B/1T	SH25
L-5	4'-6"	8F16-0B/1T	SH25
L-6	4'-6"	8F12-0B/1T	3/0X1/0 F.G.
L-7	4'-4"	8RF12-0B/1T	2600 1-LITE DR.
L-8	11'-4"	8F16-0B/1T	(3) SH25
L-9			
L-10	13'-4"	8F16-0B/1T	12/0XB/0 S.G.D.
L-11			
L-12	7'-6"	8F16-0B/1T	FR. SH25
L-13	5'-4"	8F8-0B/1T	4/0X1/0 F.G.
L-14	5'-4"	8F8-0B/1T	4/0X1/0 F.G.
L-15	4'-6"	8F16-0B/1T	SH25
L-16	4'-6"	8F16-0B/1T	SH25
L-17	5'-10"	8RF12-0B/1T	FRONT DOOR
L-18	6'-8"	8F40-1B/1T	FRONT ENTRY
L-19	7'-4"	8F40-1B/1T	FRONT ENTRY
L-20	7'-4"	8F40-1B/1T	FRONT ENTRY
L-21	6'-8"	8F40-1B/1T	FRONT ENTRY
L-22	4'-6"	8F16-0B/1T	SH25
L-23	18'-8"	8F24-1B/1T	GARAGE ENTRY
L-24	10'-6"	8F24-0B/1T	GARAGE ENTRY
L-25			
L-26			
L-27			
L-28			
L-29			
L-30			
L-31			
L-32	15'-0"	8F16-1B/1T	REAR LANAI
L-33	15'-4"	8F16-1B/1T	REAR LANAI
L-34	16'-0"	8F16-1B/1T	REAR LANAI
L-35	8'-8"	8F16-1B/1T	REAR LANAI
L-36			
L-37			
L-38			
L-39			
L-40			

PRE CAST LINTEL LAYOUT "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
PRE CAST LINTEL LAYOUT		
THE VALENCIA	NAPA SERIES	
6375		
DATE	08-26-19	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	6375	
SHEET	13D.0	
OF	9 SHEETS	




BLOCK WALL HT. TRANSITION DETAIL

CAST CRETE / LOTTS / WEKIWA / FLORIDA ROCK PRE CAST LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F34-1B/1T	GARAGE DOOR
L-2	9'-4"	8F34-1B/1T	GARAGE DOOR
L-3	4'-6"	8F12-0B/1T	3/0X1/0 F.G.
L-4	4'-6"	8F16-0B/1T	SH25
L-5	4'-6"	8F16-0B/1T	SH25
L-6	4'-6"	8F12-0B/1T	3/0X1/0 F.G.
L-7	4'-4"	8RF12-0B/1T	2600 1-LITE DR.
L-8	11'-4"	8F16-0B/1T	(3) SH25
L-9			
L-10	13'-4"	8F16-0B/1T	12/0XB/0 S.G.D.
L-11			
L-12	7'-6"	8F16-0B/1T	FR SH25
L-13	5'-4"	8F8-0B/1T	4/0X1/0 F.G.
L-14	5'-4"	8F8-0B/1T	4/0X1/0 F.G.
L-15	4'-6"	8F16-0B/1T	SH25
L-16	4'-6"	8F16-0B/1T	SH25
L-17	5'-10"	8RF12-0B/1T	FRONT DOOR
L-18	6'-8"	8F40-1B/1T	FRONT ENTRY
L-19	7'-4"	8F40-1B/1T	FRONT ENTRY
L-20	7'-4"	8F40-1B/1T	FRONT ENTRY
L-21	6'-8"	8F40-1B/1T	FRONT ENTRY
L-22	4'-6"	8F16-0B/1T	SH25
L-23	18'-8"	8F24-1B/1T	GARAGE ENTRY
L-24	10'-6"	8F24-0B/1T	GARAGE ENTRY
L-25			
L-26			
L-27			
L-28			
L-29			
L-30			
L-31			
L-32	15'-0"	8F16-1B/1T	REAR LANAI
L-33	15'-4"	8F16-1B/1T	REAR LANAI
L-34	16'-0"	8F16-1B/1T	REAR LANAI
L-35	8'-8"	8F16-1B/1T	REAR LANAI
L-36			
L-37			
L-38			
L-39			
L-40			

PRE CAST LINTEL LAYOUT "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES



© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
PRE CAST LINTEL LAYOUT		
THE VALENCIA	NAPA SERIES	
6375		
DATE 08-26-19		
SCALE AS NOTED		
DRAWN RDC		
JOB 6375		
SHEET		
13E.0		
OF SHEETS		

CAST CRETE / LOTTS / WEKIWA / FLORIDA ROCK PRE CAST LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F34-1B/1T	GARAGE DOOR
L-2	9'-4"	8F34-1B/1T	GARAGE DOOR
L-3	4'-6"	8F12-0B/1T	3/0X1/0 F.G.
L-4	4'-6"	8F16-0B/1T	SH25
L-5	4'-6"	8F16-0B/1T	SH25
L-6	4'-6"	8F12-0B/1T	3/0X1/0 F.G.
L-7	4'-4"	8RF12-0B/1T	2600 1-LITE DR.
L-8	11'-4"	8F16-0B/1T	(3) SH25
L-9			
L-10	13'-4"	8F16-0B/1T	12/0XB/0 S.G.D.
L-11			
L-12	7'-6"	8F16-0B/1T	FR SH25
L-13	5'-4"	8F8-0B/1T	4/0X1/0 F.G.
L-14	5'-4"	8F8-0B/1T	4/0X1/0 F.G.
L-15	4'-6"	8F16-0B/1T	SH25
L-16	4'-6"	8F16-0B/1T	SH25
L-17	5'-10"	8RF12-0B/1T	FRONT DOOR
L-18	6'-8"	8F40-1B/1T	FRONT ENTRY
L-19	7'-4"	8F40-1B/1T	FRONT ENTRY
L-20	7'-4"	8F40-1B/1T	FRONT ENTRY
L-21	6'-8"	8F40-1B/1T	FRONT ENTRY
L-22	4'-6"	8F16-0B/1T	SH25
L-23	18'-8"	8F24-1B/1T	GARAGE ENTRY
L-24	10'-6"	8F24-0B/1T	GARAGE ENTRY
L-25			
L-26			
L-27			
L-28			
L-29			
L-30			
L-31			
L-32	15'-0"	8F16-1B/1T	REAR LANAI
L-33	15'-4"	8F16-1B/1T	REAR LANAI
L-34	16'-0"	8F16-1B/1T	REAR LANAI
L-35	8'-8"	8F16-1B/1T	REAR LANAI
L-36			
L-37			
L-38			
L-39			
L-40			

PRE CAST LINTEL LAYOUT "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH


NAPA SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.


REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
PRE CAST LINTEL LAYOUT		
THE VALENCIA	NAPA SERIES	
6375	DATE 08-26-19	
	SCALE AS NOTED	
	DRAWN RDC	
	JOB 6375	
	SHEET 13F.0	
	OF 9 SHEETS	




4
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




3
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




2
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34) (BRG. W/O UPLIFT)




1
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34) (BRG. W/ UPLIFT)




10
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




8
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




6
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




38
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




11
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



9
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



7
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



5
14
1/2"=1'-0" (11X17) 1"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

Engineering By:
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park
Square
HOMES

TYPICAL DETAILS

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19


SCALE AS NOTED

DRAWN RDC


JOB 6375

SHEET

14
OF SHEETS



4
15 TYP. STAIR CONNECT.
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34") PLATFORM FRAMING



5
15 TYP. HANDRAIL DET.
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34")

NOTES:
STAIRWAY CONSTRUCTION TO CONFORM TO FBCR 2020, 7TH EDITION SECTION R311.7


MAX. HGT. OF RISER TO BE 7 3/4"
MIN. WIDTH OF TREAD TO BE 9" (EXCLUSIVE OF NOSING)
ALL TREADS LESS THAN 10" IN WIDTH SHALL HAVE APPROX. 1" OF NOSING
3/16" MAX. VARIATION IN RISERS/TREADS ADJACENT TO EACH OTHER
3/8" MAX. VARIATION IN ANY RISER/TREAD

HAND RAIL CIRCULAR CROSS SECTION DIA. TO BE 1 1/4" - 2" OR TO PROVIDE EQUIVALENT GRASPABILITY.


WINDERS: MIN. 6" WIDE @ NARROW END

34" MIN.-38" MAX., HANDRAIL HGT.


HEADROOM CLEARANCE MIN. 6'-8"



1
15 STAIR DETAIL
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34") STAIR DATA



2
15 TYP. STAIR CONNECT.
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34") STRINGER TO FLOOR TRUSS



3
15 TYP. STAIR CONNECT.
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34") STRINGER TO FLOOR

CONNECTOR SCHEDULE						
CONNECT. TYPE	SIMPSON		USP		MAX. UPLIFT	LAT. LDS. FI / F2
	DESCRIPTION	FASTENERS PER CONNECTOR	DESCRIPTION	FASTENERS PER CONNECTOR		
4	HETA20	14-10d x 1 1/2"	ETA20	14-10d	1,810	65 / 960
5	DETA20	18-10d x 1 1/2"	N/A	N/A	2,480	2000 / 1370
20	H3	RFT: 4-8d / PLT: 4-8d	RT3	RFT: 4-8d / PLT: 4-8d	455	125 / 160
21	H1	RFT: 6-8dx1 1/2" / PLT: 4-8d	RT15	RFT: 5-8dx1 1/2" / PLT: 5-8d	475	485 / 165
22	H10A	RFT: (9) 10d x 1 1/2"	RT16	RFT: 8-8d x 1 1/2"	990	585 / 525
		PLT: (9) 10d x 1 1/2"		PLT: 8-8d		
23	LUS26	HDR: 4-10d / JST: 4-10d	JUS26	HDR: 4-10d / JST: 4-10d	935	N/A
24	H7Z	RFT / TRS: (4) 8d PLT / STD: (2) 8dx 1 1/2" (8) 8d	RT20	RFT / TRS: 9-10d PLT / STD: 13-10d	985	400 / N/A
26	H25A	RFT: 5-8d / PLT: 5-8d		RFT: 5-8d / PLT: 5-8d		
34	A34	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	MP34	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	365	280 / 303
35	A35F	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	MPAIF	H: 6-8dx1 1/2" / P: 6-8dx1 1/2"	440	440 / N/A
37	MTS12	14-10d	MTW12	14-10d	1,000	N/A
38	MTS16	14-10d	MTW16	14-10d	1,000	N/A
43	LSTA12	10-10d	LSTA12	10-10d	905	N/A
45	ST18	14-16d	ST18	14-16d	1,200	N/A
47	LSTA24	18-10d	LSTA24	18-10d	1,295	N/A
71	MSTA36	26-10d	MSTA36	26-10d	2,135	N/A
72	MSTC66	64-16d SINKERS	N/A	N/A	5,495	N/A
79	SP1	STD: 6-10d / PLT: 4-10d	SPT22	STD: 4-10d / PLT: 4-10d	535	560 / 260
80	SP2	STD: 6-10d / PLT: 6-10d	SPT224	STD: 6-10d / PLT: 6-10d	605	560 / 260
81	SPH468	12-10d x 1 1/2"	TP46,48	12-10d x 1 1/2"	885	N/A
90	ABU66	12-16d	PAU66	12-16d	2,240	N/A
89	CB66	(2) 5/8" BOLTS	PA8X8	4-10d	2,300	985
92	ABU44	12-16d	PAU44	12-16d	2,200	N/A
93	AC6 (MAX)	28-16d	PB666	24-16d	1,815	1,070
94	AC4 (MAX)	28-16d	PB644	24-16d	1,815	1,070
95	HTS20	20-10d	HTW20	20-10d	1,450	N/A
96	HD8A	SILL: 7/8" BOLT STUD: (3) 7/8"x5 1/2" BOLTS	HH8A	SILL: 7/8" BOLT STUD: (3) 7/8"x5 1/2" BOLTS	7,910	N/A
99	A35	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	MPA1	H: 6-8dx1 1/2" / P: 6-8dx1 1/2"	440	440 / N/A
98-101	HTT4	5/8" BOLT / 18-16dx2 1/2"	N/A	N/A	3,640	N/A
97-100-102	HTT5	5/8" BOLT / 26-10d	N/A	N/A	4,275	N/A
103	VGTR/L	32-9DS 1/4" X 3" / (2) 5/8" BLT	N/A	N/A	3,990	N/A
104	HDS8-SDS25	7/8" BLT / 20-9DS 1/4" X 2 1/2"	N/A	N/A	5,020	N/A
110	HCF2	12-10d x 1 1/2"	HHCF2	20-10d x 1 1/2"	520	260 / N/A
167	HHUS46	H: 14-16d / J: 6-16d	THD46	H: 8-18d / J: 12-10d	1,550	N/A
168	U46	H: 8-10d / J: 4-10d	SHU46	H: 8-16d / J: 4-16d	710	N/A
181	HUS26	20-16d	THD26	H: 20-16d / J: 10-10d	1,550	N/A
184	HHUS28-2	G: 28-16d / T: 8-16d	EHU28-2	12-16d	2,000	N/A
214	HUC212-3TF	HD: 18-3/16"x1 1/2" TAPCON BM: 6-16d	HDO212-3	HD: 18-3/16"x1 1/2" TAPCON BM: 6-10d	1,135	N/A
215	HGS210-2	HDR: 46-16d / JST: 10-16d	EHU210-2	HDR: 40-16d / JST: 16-10d	2,720	N/A
216	HUS412	BLOCK: 10-1/4"x1 1/2" TC JOIST: 10-16d	HUS412	BLOCK: 10-1/4"x1 1/2" TC JOIST: 10-16d	3,240	N/A
217	HUS212-2	BLOCK: 10-1/4"x1 1/2" TC JOIST: 10-16d	HUS212-2	BLOCK: 10-1/4"x1 1/2" TC JOIST: 10-16d	2,630	N/A
219	MBHA412	H: 1-ATR 3/4" X 8 TOP & FACE JOIST: 18-10d	NFM35X12U	H: 1-1/2" J-BOLT J: 5-1/2" BOLTS	3,145	N/A
220	N/A	N/A	NFM 3X12	BLK: 1/2" x J / JST: 14-10d	1,620	N/A
226	MBHA4.75/12	HDR: (2) 3/4" x 8" JOIST: 18-10d	NFM45U	HDR: MIN. 1/2" x J-BOLT JOIST: (5) 1/2" x BOLTS	2,160	N/A
231	MBHA3.56/16	HDR: (2) 3/4" x 8" JOIST: 18-10d	NFM3.5X16U	HDR: MIN. 1/2" x J-BOLTS JOIST: (5) 1/2" x BOLTS	3,450	N/A
232	MBHA5.50/16	HDR: (2) 3/4" x 8" JOIST: 18-10d	NFM5.5X16U	HDR: MIN. 1/2" x J-BOLTS JOIST: (5) 1/2" x BOLTS	3,450	N/A
240	H15	R: 4-10dx1 1/2" / P: 4-10dx1 1/2"	N/A	N/A	1,300	480 / N/A
241	LGT2	30-16d-sinker	LUGT2	32-10d	2,000	1015 / 440
301	MGT	(1) 3/4" BLTS / GIR: 22-10d	N/A	N/A	3,965	N/A
302	HGT-2 or 3	LTL: 3/4" BLTS / GIR: 8-10d	USC63	LTL: 3/4" BLTS / GIR: 8-16d	6,485	N/A
303	HGT-4	LTL: 3/4" BLTS / GIR: 16-10d	N/A	N/A	9,250	N/A
401	SUR/L414	FACE: 18-16d / JST: 8-16d	N/A	N/A	1,700	N/A
T	CONNECTORS TO BE SPECIFIED AND PROVIDED BY TRUSS MANUFACTURERS					

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and designs. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS

BY

Engineering By:
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

TYPICAL DETAILS /
CONNECTOR SCHEDULE

THE VALENCIA
NAPA SERIES

6375

DATE 08-26-19


SCALE AS NOTED

DRAWN RDC

JOB 6375


SHEET 15

OF SHEETS




5 DETAIL

1/2"=1'-0" (11X17) 1"=1'-0" (22X34')




3 DETAIL

1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




6 DETAIL

1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




4 DETAIL

1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



2 DETAIL

3/4"=1'-0" (11X17) 1/2"=1'-0" (22X34)



1 DETAIL

3/4"=1'-0" (11X17) 1/2"=1'-0" (22X34)

NAPA SERIES

Engineering By
DBE and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

Park Square
HOMES

TYPICAL DETAILS

THE VALENCIA

NAPA SERIES

6375

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET

16

OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.


SAFE LOAD TABLES FOR GRAVITY, UPLIFT & LATERAL LOADS

8" PRECAST & PRESTRESSED U-LINTELS									
		GRAVITY							
LENGTH	TYPE	8F8-0B	8F12-0B	8F16-0B	8F20-0B	8F24-0B	8F28-0B	8F32-0B	8F36-0B
2'-10" (34')	PRECAST	2302	3166	4473	6039	7526	9004	10472	11936
3'-6" (42')	PRECAST	2302	3166	4473	6039	7526	9004	10472	11936
4'-0" (48')	PRECAST	2029	2646	4473	6039	7526	9004	10472	11936
4'-6" (54')	PRECAST	1651	2170	4021	6039	7526	9004	10472	11936
5'-4" (64')	PRECAST	1184	1665	2889	5057	6039	7526	9004	10472
5'-10" (70')	PRECAST	972	1453	2464	4144	5458	6437	7526	8612
6'-6" (78')	PRECAST	937	1255	2101	3263	4144	5458	6437	7526
7'-6" (90')	PRECAST	167	1029	1675	2610	3393	4596	6613	8047
9'-4" (112')	PRECAST	973	168	122	188	2544	3469	4090	5127
10'-6" (126')	PRECAST	456	658	1025	1514	2081	2714	3150	3804
11'-4" (136')	PRECAST	445	598	935	1365	1854	2359	2793	3404
12'-0" (144')	PRECAST	414	545	864	1254	1699	2274	2714	3280
13'-4" (160')	PRECAST	362	427	726	1029	1331	1635	2224	2714
14'-0" (168')	PRECAST	338	381	648	975	1290	1627	2087	2540
14'-8" (176')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR
15'-4" (184')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR
17'-4" (208')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR
19'-4" (232')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR
21'-4" (256')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR
22'-0" (264')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR
24'-0" (288')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR

8" PRECAST W/ 2" RECESS DOOR U-LINTELS									
		GRAVITY							
LENGTH	TYPE	8F16-0B	8F20-0B	8F24-0B	8F28-0B	8F32-0B	8F36-0B	8F40-0B	8F44-0B
4'-4" (52')	PRECAST	1489	1971	3402	4982	6472	7947	9416	10878
4'-6" (54')	PRECAST	1351	1702	3402	4982	6472	7947	9416	10878
5'-8" (68')	PRECAST	785	832	1602	1550	2098	2566	3075	3585
5'-10" (70')	PRECAST	735	779	1500	1449	1924	2400	2876	3352
6'-8" (80')	PRECAST	822	907	1677	2933	4100	6130	8177	10207
7'-6" (90')	PRECAST	665	761	1377	2252	3958	5491	7344	9339
9'-8" (116')	PRECAST	371	420	834	1293	1071	1342	1614	1886

8" PRECAST & PRESTRESSED U-LINTELS									
		UPLIFT						LATERAL	
LENGTH	TYPE	8F8-1T	8F12-1T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1T	8F36-1T
2'-10" (34')	PRECAST	2121	2818	4101	5332	6569	7811	9059	2021
3'-6" (42')	PRECAST	2121	2784	3981	5190	6407	7630	8857	1291
4'-0" (48')	PRECAST	1878	2165	3165	4125	5091	6061	7036	938
4'-6" (54')	PRECAST	1660	1878	2832	3680	4532	5387	6245	127
5'-4" (64')	PRECAST	1393	1431	2050	2610	3293	3920	4549	505
5'-10" (70')	PRECAST	1272	1351	1930	2505	3084	3665	4247	418
6'-6" (78')	PRECAST	1141	1200	1733	2250	2769	3290	3812	107
7'-6" (90')	PRECAST	959	992	1475	184	2354	2791	3240	591
9'-4" (112')	PRECAST	807	807	112	188	2544	3469	4090	454
10'-6" (126')	PRECAST	716	611	1039	1389	1711	2034	2358	396
11'-4" (136')	PRECAST	666	635	905	1235	1595	1956	2318	363
12'-0" (144')	PRECAST	607	400	631	916	1201	1486	1772	340
13'-4" (160')	PRECAST	500	340	532	686	841	997	1153	302
14'-0" (168')	PRECAST	458	316	493	635	778	922	1065	286
14'-8" (176')	PRESTRESSED	243	352	582	852	1156	1491	1742	NR
15'-4" (184')	PRESTRESSED	228	278	430	553	677	801	925	NR
17'-4" (208')	PRESTRESSED	188	236	361	464	567	670	774	NR
19'-4" (232')	PRESTRESSED	165	216	344	449	554	659	764	NR
21'-4" (256')	PRESTRESSED	145	186	278	356	433	512	590	NR
22'-0" (264')	PRESTRESSED	142	172	236	314	391	469	547	NR
24'-0" (288')	PRESTRESSED	127	165	244	312	380	447	515	NR

*REDUCE VALUE BY 25% FOR GRADE 40 FIELD REBAR



MATERIALS

1. f'c precast lintels = 3500 psi.
2. f'c prestressed lintels = 6000 psi.
3. f'c grout = 3000 psi w/ maximum 3/8" aggregate.
4. Concrete masonry units (CMU) per ASTM C90 w/ minimum net area compressive strength = 1900 psi.
5. Rebar provided in precast lintel per ASTM A615 GR60. Field rebar per ASTM A615 GR40 or GR60.
6. Prestressing strand per ASTM A416 grade 270 low relaxation.

7. 1/32 wire per ASTM A510.
8. Mortar per ASTM C270 type M or S.

GENERAL NOTES


1. Provide full mortar head and bed joints.
2. Shore filled lintels as required.
3. Installation of lintel must comply with the architectural and/or structural drawings.
4. Lintels are manufactured with 5-1/2' long notches at the ends to accommodate vertical cell reinforcing and grouting.
5. All lintels meet or exceed L/360 vertical deflection, except lintels 17'-4" and longer with a nominal height of 8' meet or exceed L/180.
6. Bottom field added rebar to be located at the bottom of the lintel cavity.
7. 1/32" diameter wire stirrups are welded to the bottom steel for mechanical anchorage.
8. Cast-in-place concrete may be provided in composite lintel in lieu of concrete masonry units.
9. Safe load ratings based on rational design analysis per ACI 318 and ACI 530

SAFE LOAD TABLE NOTES

1. All values based on minimum 4" bearing. Exception: Safe loads for unfilled lintels must be reduced by 20% if bearing length is less than 6-1/2". Safe loads for all recessed lintels based on 8" nominal bearing.
2. N.R. = Not Rated.
3. Safe loads are total superimposed allowable load on the section specified.
4. Safe loads based on grade 40 or grade 60 field rebar.
5. Additional lateral load capacity can be obtained by the designer by providing additional reinforced masonry above the precast lintel.
6. One #1 rebar may be substituted for two #5 rebars in 8" lintels only.
7. The designer may evaluate concentrated loads from the safe load tables by calculating the maximum resisting moment and shear at d-away from the face of support.
8. For composite lintel heights not shown, use safe load from next lower height.
9. All safe loads in units of pounds per linear foot.


8" PRECAST W/ 2" RECESS DOOR U-LINTELS									
		UPLIFT						LATERAL	
LENGTH	TYPE	8F8-1T	8F12-1T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1T	8F36-1T
4'-4" (52')	PRECAST	1244	1573	2413	3260	412	4967	5825	932
4'-6" (54')	PRECAST	1192	1507	2311	3121	3937	4756	5577	853
5'-8" (68')	PRECAST	924	1172	1785	2423	3055	3689	4325	501
5'-10" (70')	PRECAST	896	1099	1690	2288	2891	3497	4106	469
6'-8" (80')	PRECAST	778	882	1513	2042	2573	3107	3642	830
7'-6" (90')	PRECAST	688	697	1325	1810	2280	2753	3227	710
9'-8" (116')	PRECAST	533	433	808	1123	1413	1704	1995	516

*REDUCE VALUE BY 25% FOR GRADE 40 FIELD REBAR




DETAIL

- 1/2"=1'-0" (11X17) 1"=1'-0" (22X34")




DETAIL

- 1/2"=1'-0" (11X17) 1"=1'-0" (22X34")



DETAIL

- 1/2"=1'-0" (11X17) 1"=1'-0" (22X34")



DETAIL

- 1/2"=1'-0" (11X17) 1"=1'-0" (22X34")

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

NAPA SERIES

Engineering By
D&E and C
MICHAEL A. THOMPSON
PE 47509
PHONE 407-721-2292

A DIVISION OF PARK SQUARE
ENTERPRISES, INC.
5200 Vineland Road, Suite 200
Orlando, Florida 32811
Phone: (407) 529 - 3000

PRE CAST LINTEL DATA /

STRUCTURAL DETAILS

DATE 08-26-19

SCALE AS NOTED

DRAWN RDC

JOB 6375

SHEET 17

OF SHEETS