

4073 (D,E,F)

THE REDWOOD

THE PARK SERIES

D (50' X 70') E (50' X 70') F (50' X 70'4")

SHEET INDEX: 'D'

- 00 COVER SHEET
- 01D.0 FOUNDATION PLAN
- 01D.1 FOUNDATION PLAN-SUPER BONUS
- 02D.0 FLOOR PLAN W/ DIMENSIONS
- 02D.1 FLOOR PLAN W/ DIMENSIONS-SUPER BONUS
- 03D.0 FLOOR PLAN W/ NOTES
- 03D.1 FLOOR PLAN W/ NOTES-SUPER BONUS
- 04D.0 UPPER FLOOR PLAN W/ DIMENSIONS
- 04D.1 UPPER FLOOR PLAN W/ DIMENS.-SUPER BONUS
- 04D.2 UPPER FLOOR PLAN W/ DIMENS.-BDRM 7/BATH 6 /LOFT
- 05D.0 UPPER FLOOR PLAN W/ NOTES
- 05D.1 UPPER FLOOR PLAN W/ NOTES-SUPER BONUS
- 05D.2 UPPER FLOOR PLAN W/ NOTES-BDRM 7/BATH 6/LOFT
- 06D.0 EXT. ELEV.-FRONT & REAR
- 06D.1 EXT. ELEV.-FRONT & REAR-SUPER BONUS
- 07D.0 EXT. ELEV.-LEFT AND RIGHT
- 07D.1 EXT. ELEV.-LEFT AND RIGHT-SUPER BONUS
- 08.0 INTERIOR ELEVATIONS
- 08.1 CROSS SECTION/ STAIR SECTION
- 09.0 ELECTRICAL PLAN
- 10.0 UPPER ELECTRICAL PLAN
- 10.1 UPPER ELECTRICAL PLAN-SUPER BONUS
- 10.2 UPPER ELECTRICAL PLAN-BDRM 7/ BATH 6/LOFT
- 11D.0 TRUSS LAYOUT- ELEV.
- 11D.1 TRUSS LAYOUT- ELEV.-SUPER BONUS
- 11D.2 TRUSS LAYOUT- ELEV.-BDRM 7/BATH 6/LOFT
- 12D.0 UPPER TRUSS LAYOUT- ELEV.
- 12D.1 UPPER TRUSS LAYOUT- ELEV.-SUPER BONUS
- 13D.0 PRE CAST LINTEL LAYOUT-ELEV.
- 14 PRE CAST LINTEL DATA/ CONNECTOR SCHEDULE
- 15 TYPICAL DETAILS
- 16 TYPICAL DETAILS
- 17 TYPICAL DETAILS
- 18 TYPICAL DETAILS
- 19.1 OPTIONS-GOURMET KITCHEN
- LO1 LIGHTING OPTIONS-FIRST FLOOR
- LO2.0 LIGHTING OPTIONS-UPPER FLOOR
- LO2.1 LIGHTING OPTIONS-UPPER FLOOR-SUPER BONUS
- LO2.2 LIGHTING OPTIONS-UPPER FLOOR-BDRM 7/ BATH 6/LOFT
- D1 TYPICAL STRUCTURAL DETAILS
- D2 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 TYPICAL STRUCTURAL DETAILS
- D5 TYPICAL STRUCTURAL DETAILS

SHEET INDEX: 'E'

- 00 COVER SHEET
- 01E.0 FOUNDATION PLAN
- 01E.1 FOUNDATION PLAN-SUPER BONUS
- 02E.0 FLOOR PLAN W/ DIMENSIONS
- 02E.1 FLOOR PLAN W/ DIMENSIONS-SUPER BONUS
- 03E.0 FLOOR PLAN W/ NOTES
- 03E.1 FLOOR PLAN W/ NOTES-SUPER BONUS
- 04E.0 UPPER FLOOR PLAN W/ DIMENSIONS
- 04E.1 UPPER FLOOR PLAN W/ DIMENS.-SUPER BONUS
- 04E.2 UPPER FLOOR PLAN W/ DIMENS.-BDRM 7/BATH 6 /LOFT
- 05E.0 UPPER FLOOR PLAN W/ NOTES
- 05E.1 UPPER FLOOR PLAN W/ NOTES-SUPER BONUS
- 05E.2 UPPER FLOOR PLAN W/ NOTES-BDRM 7/BATH 6/LOFT
- 06E.0 EXT. ELEV.-FRONT & REAR
- 06E.1 EXT. ELEV.-FRONT & REAR-SUPER BONUS
- 07E.0 EXT. ELEV.-LEFT AND RIGHT
- 07E.1 EXT. ELEV.-LEFT AND RIGHT-SUPER BONUS
- 08.0 INTERIOR ELEVATIONS
- 08.1 CROSS SECTION/ STAIR SECTION
- 09.0 ELECTRICAL PLAN
- 10.0 UPPER ELECTRICAL PLAN
- 10.1 UPPER ELECTRICAL PLAN-SUPER BONUS
- 10.2 UPPER ELECTRICAL PLAN-BDRM 7/ BATH 6/LOFT
- 11E.0 TRUSS LAYOUT- ELEV.
- 11E.1 TRUSS LAYOUT- ELEV.-SUPER BONUS
- 11E.2 TRUSS LAYOUT- ELEV.-BDRM 7/BATH 6/LOFT
- 12E.0 UPPER TRUSS LAYOUT- ELEV.
- 12E.1 UPPER TRUSS LAYOUT- ELEV.-SUPER BONUS
- 13E.0 PRE CAST LINTEL LAYOUT-ELEV.
- 14 PRE CAST LINTEL DATA/ CONNECTOR SCHEDULE
- 15 TYPICAL DETAILS
- 16 TYPICAL DETAILS
- 17 TYPICAL DETAILS
- 18 TYPICAL DETAILS
- 19.1 OPTIONS-GOURMET KITCHEN
- LO1 LIGHTING OPTIONS-FIRST FLOOR
- LO2.0 LIGHTING OPTIONS-UPPER FLOOR
- LO2.1 LIGHTING OPTIONS-UPPER FLOOR-SUPER BONUS
- LO2.2 LIGHTING OPTIONS-UPPER FLOOR-BDRM 7/ BATH 6/LOFT
- D1 TYPICAL STRUCTURAL DETAILS
- D2 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 TYPICAL STRUCTURAL DETAILS
- D5 TYPICAL STRUCTURAL DETAILS

SHEET INDEX: 'F'

- 00 COVER SHEET
- 01F.0 FOUNDATION PLAN
- 01F.1 FOUNDATION PLAN-SUPER BONUS
- 02F.0 FLOOR PLAN W/ DIMENSIONS
- 02F.1 FLOOR PLAN W/ DIMENSIONS-SUPER BONUS
- 03F.0 FLOOR PLAN W/ NOTES
- 03F.1 FLOOR PLAN W/ NOTES-SUPER BONUS
- 04F.0 UPPER FLOOR PLAN W/ DIMENSIONS
- 04F.1 UPPER FLOOR PLAN W/ DIMENS.-SUPER BONUS
- 04F.2 UPPER FLOOR PLAN W/ DIMENS.-BDRM 7/BATH 6 /LOFT
- 05F.0 UPPER FLOOR PLAN W/ NOTES
- 05F.1 UPPER FLOOR PLAN W/ NOTES-SUPER BONUS
- 05F.2 UPPER FLOOR PLAN W/ NOTES-BDRM 7/BATH 6/LOFT
- 06F.0 EXT. ELEV.-FRONT & REAR
- 06F.1 EXT. ELEV.-FRONT & REAR-SUPER BONUS
- 07F.0 EXT. ELEV.-LEFT AND RIGHT
- 07F.1 EXT. ELEV.-LEFT AND RIGHT-SUPER BONUS
- 08.0 INTERIOR ELEVATIONS
- 08.1 CROSS SECTION/ STAIR SECTION
- 09.0 ELECTRICAL PLAN
- 10.0 UPPER ELECTRICAL PLAN
- 10.1 UPPER ELECTRICAL PLAN-SUPER BONUS
- 10.2 UPPER ELECTRICAL PLAN-BDRM 7/ BATH 6/LOFT
- 11F.0 TRUSS LAYOUT- ELEV.
- 11F.1 TRUSS LAYOUT- ELEV.-SUPER BONUS
- 11F.2 TRUSS LAYOUT- ELEV.-BDRM 7/BATH 6/LOFT
- 12F.0 UPPER TRUSS LAYOUT- ELEV.
- 12F.1 UPPER TRUSS LAYOUT- ELEV.-SUPER BONUS
- 13F.0 PRE CAST LINTEL LAYOUT-ELEV.
- 14 PRE CAST LINTEL DATA/ CONNECTOR SCHEDULE
- 15 TYPICAL DETAILS
- 16 TYPICAL DETAILS
- 17 TYPICAL DETAILS
- 18 TYPICAL DETAILS
- 19.1 OPTIONS-GOURMET KITCHEN
- LO1 LIGHTING OPTIONS-FIRST FLOOR
- LO2.0 LIGHTING OPTIONS-UPPER FLOOR
- LO2.1 LIGHTING OPTIONS-UPPER FLOOR-SUPER BONUS
- LO2.2 LIGHTING OPTIONS-UPPER FLOOR-BDRM 7/ BATH 6/LOFT
- D1 TYPICAL STRUCTURAL DETAILS
- D2 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 TYPICAL STRUCTURAL DETAILS
- D5 TYPICAL STRUCTURAL DETAILS


REVISION SCHEDULE			
NO.	DATE	DESCRIPTION	BY
1	03-17-17	ADD OPTIONAL SINK IN BATH #2	MW
2	03-19-17	-CHG. HF. WALL @ 1ST. FLR. STAIRS TO STD. RAILING	RDC
		-CHG. CAFE WINDOWS TO STD. TRIPLE WINDOWS	
		-CHG. WINDOW @ M.B.A. W.C. TO 2'0"x2'0" F.G.	
		-DELETE HALF WALL AT FAMILY RM.	
		-ADD 1/6 BIFOLD TO LAUNDRY CHUTE	
		-DELETE WINDOW @ BEDROOM 3	
		-ADDED OPT. BR. 1/ BA. 6, LOFT/ OPT. MEDIA	
		-DROP CLG. IN PDR. TO 8'-8"	
		-RAISE HEADER AT DINING TO MATCH HGT. OF	
		HALF WALL ON SECOND FLOOR	
		-ADD WINDOW TO BEDROOM 5	
3	08-07-18	REPLACE ALL INTERIOR ARCH'S W/FLAT SOFFIT	MW
4	02-28-19	2017 CODE UPDATE - ELEV A	MW
6	07-21-21	-TRUSSES APPLIED FOR STD. 4 OPT. BR. 1 ON ELEV. D, E & F	JA
7	08-02-21	- REPLACE FLORESCENT LTS. W/ RECESS CANS ELEV. D, E & F	N
8	02-27-23	- REDESIGN LAUNDRY RM/LAUNDRY CHUTE CLOSET	MW

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
COVER SHEET		
4073		REDWOOD
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	00	
OF	SHEETS	




#### FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6x6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER. TERMITE TREATED SOIL WITH 006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WUF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. \*FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- ~~10 STANDARD FOOTING~~ NOT USED  
~~11 ALTERNATE FOOTING~~
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.482 FLORIDA BUILDING CODE.


#### S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



#### GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



#### BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




#### FOUNDATION

##### PLAN "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

#### TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

#### THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park  
Square  
HOMES

#### FOUNDATION PLAN

4073

REDWOOD

DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	01D.0
OF	SHEETS



# FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR. WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER. TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WUF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. \*FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- 16  
D2


1  
D2

16  
D2

1  
D2
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.482 FLORIDA BUILDING CODE.


## S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



## GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



## BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




## FOUNDATION PLAN "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

## TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

**THE PARK SERIES**

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
<b>Park Square HOMES</b>	
<b>FOUNDATION PLAN</b>	
<b>4073</b>	
<b>REDWOOD</b>	
DATE 05-15-21	
SCALE AS NOTED	
DRAWN RDC	
JOB N/A	
SHEET 01D.1	
OF SHEETS	

# FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR. WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER. TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WUF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. \*FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- 16

D2


 STANDARD FOOTING
- 1

D2

 ALTERNATE FOOTING
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.482 FLORIDA BUILDING CODE.


## S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




## GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



## BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




## FOUNDATION PLAN "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

## TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park  
Square  
HOMES


FOUNDATION PLAN

4073






REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 01E.0  
OF SHEETS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




## FOUNDATION NOTES

1. CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
2.  DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR. GRADE 60
3.  DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR. GRADE 60
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
5. WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
6.  DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6x6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER. TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WUF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS.  
\*FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
7. PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
8.  STANDARD FOOTING  
 ALTERNATE FOOTING
9. MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
10. IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMITICIDE.
11. BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.482 FLORIDA BUILDING CODE.

## GLASS BLOCK OPT.

1/8" = 1'-0" (11x17) 1/4" = 1'-0" (22x34)




BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

FOUNDATION  
PLAN "E"

$1/8'' = 1' - 0''$  (11X17)     $1/4'' = 1' - 0''$  (22X34)

## TRPL. WDW. OPT.

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


---

---

---

# SUPER BONUS OPTION

DATE 05-15-2015

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET 01E.1

OF SHEETS

4073

REDWOOD

# FOUNDATION PLAN

**Park  
Square  
HOMES**


**A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000**

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292


THE PARK SERIES

n. These plans, ideas and designs are not to be copied or reproduced in any form without the express written permission from Park Square Homes.

REVISIONS	BY

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


BUTLER PANTRY OPT.




1. CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.

2. □ DENOTES FILL CELL REINF. W/ CONC  
W/ (1) #5φ REBAR. GRADE 60

3. ■ DENOTES FILL CELL REINF. W/ CONC  
W/ (2) #5 $\phi$  REBAR. GRADE 60

4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.

5. WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR. WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.

6.  DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER. TERMITE TREATED SOIL WITH 206mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WWF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS.
- \*FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.

7. PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.

8.  STANDARD FOOTING


- ☐ ALTERNATE FOOTING

9. MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.


10. IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.

11. BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.482 FLORIDA BUILDING CODE.

## PLAN "F"



1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



# FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR GRADE 60
- DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR GRADE 60
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- WATER HEATER T & P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR. WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. WITH MIN. 1" COVER. TERMITE TREATED SOIL WITH .006mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WUF SHALL BE PLACED IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. \*FIBER MESH REINFORCEMENT MAY BE USED AS ALTERNATIVE TO WIRE MESH.
- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS ARE USED.
- 16  
D2


STANDARD FOOTING

1  
D2

ALTERNATE FOOTING
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE TREATED SOIL CAN BE TERMICIDE.
- BORA-CARE TO BE APPLIED ON INTERIOR WALLS IAW MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT TO CH.482 FLORIDA BUILDING CODE.


## S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



## GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



## BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




## FOUNDATION PLAN "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

## TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

**THE PARK SERIES**

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
<b>Park Square HOMES</b>	
<b>FOUNDATION PLAN</b>	
<b>4073</b>	
<b>REDWOOD</b>	
DATE 05-15-21	
SCALE AS NOTED	
DRAWN RDC	
JOB N/A	
SHEET 01F.1	
OF SHEETS	



Floor plan of a bathroom. The overall width is 6'-2 1/2". The layout includes a toilet (5'-2" wide), a shower area (5'-4" CLG.), and a vanity area (2'-4" wide). The distance from the wall to the vanity is 2'-2 3/4". The distance from the vanity to the shower is 3'-1". The distance from the shower to the toilet is 2'-4".

DATE	05-15-2
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	
02D.0	
OF	SHEETS




TABULATION	
UPPER LIVING	2,230 SF.
LOWER LIVING	2,399 SF.
TOTAL LIVING	4,629 SF.
GARAGE	628 SF.
ENTRY	163 SF.
LANAI	200 SF.
TOTAL UNDER ROOF	5,620 SF.
BR. 6/BA. 5 OPTION	146 SF.
TOTAL UNDER ROOF	5,766 SF.
BR. 1/BA. 6 OPTION	185 SF.
TOTAL UNDER ROOF	5,805 SF.


- GENERAL NOTES**
- CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  - DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  - ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3½" UNLESS NOTED OTHERWISE.
  - ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1½" UNLESS NOTED OTHERWISE.
  - FULL ALL DIMENSIONS FROM THE REAR OF PLAN.

**FLOOR PLAN W/  
DIMENSIONS "D"**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



**BUTLER PANTRY OPT.**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



**GLASS BLOCK OPT.**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



**S.G.D. OPTIONS**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

**THE PARK SERIES**

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 02D.1  
OF SHEETS

**FLOOR PLAN W/ DIMENSIONS**

**Park Square HOMES**

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

REVISIONS BY

TABULATION	
UPPER LIVING	1,674 SF.
LOWER LIVING	2,399 SF.
TOTAL LIVING	4,073 SF.
GARAGE	628 SF.
ENTRY	163 SF.
LANAI	200 SF.
TOTAL UNDER ROOF	5,064 SF.
BR. 6/BA. 5 OPTION	146 SF.
TOTAL UNDER ROOF	5,210 SF.
BR. 1/BA. 6 OPTION	185 SF.
TOTAL UNDER ROOF	5,249 SF.


- GENERAL NOTES
- CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  - DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  - ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3/2" UNLESS NOTED OTHERWISE.
  - ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1 1/2" UNLESS NOTED OTHERWISE.
  - FULL ALL DIMENSIONS FROM THE REAR OF PLAN.

FLOOR PLAN W/  
DIMENSIONS "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Engineering By

DBE and C

MICHAEL A. THOMPSON

PE 47509

PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC.

5200 Vineland Road, Suite 200

Orlando, Florida 32811

Phone: (407) 529 - 3000

© COPYRIGHT 2015

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

DATE

05-15-21

SCALE

AS NOTED

DRAWN

RDC

JOB

N/A

SHEET

02E.0

OF

SHEETS

4073

REDWOOD

FLOOR PLAN W/ DIMENSIONS

Park Square HOMES

ENTERPRISES, INC.

5200 Vineland Road, Suite 200

Orlando, Florida 32811

Phone: (407) 529 - 3000

REVISIONS

BY

REDWOOD

4073

FLOOR PLAN W/ DIMENSIONS

Park Square HOMES

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

TABULATION	
UPPER LIVING	2,230 SF.
LOWER LIVING	2,399 SF.
TOTAL LIVING	4,629 SF.
GARAGE	628 SF.
ENTRY	163 SF.
LANAI	200 SF.
TOTAL UNDER ROOF	5,620 SF.
BR. 6/BA. 5 OPTION	146 SF.
TOTAL UNDER ROOF	5,766 SF.
BR. 1/BA. 6 OPTION	185 SF.
TOTAL UNDER ROOF	5,805 SF.

#### GENERAL NOTES


- CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3 1/2" UNLESS NOTED OTHERWISE.
- ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1 1/2" UNLESS NOTED OTHERWISE.
- FULL ALL DIMENSIONS FROM THE REAR OF PLAN.

### FLOOR PLAN W/ DIMENSIONS "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


#### BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





#### GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



#### S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



#### TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)  
20'-0"

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

#### SUPER BONUS OPTION

#### THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	02E.1
OF	SHEETS

#### FLOOR PLAN W/ DIMENSIONS

**Park Square**  
HOMES

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

REVISIONS	BY
-----------	----

2F.0  
SHEETS

REVISIONS	BY

PER 7TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

FLOOR: STRUCTURE	-----	1 PSF
CEILINGS	-----	3 PSF
MECH/ELEC	-----	5 PSF
PARTITIONS	-----	5 PSF

ROOF:	SHEATHING	-----	5	PSF
	STRUCTURE	-----	1	PSF
	CEILINGS	-----	3	PSF
	MECH/ELEC	-----	5	PSF
	TOTAL	-----	20	PSF

RESIDENTIAL FLOOR: ----- 40 PSF  
UNINHABITABLE ATTIC  
WITHOUT STORAGE: ----- 10 PSF

UNINHABITABLE ATTIC  
W/LIMITED STORAGE: ----- 20 PSF

ROOMS OTHER THAN SLEEPING ROOM: -----40 PSF

SLEEPING ROOM: -----30 PSF  
STAIR LIVE LOAD: -----40 PSF  
BALCONIES: -----10 PSF

PASSANGER VEHICLE GARAGE: ---- 50 PSF

MINIMUM ROOF LIVE LOAD (PSF)  
TRIBUTARY LOADED AREA (SQ. FT.)  
FOR ANY STRUCTURAL MEMBER

ROOF SLOPE	0-200	201-600	OVER 600
0:12 < 4:12	20	16	12
≥ 4:12 < 12:12	16	14	12
≥ 12:12	12	12	12

PER 7TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

1. BASIC WIND SPEED: -----140 MPH  
2. RISK CATEGORY ----- II  
3. WIND EXPOSURE: ----- B  
4. BUILDING TYPE: ----- V B

5. ENCLOSURE ----- +/- .18, INCLUDED  
CLASSIFICATION INTERNAL IN NOTE #6  
PRESSURE COEFFICIENT:  
6. COMPONENT / CLADDING ----- SEE PLAN  
DESIGN WIND PRESSURE:

+	XXX	DESIGN WIND PRESSURE 1AW FLA
-	XXX	RESIDENTIAL CODE, SECTION R30

NOTE: DESIGN PRESSURES BASED ON  
BASIC WIND SPEED AND NOT ULTIMATE  
WIND SPEED.

1. PROVIDE RECESS HOT & COLD WATER  
WITH DRAIN @ WASHER SPACE.

2. VENT DRYER THRU ROOF.
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.

4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.

5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.

- 6.

-  DENOTES CONC. BLOCK  
WALL HGT. @ N/A

7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS


8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES

9. ANCHOR THE CONDENSER UNIT TO SLAB  
PER CODE: M1307.1 - M1307.2


10. ALL INTER. FIRST FLOOR CEILINGS AT  
9'-4" UNLESS NOTED OTHERWISE.

- ALL INTER. SECOND FLOOR CEILINGS AT  
9'-0" UNLESS NOTED OTHERWISE.


NOTE: DOOR FROM HOUSE TO GARAGE MUST  
BE SOLID WOOD DOORS NO LESS 1 3/8"  
IAW R302.5.1




1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



1/8" = 1'-0" (11X17) 1/4" = 1'-0" (22X34)



1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: **6'-8"** U.N.O.

THE PARK SERIES

n. These plans, ideas and designs are not to be copied or reproduced in any form without the express written permission from Park Square Homes.

**Park** | A DIVISION OF PARK SQUARE ENTERPRISES, INC.

# FLOOR PLAN W/ NOTES

4073

REDWOOD

DATE 05-15-2

SCALE AS NOTED

DRAWN RDC

JOB	N/A
-----	-----

SHEET

03D.0

OF SHEETS



NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SELF CLOSING 1AW R302.5.1

### LOAD INFORMATION

PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE

#### DEAD LOADS

FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF

ROOF: SHEATHING	5 PSF
STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
TOTAL	20 PSF

#### FLOOR LIVE LOADS

RESIDENTIAL FLOOR:	40 PSF
STAIR LIVE LOAD:	40 PSF

#### ROOF LIVE LOADS

MINIMUM ROOF LIVE LOAD (PSF)  
TRIBUTARY LOADED AREA (SQ. FT.)  
FOR ANY STRUCTURAL MEMBER

ROOF SLOPE	0-200	201-600	OVER 600
0:12 < 4:12	20	16	12
≥ 4:12 < 12:12	16	14	12
≥ 12:12	12	12	12

### WIND INFORMATION

PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE



- BASIC WIND SPEED: ----- 140 MPH
- WIND IMPORTANCE FACTOR: ----- N/A
- BUILDING CATEGORY: ----- B
- INTERNAL PRESSURE COEFFICIENT: ----- +/- .18, INCLUDED IN NOTE #5
- COMPONENT / CLADDING: ----- SEE PLAN DESIGN WIND PRESSURE:

+ XXX	DESIGN WIND PRESSURE 1AW FLA
- XXX	RESIDENTIAL CODE, SECTION R301


NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.

### GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU EXTERIOR WALL.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.


6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.
-  DENOTES CONC. BLOCK WALL HGT. @ N/A

- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M 307.3 + 1307.3.1
- ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.
- ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.




### S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



### GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




### BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

### FLOOR PLAN W/ NOTES "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" U.N.O.

### THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

### FLOOR PLAN W/ NOTES

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 03D.1  
OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL, AND IS CERTIFIED AS SUCH

SUPER BONUS OPTION

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

LOAD INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF

ROOF: SHEATHING	
STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
TOTAL	20 PSF

FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 PSF

ROOMS OTHER THAN	
SLEEPING ROOM:	40 PSF
SLEEPING ROOM:	30 PSF
STAIR LIVE LOAD:	40 PSF
BALCONIES:	40 PSF
PASSANGER VEHICLE GARAGE:	50 PSF

ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (PSF) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER	
ROOF SLOPE	0-200 201-600 OVER 600
0:12 < 4:12	20 16 12
≥ 4:12 < 12:12	16 14 12
≥ 12:12	12 12 12






WIND INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

- BASIC WIND SPEED: ----- 140 MPH
- RISK CATEGORY ----- II
- WIND EXPOSURE: ----- B
- BUILDING TYPE: ----- V B
- ENCLOSURE ----- +/- 18, INCLUDED  
CLASSIFICATION INTERNAL IN NOTE #6  
PRESSURE COEFFICIENT:
- COMPONENT / CLADDING ----- SEE PLAN DESIGN  
WIND PRESSURE:  
+ XXX DESIGN WIND PRESSURE IAW FLA  
- XXX RESIDENTIAL CODE, SECTION R301  
NOTE: DESIGN PRESSURES BASED ON  
BASIC WIND SPEED AND NOT ULTIMATE  
WIND SPEED.

GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER  
WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR  
ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION  
TO BE FROM CALCULATED DIMENSIONS  
ONLY. ANY DISCREPANCIES OR ERRORS  
TO BE REPORTED PROMPTLY TO  
SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE  
DETERMINED BY COMMUNITY STANDARDS  
AND APPLICABLE COUNTY CODES.
- |            |   |
|------------|---|
| ██████████ | DENOTES CONC. BLOCK<br>WALL HGT. @ 9'-4" AFF. |
| ▨▨▨▨▨▨     | DENOTES CONC. BLOCK<br>WALL HGT. @ N/A        |
- REFER TO TYPICAL DETAIL SHEET FOR  
EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING  
REQUIREMENTS AT ALL WOOD TO  
MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB  
PER CODE: M 1307.1 - M1307.2
- ALL INTER. FIRST FLOOR CEILINGS AT  
9'-4" UNLESS NOTED OTHERWISE.  
ALL INTER. SECOND FLOOR CEILINGS AT  
9'-0" UNLESS NOTED OTHERWISE.

NOTE: DOOR FROM HOUSE TO GARAGE MUST  
BE SOLID WOOD DOORS NO LESS 1 3/8"  
IAW R302.5.1



THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park Square  
HOMES

FLOOR PLAN W/ NOTES

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 03E.0  
OF 3 SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL, AND IS CERTIFIED AS SUCH

NOTE: ALL INTERIOR DOORS ON THIS  
FLOOR TO BE: 6'-8" U.N.O.

DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	
03E.1	
OF	SHEETS

LOAD INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 P&F
CEILINGS	3 P&F
MECH/ELEC	5 P&F
PARTITIONS	5 P&F
TOTAL	20 P&F

ROOF: SHEATHING	
STRUCTURE	1 P&F
CEILINGS	3 P&F
MECH/ELEC	5 P&F
TOTAL	20 P&F

FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 P&F
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 P&F
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 P&F

ROOMS OTHER THAN	
SLEEPING ROOM:	40 P&F
SLEEPING ROOM:	30 P&F
STAIR LIVE LOAD:	40 P&F
BALCONIES:	40 P&F
PASSANGER VEHICLE GARAGE:	50 P&F

ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (P&F) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER	

ROOF SLOPE	0-200	201-600	OVER 600
0:12 < 4:12	20	16	12
≥ 4:12 < 12:12	16	14	12
≥ 12:12	12	12	12




WIND INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

- BASIC WIND SPEED: ----- 140 MPH
- RISK CATEGORY ----- II
- WIND EXPOSURE: ----- B
- BUILDING TYPE: ----- V B
- ENCLOSURE ----- +/- .18, INCLUDED  
CLASSIFICATION INTERNAL IN NOTE #6  
PRESSURE COEFFICIENT:
- COMPONENT / CLADDING ----- SEE PLAN DESIGN  
WIND PRESSURE:  
+ XXX DESIGN WIND PRESSURE IAW FLA  
- XXX RESIDENTIAL CODE, SECTION R301  
NOTE: DESIGN PRESSURES BASED ON  
BASIC WIND SPEED AND NOT ULTIMATE  
WIND SPEED.


GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER  
WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR  
ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION  
TO BE FROM CALCULATED DIMENSIONS  
ONLY. ANY DISCREPANCIES OR ERRORS  
TO BE REPORTED PROMPTLY TO  
SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE  
DETERMINED BY COMMUNITY STANDARDS  
AND APPLICABLE COUNTY CODES.
- |  |   |
|--|---|
|  | DENOTES CONC. BLOCK<br>WALL HGT. @ 9'-4" AFF. |
|  | DENOTES CONC. BLOCK<br>WALL HGT. @ N/A        |
- REFER TO TYPICAL DETAIL SHEET FOR  
EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING  
REQUIREMENTS AT ALL WOOD TO  
MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB  
PER CODE: M1307.1 - M1307.2
- ALL INTER. FIRST FLOOR CEILINGS AT  
9'-4" UNLESS NOTED OTHERWISE.  
ALL INTER. SECOND FLOOR CEILINGS AT  
9'-0" UNLESS NOTED OTHERWISE.

NOTE: DOOR FROM HOUSE TO GARAGE MUST  
BE SOLID WOOD DOORS NO LESS 1 3/8"  
IAW R302.5.1



FLOOR PLAN W/  
NOTES "F"



THE PARK SERIES

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park Square  
HOMES

FLOOR PLAN W/ NOTES

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 03F.0  
OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL, AND IS CERTIFIED AS SUCH

NOTE: ALL INTERIOR DOORS ON THIS  
FLOOR TO BE: 6'-8" U.N.O.




- GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3/2" UNLESS NOTED OTHERWISE.
  4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1 1/2" UNLESS NOTED OTHERWISE.
  5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

UPPER FLOOR PLAN  
W/ DIMENSIONS "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)






SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




BR. 6/ BA. 5 OPTION

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
UPPER FLOOR PLAN W/ DIMENSIONS		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	04D.0	
OF	SHEETS	



- GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3/2" UNLESS NOTED OTHERWISE.
  4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1 1/2" UNLESS NOTED OTHERWISE.
  5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

UPPER FLOOR PLAN  
W/ DIMENSIONS "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

SHOWER OPT.



1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

BR. 6/ BA. 5 OPTION

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

BA. 4 OPTION





1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**THE PARK SERIES**

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**


UPPER FLOOR PLAN W/  
DIMENSIONS

4073  
REDWOOD


DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 04D.1  
OF SHEETS

- ### GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE  $3\frac{1}{2}"$  UNLESS NOTED OTHERWISE.
  4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE  $1\frac{1}{2}"$  UNLESS NOTED OTHERWISE.
  5. FULL ALL DIMENSIONS FROM THE REAR OF PLAN.

UPPER FLOOR PLAN  
W/ DIMENSIONS "D"



$$\overline{1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)}$$


SHOWER OPT.

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$



SHOWER OPT.

$1/8" = 1'-0" (11 \times 17) \quad 1/4" = 1'-0" (22 \times 34)$




SHOWER OPT.

1/8" = 1'-0" (11x17)
1/4" = 1'-0" (22x34)



BA. 4 OPTION

1/8" = 1'-0" (11x17)  
1/4" = 1'-0" (22x34)




SHOWER OPT.

$$\begin{aligned} 1/8'' &= 1' - \emptyset'' \quad (11 \times 17) \\ 1/4'' &= 1' - \emptyset'' \quad (22 \times 34) \end{aligned}$$

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

1/8" = 1'-0" (11x17) 1/4" = 1'-0" (22x34)

1/8" = 1'-0" (11X17) 1/4" = 1'-0" (22X34)

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


1/8"=1'-0" (11X17)
1/4"=1'-0" (22X34)

1/8" = 1'-0" (11x17)  
1/4" = 1'-0" (22x34)

1/8" = 1'-0" (11x17)
1/4" = 1'-0" (22x34)

## GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3½" UNLESS NOTED OTHERWISE.
4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1½" UNLESS NOTED OTHERWISE.
5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

THE PARK SERIES

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

## UPPER FLOOR PLAN W/ DIMENSIONS

4073

REDWOOD

DATE 05-15-


SCALE AS NOTE

DRAWN RD


JOB	N.
-----	----

SHEET


04E.C



BR. 6/ BA. 5 OPTION

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$




SHOWER OPT.

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


SHOWER OPT.


$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

UPPER FLOOR PLAN  
W/ DIMENSIONS "E"

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$



SHOWER OPT.

1/8" = 1' - 0" (11x17)
1/4" = 1' - 0" (22x34)



BA. 4 OPTION

1/8" = 1' - 0" (11x17)  
1/4" = 1' - 0" (22x34)



SHOWER OPT.

1/8" = 1' - 0" (11x17)
1/4" = 1' - 0" (22x34)

- ### GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE  $3\frac{1}{2}"$ , UNLESS NOTED OTHERWISE.
  4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE  $1\frac{1}{2}"$ , UNLESS NOTED OTHERWISE.
  5. FULL ALL DIMENSIONS FROM THE REAR OF PLAN.

[illegible]

## SUPER BONUS OPTION

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied, reproduced, or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

4073

## UPPER FLOOR PLANS DIMENSIONS

**Park Square HOMES**

Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	REVISIONS
---	-----------

DATE 05-15-2011  
SCALE AS NOTED  
DRAWN RDO  
JOB N/A  
SHEET  
04E.1  
OF SHEETS


- GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3/2" UNLESS NOTED OTHERWISE.
  4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1 1/2" UNLESS NOTED OTHERWISE.
  5. FULL ALL DIMENSIONS FROM THE REAR OF PLAN.

UPPER FLOOR PLAN  
W/ DIMENSIONS "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

OPT. BEDROOM 7 / BATH 6, LOFT / OPT. MEDIA

UPPER FLOOR PLAN W/ DIMENSIONS

4073

REDWOOD

DATE 05-15-21

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET 04E.2

OF SHEETS

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292


A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

- GENERAL NOTES
1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
  3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE 3/2" UNLESS NOTED OTHERWISE.
  4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE 1 1/2" UNLESS NOTED OTHERWISE.
  5. FULL ALL DIMENSIONS FROM THE REAR OF PLAN.


UPPER FLOOR PLAN  
W/ DIMENSIONS "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




BR. 6/ BA. 5 OPTION

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 528 - 3000

Park Square  
HOMES


UPPER FLOOR PLAN W/  
DIMENSIONS

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 04F.0  
OF SHEETS


© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and design are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.






BR. 6/ BA. 5 OPTION

$1/8'' = 1' - 0''$  (11x17)     $1/4'' = 1' - 0''$  (22x34)



SHOWER OPT.



$1/8'' = 1' - 0''$  (11x17)     $1/4'' = 1' - 0''$  (22x34)



SHOWER OPT.


$1/8'' = 1' - 0''$  (11X17)     $1/4'' = 1' - 0''$  (22X34)

UPPER FLOOR PLAN  
W/ DIMENSIONS "F"

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$



SHOWER OPT.

1/8" = 1' - 0" (11x17)
1/4" = 1' - 0" (22x34)



BA. 4 OPTION

	1/8" = 1'-0" (11x17)
4	1/4" = 1'-0" (22x34)



SHOWER OPT.

1/8" = 1' - 0" (11x17)
1/4" = 1' - 0" (22x34)

- GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
2. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE  $3\frac{1}{2}'$  UNLESS NOTED OTHERWISE.
4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE  $7\frac{1}{2}'$  UNLESS NOTED OTHERWISE.
5. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.

1000 *Journal of Management Education*

## SUPER BONUS OPTION

THE PARK SERIES

© Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

© COPYRIGHT 2015

04F.1

JOB N/A

DRAWN RDC

SCALE AS NOTED

DATE 05-15-2

4073  
REDWOOD

## UPPER FLOOR PLAN W/ DIMENSIONS

**Park Square HOMES**  
A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000


**A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.**

**5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000**


Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-22

REVISIONS	BY



- UPPER FLOOR PLAN  
W/ DIMENSIONS "F"




SHOWER OPT.  
1/8"=1'-0" (11x17) 1/4"=1'-0" (22x34)




SHOWER OPT.  
1/8" = 1'-0" (11x17) 1/4" = 1'-0" (22x34)



SHOWER OPT.  
1/8"=1'-0" (11x17)  
1/4"=1'-0" (22x34)



BA. 4 OPTION



SHOWER OPT.  
1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>TH</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	REVISIONS	BY

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

## UPPER FLOOR PLAN W/ DIMENSIONS

4073  
REDWOOD

DATE	05-15-2
SCALE	AS NOTED
DRAWN	RDO
JOB	N/A
SHEET	
04F.2	
OF	SHEETS









NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SELF CLOSING IAW R302.5.1


LOAD INFORMATION	
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE	
DEAD LOADS	
FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF
ROOF: SHEATHING	
STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
TOTAL	20 PSF
FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 PSF
STAIR LIVE LOAD:	40 PSF
ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (PSF)	
TRIBUTARY LOADED AREA (SQ. FT.)	
FOR ANY STRUCTURAL MEMBER	
ROOF SLOPE	0-200
201-600	OVER 600
0:12 < 4:12	20
4:12 < 12:12	16
12:12	12

WIND INFORMATION	
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE	
1. BASIC WIND SPEED:	140 MPH
2. WIND IMPORTANCE FACTOR:	N/A
3. BUILDING CATEGORY:	B
4. INTERNAL PRESSURE COEFFICIENT:	+/- .18, INCLUDED IN NOTE #5
5. COMPONENT / CLADDING DESIGN WIND PRESSURE:	SEE PLAN
+ XXX	DESIGN WIND PRESSURE IAW FLA
- XXX	RESIDENTIAL CODE, SECTION R301
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.	

GENERAL NOTES	
1. PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.	
2. VENT DRYER THRU EXTERIOR WALL.	
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.	
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.	
5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.	
6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.	
 DENOTES CONC. BLOCK WALL HGT. @ N/A	
7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS	
8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES	
9. ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M 307.3 + I307.3.1	
10. ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.	
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.	



UPPER FLOOR PLAN  
W/ NOTES "D"  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" U.N.O.

THE PARK SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

UPPER FLOOR PLAN  
W/ NOTES

4073  
REDWOOD

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park  
Square  
HOMES

REVISIONS

BY

DATE

05-15-21

SCALE

AS NOTED

DRAWN

RDC

JOB

N/A

SHEET

05D.2

OF

SHEETS

LOAD INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF
FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 PSF
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 PSF
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 PSF
ROOMS OTHER THAN	
SLEEPING ROOM:	40 PSF
SLEEPING ROOM:	30 PSF
STAIR LIVE LOAD:	40 PSF
BALCONIES:	40 PSF
PASSANGER VEHICLE GARAGE:	50 PSF
ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (PSF) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER	

ROOF SLOPE	0-200	201-600	OVER 600
0:12 < 4:12	20	16	12
≥ 4:12 < 12:12	16	14	12
≥ 12:12	12	12	12

WIND INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

- BASIC WIND SPEED: 140 MPH
  - RISK CATEGORY: II
  - WIND EXPOSURE: B
  - BUILDING TYPE: V-B
  - ENCLOSURE: +/-, INCLUDED CLASSIFICATION INTERNAL IN NOTE #6 PRESSURE COEFFICIENT:
  - COMPONENT / CLADDING: SEE PLAN DESIGN WIND PRESSURE:
- +XXX DESIGN WIND PRESSURE IAW FLA  
-XXX RESIDENTIAL CODE, SECTION R301
- NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.

GENERAL NOTES


- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.
- ██████████

 DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.  


▨▨▨▨▨▨

 DENOTES CONC. BLOCK WALL HGT. @ N/A
- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2
- ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.  
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.


NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOORS NO LESS 1 3/8" IAW R302.5.1



BR. 6/ BA. 5 OPTION





SHOWER OPT.



SHOWER OPT.




UPPER FLOOR PLAN  
W/ NOTES "E"




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" UNO.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES



Copyright 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.





REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
Park Square HOMES	
UPPER FLOOR PLAN W/ NOTES	
4073 REDWOOD	
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	05E.0
OF	SHEETS

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SELF CLOSING 1AW R302.5.1






LOAD INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
DEAD LOADS		
FLOOR: STRUCTURE	-----	1 PSF
CEILINGS	-----	3 PSF
MECH/ELEC	-----	5 PSF
PARTITIONS	-----	5 PSF
TOTAL	-----	20 PSF
ROOF: SHEATHING		
STRUCTURE	-----	5 PSF
CEILINGS	-----	1 PSF
MECH/ELEC	-----	3 PSF
TOTAL	-----	20 PSF
FLOOR LIVE LOADS		
RESIDENTIAL FLOOR:	-----	40 PSF
STAIR LIVE LOAD:	-----	40 PSF
ROOF LIVE LOADS		
MINIMUM ROOF LIVE LOAD (PSF)		
TRIBUTARY LOADED AREA (SQ. FT.)		
FOR ANY STRUCTURAL MEMBER		
ROOF SLOPE	0-200	201-600
0:12 < 4:12	20	16
≥ 4:12 < 12:12	16	14
≥ 12:12	12	12

WIND INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
1. BASIC WIND SPEED:	-----	140 MPH
2. WIND IMPORTANCE FACTOR:	-----	N/A
3. BUILDING CATEGORY:	-----	B
4. INTERNAL PRESSURE COEFFICIENT:	-----	+/- .18, INCLUDED IN NOTE #5
5. COMPONENT / CLADDING DESIGN WIND PRESSURE:	-----	SEE PLAN
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.		

GENERAL NOTES		
1. PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.		
2. VENT DRYER THRU EXTERIOR WALL.		
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.		
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.		
5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.		
6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.		
 DENOTES CONC. BLOCK WALL HGT. @ N/A		
7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS		
8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES		
9. ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M 307.3 + I307.3.1		
10. ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.		
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.		



UPPER FLOOR PLAN W/ NOTES "E"



THE PARK SERIES

Engineering By DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000

Park Square HOMES

UPPER FLOOR PLAN W/ NOTES

4073 REDWOOD

DATE 05-15-21

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET 05E.1

OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

SUPER BONUS OPTION

NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" UNO.

5



LOAD INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

DEAD LOADS	
FLOOR: STRUCTURE	1 P&F
CEILINGS	3 P&F
MECH/ELEC	5 P&F
PARTITIONS	5 P&F
TOTAL	20 P&F
ROOF: SHEATHING	
STRUCTURE	1 P&F
CEILINGS	3 P&F
MECH/ELEC	5 P&F
TOTAL	20 P&F

FLOOR LIVE LOADS	
RESIDENTIAL FLOOR:	40 P&F
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 P&F
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 P&F
ROOMS OTHER THAN	
SLEEPING ROOM:	40 P&F
SLEEPING ROOM:	30 P&F
STAIR LIVE LOAD:	40 P&F
BALCONIES:	40 P&F
PASSANGER VEHICLE GARAGE:	50 P&F
ROOF LIVE LOADS	
MINIMUM ROOF LIVE LOAD (P&F) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER	
ROOF SLOPE	0-200 201-600 OVER 600
0:12 < 4:12	20 16 12
≥ 4:12 < 12:12	16 14 12
≥ 12:12	12 12 12


WIND INFORMATION  
PER 1TH EDITION, 2020 FLORIDA BUILDING  
RESIDENTIAL CODE

- BASIC WIND SPEED: 140 MPH
  - RISK CATEGORY: II
  - WIND EXPOSURE: B
  - BUILDING TYPE: V-B
  - ENCLOSURE: +/-18, INCLUDED CLASSIFICATION INTERNAL IN NOTE #6 PRESSURE COEFFICIENT:
  - COMPONENT / CLADDING: SEE PLAN DESIGN WIND PRESSURE:
- +XXX DESIGN WIND PRESSURE IAW FLA  
-XXX RESIDENTIAL CODE, SECTION R301
- NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.


GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.
- |  |  |
|--|--|
|  | DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF. |
|  | DENOTES CONC. BLOCK WALL HGT. @ N/A        |
- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2
- ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.  
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.


NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOORS NO LESS 1 3/8" IAW R302.5.1



BR. 6/ BA. 5 OPTION



SHOWER OPT.





SHOWER OPT.




UPPER FLOOR PLAN  
W/ NOTES "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" W.O.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 528 - 3000

Park Square  
HOMES

UPPER FLOOR PLAN  
W/ NOTES

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 05F.0  
OF SHEETS

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SELF CLOSING 1AW R302.5.1

### LOAD INFORMATION

PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE

#### DEAD LOADS

FLOOR: STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
PARTITIONS	5 PSF
TOTAL	20 PSF

ROOF: SHEATHING	5 PSF
STRUCTURE	1 PSF
CEILINGS	3 PSF
MECH/ELEC	5 PSF
TOTAL	20 PSF

#### FLOOR LIVE LOADS

RESIDENTIAL FLOOR:	40 PSF
STAIR LIVE LOAD:	40 PSF

#### ROOF LIVE LOADS

MINIMUM ROOF LIVE LOAD (PSF)  
TRIBUTARY LOADED AREA (SQ. FT.)  
FOR ANY STRUCTURAL MEMBER

ROOF SLOPE	0-200	201-600	OVER 600
0:12 < 4:12	20	16	12
≥ 4:12 < 12:12	16	14	12
≥ 12:12	12	12	12

### WIND INFORMATION



PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE


- BASIC WIND SPEED: ----- 140 MPH
- WIND IMPORTANCE FACTOR: ----- N/A
- BUILDING CATEGORY: ----- B
- INTERNAL PRESSURE: ----- +/- .18, INCLUDED COEFFICIENT: IN NOTE #5
- COMPONENT / CLADDING: ----- SEE PLAN DESIGN WIND PRESSURE:

+ XXX DESIGN WIND PRESSURE 1AW FLA  
- XXX RESIDENTIAL CODE, SECTION R301

NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.


### GENERAL NOTES

- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU EXTERIOR WALL.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.
-  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.  
 DENOTES CONC. BLOCK WALL HGT. @ N/A
- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M 307.3 + I307.3.1
- ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.  
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.




### BR. 6/ BA. 5 OPTION

1/8'x1'-0" (11X17) 1/4'x1'-0" (22X34)



### SHOWER OPT.

1/8'x1'-0" (11X17) 1/4'x1'-0" (22X34)




### SHOWER OPT.

1/8'x1'-0" (11X17) 1/4'x1'-0" (22X34)

### UPPER FLOOR PLAN W/ NOTES "F"

1/8'x1'-0" (11X17) 1/4'x1'-0" (22X34)



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" U.N.O.

### THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

REVISIONS	BY

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park  
Square  
HOMES

UPPER FLOOR PLAN  
W/ NOTES

4073  
REDWOOD



### SUPER BONUS OPTION



DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	05F.1
OF	SHEETS

NOTE: DOOR FROM HOUSE TO GARAGE MUST BE SELF CLOSING IAW R302.5.1


LOAD INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
DEAD LOADS		
FLOOR: STRUCTURE	-----	1 PSF
CEILINGS	-----	3 PSF
MECH/ELEC	-----	5 PSF
PARTITIONS	-----	5 PSF
TOTAL	-----	20 PSF
ROOF: LIVE LOADS		
ROOF: SHEATHING	-----	5 PSF
STRUCTURE	-----	1 PSF
CEILINGS	-----	3 PSF
MECH/ELEC	-----	5 PSF
TOTAL	-----	20 PSF
FLOOR LIVE LOADS		
RESIDENTIAL FLOOR:	-----	40 PSF
STAIR LIVE LOAD:	-----	40 PSF
ROOF LIVE LOADS		
MINIMUM ROOF LIVE LOAD (PSF)		
TRIBUTARY LOADED AREA (SQ. FT.)		
FOR ANY STRUCTURAL MEMBER		
ROOF SLOPE	0-200	201-600
0:12 < 4:12	20	16
≥ 4:12 < 12:12	16	14
≥ 12:12	12	12

WIND INFORMATION		
PER 1TH EDITION, 2020 FLORIDA BUILDING RESIDENTIAL CODE		
1. BASIC WIND SPEED:	-----	140 MPH
2. WIND IMPORTANCE FACTOR:	-----	N/A
3. BUILDING CATEGORY:	-----	B
4. INTERNAL PRESSURE COEFFICIENT:	-----	+/- .18, INCLUDED IN NOTE #5
5. COMPONENT / CLADDING DESIGN WIND PRESSURE:	-----	SEE PLAN
NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.		

GENERAL NOTES		
1. PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.		
2. VENT DRYER THRU EXTERIOR WALL.		
3. PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.		
4. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.		
5. MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.		
6.  DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.		
 DENOTES CONC. BLOCK WALL HGT. @ N/A		
7. REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS		
8. REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES		
9. ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M 307.3 + I307.3.1		
10. ALL INTER. FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.		
ALL INTER. SECOND FLOOR CEILINGS AT 9'-0" UNLESS NOTED OTHERWISE.		



UPPER FLOOR PLAN W/ NOTES "F"



NOTE: ALL INTERIOR DOORS ON THIS FLOOR TO BE: 6'-8" U.N.O.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

UPPER FLOOR PLAN W/ NOTES

4073 REDWOOD

DATE 05-15-21

SCALE AS NOTED


DRAWN RDC

JOB N/A

SHEET 05F.2 OF SHEETS

Engineering By: DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000



**EXTERIOR FINISH NOTES**

1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020 - ALL LATH AND LATH ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIAL. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED WITH 1-1/2 INCH 11 GAGE NAILS HAVING A 7/16 INCH HEAD, OR 1/8 INCH LONG 16 GAGE STAPLES SPACED NO MORE THAN 6 INCHES, OR AS OTHERWISE APPROVED.

2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020

3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020 - MINIMUM NO 26 GALVANIZED SHEET GAGE CORROSION-RESISTANT WEEP SCREED OR PLASTIC WEEP SCREED WITH A MINIMUM VERTICAL ATTACHMENT FLANGE OF 3-1/2 INCHES SHALL BE PROVIDED AT OR BELOW THE PLATE LINE ON EXTERIOR STUD WALLS IN ACCORDANCE WITH ASTM C 926. THE WEEP SCREED SHALL BE PLACED A MINIMUM OF 4 INCHES ABOVE THE EARTH OR 2 INCHES ABOVE PAVED AREAS. THE WEATHER RESISTANT BARRIER SHALL LAP THE ATTACHMENT FLANGE. THE EXTERIOR LATH SHALL COVER AND TERMINATE ON THE ATTACHMENT FLANGE OF THE WEEP SCREED.

4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020 - INSTALLED OVER WOOD BASED SHEATHING SHALL INCLUDE A WATER RESISTIVE VAPOR PERMEABLE BARRIER EQUIVALENT TO 2 LAYERS OF GRADE D PAPER


5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.

6. STUCCO APPLICATION MUST BE IAW R103.1.4 OF THE 11TH EDITION, FBCR 2020 OR EXCEPTION : APPLICATION INSTALLED IN ACCORDANCE WITH ASTM C 926

7. UNDERLAYMENT REQUIREMENTS MUST BE IAW R305.1.1 OF THE 11TH EDITION, FBCR 2020 -

1. Roof slopes from two units vertical in 12 units horizontal (17-percent slope), and less than four units vertical in 12 units horizontal (33-percent slope). Apply a 19-inch (483 mm) strip of underlayment felt parallel to and starting at the eaves, fastened sufficiently to hold in place. Starting at the eave, apply 36-inchwide (914 mm) sheets of underlayment, overlapping successive sheets 19 inches (483 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with corrosion-resistant fasteners with one row centered in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1/2 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic Caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.

2. Roof slopes of four units vertical in 12 units horizontal (33-percent slope) or greater. Underlayment shall be applied shingle fashion, parallel to and starting from the eave and lapped 4 inches (51 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with two staggered rows in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.



**FRONT ELEVATION "D"**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



**REAR ELEVATION**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**THE PARK SERIES**

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292


A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

**EXTERIOR ELEVATION FRONT AND REAR**



4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 06D.0  
OF SHEETS



**EXTERIOR FINISH NOTES**

- LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020 - ALL LATH AND LATH ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIAL. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED WITH 1-1/2 INCH 11 GAGE NAILS HAVING A 7/16 INCH HEAD, OR 1/8 INCH LONG 16 GAGE STAPLES SPACED NO MORE THAN 6 INCHES, OR AS OTHERWISE APPROVED.
- PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
- WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020- MINIMUM NO 26 GALVANIZED SHEET GAGE CORROSION-RESISTANT WEEP SCREED OR PLASTIC WEEP SCREED WITH A MINIMUM VERTICAL ATTACHMENT FLANGE OF 3-1/2 INCHES SHALL BE PROVIDED AT OR BELOW THE PLATE LINE ON EXTERIOR STUD WALLS IN ACCORDANCE WITH ASTM C 926. THE WEEP SCREED SHALL BE PLACED A MINIMUM OF 4 INCHES ABOVE THE EARTH OR 2 INCHES ABOVE PAVED AREAS. THE WEATHER RESISTANT BARRIER SHALL LAP THE ATTACHMENT FLANGE. THE EXTERIOR LATH SHALL COVER AND TERMINATE ON THE ATTACHMENT FLANGE OF THE WEEP SCREED.
- WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020- INSTALLED OVER WOOD BASED SHEATHING SHALL INCLUDE A WATER RESISTIVE VAPOR PERMEABLE BARRIER EQUIVALENT TO 2 LAYERS OF GRADE D PAPER
- 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.
- STUCCO APPLICATION MUST BE IAW R103.1.4 OF THE 11TH EDITION, FBCR 2020 OR EXCEPTION : APPLICATION INSTALLED IN ACCORDANCE WITH ASTM C 926
- UNDERLAYMENT REQUIREMENTS MUST BE IAW R305.1.1 OF THE 11TH EDITION, FBCR 2020 -  
1. Roof slopes from two units vertical in 12 units horizontal (17-percent slope), and less than four units vertical in 12 units horizontal (33-percent slope). Apply a 19-inch (483 mm) strip of underlayment felt parallel to and starting at the eaves, fastened sufficiently to hold in place. Starting at the eave, apply 36-inchwide (914 mm) sheets of underlayment, overlapping successive sheets 19 inches (483 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with corrosion-resistant fasteners with one row centered in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1/2 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic Caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.  
2. Roof slopes of four units vertical in 12 units horizontal (33-percent slope) or greater. Underlayment shall be applied shingle fashion, parallel to and starting from the eave and lapped 4 inches (51 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with two staggered rows in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.



NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

**THE PARK SERIES**

Engineering By: DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**


**EXTERIOR ELEVATION FRONT AND REAR**

**4073 REDWOOD**

DATE: 05-15-21  
SCALE: AS NOTED  
DRAWN: RDC  
JOB: N/A  
SHEET: 06D.1 OF 2 SHEETS









1. LATH TO BE ATTACHED IAW R703.1.1 OF THE 11TH EDITION, FBCR. 2020 - ALL LATH AND LATH ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIAL. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED WITH 1-1/2 INCH 11 GAGE NAILS HAVING A 7/16 INCH HEAD, OR 7/8 INCH LONG 16 GAGE STAPLES SPACED NO MORE THAN 6 INCHES, OR AS OTHERWISE APPROVED.
2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R703.1.2 OF THE 11TH EDITION, FBCR. 2020
3. WEEP SCREED TO BE INSTALLED IAW R703.1.2.1 OF THE 11TH EDITION, FBCR. 2020- MINIMUM NO 26 GALVANIZED SHEET GAGE CORROSION-RESISTANT WEEP SCREED OR PLASTIC WEEP SCREED WITH A MINIMUM VERTICAL ATTACHMENT FLANGE OF 3-1/2 INCHES SHALL BE PROVIDED AT OR BELOW THE PLATE LINE ON EXTERIOR STUD WALLS IN ACCORDANCE WITH ASTM C 926. THE WEEP SCREED SHALL BE PLACED A MINIMUM OF 4 INCHES ABOVE THE EARTH OR 2 INCHES ABOVE PAVED AREAS. THE WEATHER RESISTANT BARRIER SHALL LAP THE ATTACHMENT FLANGE, THE EXTERIOR LATH SHALL COVER AND TERMINATE ON THE ATTACHMENT FLANGE OF THE WEEP SCREED.
4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R703.1.3 OF THE 11TH EDITION, FBCR. 2020- INSTALLED OVER WOOD BASED SHEATHING SHALL INCLUDE A WATER RESISTIVE VAPOR PERMEABLE BARRIER EQUIVALENT TO 2 LAYERS OF GRADE D PAPER
5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.
6. STUCCO APPLICATION MUST BE IAW R703.1.4 OF THE 11TH EDITION, FBCR. 2020 OR EXCEPTION : APPLICATION INSTALLED IN ACCORDANCE WITH ASTM C 926
7. UNDERLAYMENT REQUIREMENTS MUST BE IAW R905.1.1 OF THE 11TH EDITION, FBCR 2020 -
  - 1.Roof slopes from two units vertical in 12 units horizontal (17-percent slope), and less than four units vertical in 12 units horizontal (33-percent slope). Apply a 19-inch (483 mm) strip of underlayment felt parallel to and starting at the eaves, fastened sufficiently to hold in place. Starting at the eave, apply 36-inchwide (914 mm) sheets of underlayment, overlapping successive sheets 19 inches (483 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with corrosion-resistant fasteners with one row centered in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than Z E 1 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic Caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.
  - 2.Roof slopes of four units vertical in 12 units horizontal (33-percent slope) or greater. Underlayment shall be applied shingle fashion, parallel to and starting from the eave and lapped 4 inches (51 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with two staggered rows in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.




FRONT ELEVATION "E"



REAR ELEVATION

NOTE: ADD N/A SMOOTH FINISH BANDS  
TO ALL WINDOWS, DOORS & S.G.D.S  
(TYP @ SIDES & REAR ELEVATIONS)





### EXTERIOR FINISH NOTES

- LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020 - ALL LATH AND LATH ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIAL. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED WITH 1-1/2 INCH 11 GAGE NAILS HAVING A 7/16 INCH HEAD, OR 1/8 INCH LONG 16 GAGE STAPLES SPACED NO MORE THAN 6 INCHES, OR AS OTHERWISE APPROVED.
- PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
- WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020- MINIMUM NO 26 GALVANIZED SHEET GAGE CORROSION-RESISTANT WEEP SCREED OR PLASTIC WEEP SCREED WITH A MINIMUM VERTICAL ATTACHMENT FLANGE OF 3-1/2 INCHES SHALL BE PROVIDED AT OR BELOW THE PLATE LINE ON EXTERIOR STUD WALLS IN ACCORDANCE WITH ASTM C 926. THE WEEP SCREED SHALL BE PLACED A MINIMUM OF 4 INCHES ABOVE THE EARTH OR 2 INCHES ABOVE PAVED AREAS. THE WEATHER RESISTANT BARRIER SHALL LAP THE ATTACHMENT FLANGE. THE EXTERIOR LATH SHALL COVER AND TERMINATE ON THE ATTACHMENT FLANGE OF THE WEEP SCREED.
- WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020- INSTALED OVER WOOD BASED SHEATHING SHALL INCLUDE A WATER RESISTIVE VAPOR PERMEABLE BARRIER EQUIVALENT TO 2 LAYERS OF GRADE D PAPER
- 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.
- STUCCO APPLICATION MUST BE IAW R103.1.4 OF THE 11TH EDITION, FBCR 2020 OR EXCEPTION : APPLICATION INSTALLED IN ACCORDANCE WITH ASTM C 926
- UNDERLAYMENT REQUIREMENTS MUST BE IAW R305.1.1 OF THE 11TH EDITION, FBCR 2020 -  
1. Roof slopes from two units vertical in 12 units horizontal (17-percent slope), and less than four units vertical in 12 units horizontal (33-percent slope). Apply a 19-inch (483 mm) strip of underlayment felt parallel to and starting at the eaves, fastened sufficiently to hold in place. Starting at the eave, apply 36-inchwide (914 mm) sheets of underlayment, overlapping successive sheets 19 inches (483 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with corrosion-resistant fasteners with one row centered in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than Z E 1 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic Caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.  
2. Roof slopes of four units vertical in 12 units horizontal (33-percent slope) or greater. Underlayment shall be applied shingle fashion, parallel to and starting from the eave and lapped 4 inches (51 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with two staggered rows in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.




FRONT ELEVATION "F"  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



REAR ELEVATION  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)






EXTERIOR FINISH NOTES


1. LATH TO BE ATTACHED IAW R703.1.1 OF THE 1TH EDITION, FBCR, 2020 - ALL LATH AND LATH ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIAL. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED WITH 1-1/2 INCH 11 GAGE NAILS HAVING A 7/16 INCH HEAD, OR 7/8 INCH LONG 16 GAGE STAPLES SPACED NO MORE THAN 6 INCHES, OR AS OTHERWISE APPROVED.
2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R703.1.2 OF THE 1TH EDITION, FBCR, 2020
3. WEEP SCREED TO BE INSTALLED IAW R703.1.2.1 OF THE 1TH EDITION, FBCR, 2020- MINIMUM NO 26 GALVANIZED SHEET GAGE CORROSION-RESISTANT WEEP SCREED OR PLASTIC WEEP SCREED WITH A MINIMUM VERTICAL ATTACHMENT FLANGE OF 3-1/2 INCHES SHALL BE PROVIDED AT OR BELOW THE PLATE LINE ON EXTERIOR STUD WALLS IN ACCORDANCE WITH ASTM C 926. THE WEEP SCREED SHALL BE PLACED A MINIMUM OF 4 INCHES ABOVE THE EARTH OR 2 INCHES ABOVE PAVED AREAS. THE WEATHER RESISTANT BARRIER SHALL LAP THE ATTACHMENT FLANGE, THE EXTERIOR LATH SHALL COVER AND TERMINATE ON THE ATTACHMENT FLANGE OF THE WEEP SCREED.
4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R703.1.3 OF THE 1TH EDITION, FBCR, 2020- INSTALLED OVER WOOD BASED SHEATHING SHALL INCLUDE A WATER RESISTIVE VAPOR PERMEABLE BARRIER EQUIVALENT TO 2 LAYERS OF GRADE D PAPER
5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.
6. STUCCO APPLICATION MUST BE IAW R703.1.4 OF THE 1TH EDITION, FBCR, 2020 OR EXCEPTION : APPLICATION INSTALLED IN ACCORDANCE WITH ASTM C 926
7. UNDERLAYMENT REQUIREMENTS MUST BE IAW R905.1.1 OF THE 1TH EDITION, FBCR 2020 -
  1. Roof slopes from two units vertical in 12 units horizontal (17-percent slope), and less than four units vertical in 12 units horizontal (33-percent slope). Apply a 19-inch (483 mm) strip of underlayment felt parallel to and starting at the eaves, fastened sufficiently to hold in place. Starting at the eave, apply 36-inchwide (914 mm) sheets of underlayment, overlapping successive sheets 19 inches (483 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with corrosion-resistant fasteners with one row centered in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1/8 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic Caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.
  2. Roof slopes of four units vertical in 12 units horizontal (33-percent slope) or greater. Underlayment shall be applied shingle fashion, parallel to and starting from the eave and lapped 4 inches (51 mm), end laps shall be 6 inches and shall be offset by 6 feet. The underlayment shall be attached to a nailable deck with two staggered rows in the field of the sheet with a maximum fastener spacing of 12 inches (305 mm) o.c., and one row at the end and side laps fastened 6 inches (152 mm) o.c. Underlayment shall be attached using metal or plastic cap nails with a nominal cap diameter of not less than 1/8 inch. Metal caps shall have a thickness of not less than 32-gage sheet metal. Power-driven metal caps shall have a minimum thickness of 0.010 inch. Minimum thickness of the outside edge of plastic caps shall be 0.035 inch. The cap nail shank shall be not less than 0.083 inch for ring shank cap nails and 0.091 inch for smooth shank cap nails. Cap nail shank shall have a length sufficient to penetrate through the roof sheathing or not less than 3/4 inch into the roof sheathing.



FRONT ELEVATION "F"




REAR ELEVATION




NOTE: ADD N/A SMOOTH FINISH BANDS  
TO ALL WINDOWS, DOORS & S.G.D.S  
(TYP @ SIDES & REAR ELEVATIONS)

- EXTERIOR FINISH NOTES
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



LEFT ELEVATION "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



RIGHT ELEVATION "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 528 - 3000

4073 REDWOOD

EXTERIOR ELEVATION LEFT AND RIGHT

DATE 05-15-21

SCALE AS NOTED


DRAWN RDC

JOB N/A

SHEET 07D.0 OF SHEETS


REVISIONS	BY

- EXTERIOR FINISH NOTES
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



LEFT ELEVATION "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



RIGHT ELEVATION "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**THE PARK SERIES**


**SUPER BONUS OPTION**

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.


© COPYRIGHT 2015 Park Square Homes

REVISIONS		BY
Engineering By:		
DBE and C		
MICHAEL A. THOMPSON		
PE 47509		
PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC.		
5200 Vineland Road, Suite 200		
Orlando, Florida 32811		
Phone: (407) 529 - 3000		
Park Square HOMES		
EXTERIOR ELEVATION LEFT AND RIGHT		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	07D.1	
OF	SHEETS	

- EXTERIOR FINISH NOTES
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



LEFT ELEVATION "E"



RIGHT ELEVATION "E"


NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES  
Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.  
© COPYRIGHT 2015


REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
Park Square HOMES	
EXTERIOR ELEVATION LEFT AND RIGHT	
4073	REDWOOD
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	07E.0
OF	SHEETS

- EXTERIOR FINISH NOTES
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



LEFT ELEVATION "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



RIGHT ELEVATION "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**THE PARK SERIES**


**SUPER BONUS OPTION**

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
<b>Park Square HOMES</b>		
EXTERIOR ELEVATION LEFT AND RIGHT		
4073	REDWOOD	
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	07E.1	
OF	SHEETS	




- EXTERIOR FINISH NOTES
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 11TH EDITION, FBCR 2020
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 11TH EDITION, FBCR 2020
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 11TH EDITION, FBCR 2020
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 11TH EDITION, FBCR 2020
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



LEFT ELEVATION "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



RIGHT ELEVATION "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: ADD N/A SMOOTH FINISH BANDS TO ALL WINDOWS, DOORS & S.G.D.S (TYP @ SIDES & REAR ELEVATIONS)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

**THE PARK SERIES**

Engineering By: DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 528 - 3000


















**Park Square HOMES**

EXTERIOR ELEVATION LEFT AND RIGHT


4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 07F.1  
OF SHEETS

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$






**NOTE:** HANDRAIL CONTINUITY PER R311.1.2.2 -  
HANDRAILS FOR STAIRS SHALL BE CONTINUOUS FOR FULL LENGTH OF THE FLIGHT, FROM A POINT DIRECTLY ABOVE THE TOP RISER OF THE FLIGHT TO A POINT DIRECTLY ABOVE THE LOWEST RISER OF THE FLIGHT. HANDRAIL ENDS SHALL BE RETURNED OR SHALL TERMINATE IN NEWEL POST OR SAFETY TERMINALS. HANDRAILS ADJACENT TO A WALL SHALL HAVE A SPACE OF NO LESS THAN 1 1/2" (38MM) BETWEEN THE WALL AND THE HANDRAIL.

MECHANICAL/GENERAL NOTES

PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL  
1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE  
COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY  
CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR  
INSPECTION, SERVICE, REPAIR AND REPLACEMENT  
WITHOUT REMOVING PERMANENT CONSTRUCTION.

A) CHAPTER 13 OF THE FBC-R 2020 1TH  
SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE  
COMPLETELY BALANCED. ALL ROOMS ISOLATED  
FROM THE RETURN AIR SHALL BE PROVIDED WITH  
MEANS TO COMPLY WITH SECTION M1602 OF THE  
FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12- ALL 15A OR 20A, 120V  
BRANCH CIRCUITS SUPPLYING OUTLETS OR  
DEVICES IN THE FOLLOWING LOCATIONS REQUIRE  
AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING  
RMS, LIVING RMS, PARLORS, LIBRARIES,  
BEDROOMS, DENS, CLOSETS, SUNROOMS,  
RECREATION RMS, HALLWAYS OR SIMILAR AREAS  
SHALL BE PROTECTED BY A LISTED AFCI DEVICE  
OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V  
RECEPTACLES SHALL BE LISTED AS TAMPER  
RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY  
ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING  
AREAS, SHALL BE INTERCONNECTED, SHALL BE  
WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE  
SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/  
A BATTERY BACKUP. ALARMS MAY NOT BE  
CONNECTED WHERE ALARMS ARE WIRELESS & ALL  
ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3  
& R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION  
SOURCE TO BE ELEVATED SUCH THAT THE SOURCE  
OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR  
UNLESS WATER HEATER IS LISTED AS FLAMMABLE  
VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH  
ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING  
WATER HEATERS HAVING AN IGNITION SOURCE TO  
BE ELEVATED SUCH THAT THE SOURCE OF IGNITION  
IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS  
LISTED AS FLAMMABLE VAPOR IGNITION  
RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH  
SHALL BE DETERMINED BY ONE OF THE METHODS  
SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC  
2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN  
ACCORDANCE WITH NEC 250.53.(A)2)



NOTE: ALL ELECTRICAL MATERIALS AND INSTALLATIONS SHALL  
COMPLY WITH APPLICABLE PROVISIONS OF THE NATIONAL  
ELEC. CODE 250.52 (A)1 TO (6), LOCAL CODES, AND  
THE LOCAL POWER COMPANY.


250.52(A)1(2) Concrete-Encased Electrodes  
(1/8" x 20" (11X17) 1/4" x 20" (22X34)  
Concrete-encased electrodes can be horizontal or  
vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or  
vertical and must be at least 20 ft. long.

There are two types of concrete-encased  
electrodes: (1) steel reinforcing bars or rods which  
are not less than 1/8 inch in diameter and at least 20  
ft. long, encased in 2 inches of concrete; (2) 20 ft.  
of bare copper conductor not smaller than No. 4  
AWG encased in 2 inches of concrete.

The steel reinforcing rods must be in a location that  
is in direct contact with the earth. The reinforcing  
rods can be connected with ties/wires, and a single  
length of rod can be used as the concrete-encased  
electrode. The reinforcing rods cannot be coated  
with non-conductive material.

Section 250.50 requires a concrete-encased  
electrode to be connected to the grounding  
electrode system (GEC). Several states  
have modified this requirement to say a  
concrete-encased electrode must be used as a  
grounding electrode only if it is available. In those  
jurisdictions, if the footings or foundations have  
been poured before the electrical contractor  
arrives at the site and a reinforcing rod is not  
available for use as a grounding electrode, then a  
grounding connection to the reinforcing rod is not  
required.




BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: SEE FINAL COLOR SHEET FOR  
TV, FANS & PHONE LOCATIONS

ELECTRICAL LEGEND

⚡	SINGLE POLE SWITCH	⚡	OUTLET, TV/CABLE
⚡	THREE WAY SWITCH	⚡	OUTLET, PHONE
⚡	OUTLET 110-115	⚡	INTERCOM
⚡	OUT. 110-115, SPLIT WIRED	⚡	CHIMES
⚡	OUT. 110-115, W/ USB	⚡	SMOKE DETECTOR
⚡	OUT. 110-115, CLG. MOUNT.	⚡	CARBON MONOXIDE
⚡	OUT. 110-115, FLR. MOUNT.	⚡	PUSH BUTTON
⚡	SPCL. PURPOSE 220-240	⚡	EXHAUST FAN
⚡	LIGHT FIXT., CLG. MTD.	⚡	EX. FAN/LIGHT COMBO
⚡	LIGHT FIXT., WALL MTD.	⚡	DISPOSAL
⚡	LIGHT FIXT., RECESSED	⚡	ELECTRICAL PANEL
⚡	LIGHT FIXT., REC. ADJUST.	⚡	CEILING FAN, PREWIRE
⚡	LIGHT FIXT., PULL CHAIN	⚡	CEILING FAN, INSTALL
⚡	LIGHT FIXT., FLUORESCENT	⚡	ELECT. JUNCTION BOX
⚡	LIGHT FIXT., EXT. FLOODS	⚡	THERMOSTAT
⚡	LIGHT FIXT., EMERG. EXIT	⚡	DISCONNECT SWITCH
⚡	LIGHT FIXT., EXIT/BACKUP	⚡	ELEC. POWER METER

ELECTRICAL PLAN "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied  
or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
ELECTRICAL PLAN	
4073	REDWOOD
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	09D.0
OF	SHEETS



MECHANICAL/GENERAL NOTES

PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL  
1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE  
COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY  
CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR  
INSPECTION, SERVICE, REPAIR AND REPLACEMENT  
WITHOUT REMOVING PERMANENT CONSTRUCTION.

A) CHAPTER 13 OF THE FBC-R 2020 1TH  
SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE  
COMPLETELY BALANCED. ALL ROOMS ISOLATED  
FROM THE RETURN AIR SHALL BE PROVIDED WITH  
MEANS TO COMPLY WITH SECTION M1602 OF THE  
FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12- ALL 15A OR 20A, 120V  
BRANCH CIRCUITS SUPPLYING OUTLETS OR  
DEVICES IN THE FOLLOWING LOCATIONS REQUIRE  
AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING  
RMS, LIVING RMS, PARLORS, LIBRARIES,  
BEDROOMS, DENS, CLOSETS, SUNROOMS,  
RECREATION RMS, HALLWAYS OR SIMILAR AREAS  
SHALL BE PROTECTED BY A LISTED AFCI DEVICE  
OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V  
RECEPTACLES SHALL BE LISTED AS TAMPER  
RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY  
ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING  
AREAS, SHALL BE INTERCONNECTED, SHALL BE  
WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE  
SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/  
A BATTERY BACKUP. ALARMS MAY NOT BE  
CONNECTED WHERE ALARMS ARE WIRELESS & ALL  
ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3  
& R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION  
SOURCE TO BE ELEVATED SUCH THAT THE SOURCE  
OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR  
UNLESS WATER HEATER IS LISTED AS FLAMMABLE  
VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH  
ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING  
WATER HEATERS HAVING AN IGNITION SOURCE TO  
BE ELEVATED SUCH THAT THE SOURCE OF IGNITION  
IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS  
LISTED AS FLAMMABLE VAPOR IGNITION  
RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH  
SHALL BE DETERMINED BY ONE OF THE METHODS  
SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC  
2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN  
ACCORDANCE WITH NEC 250.53.(A)2)



NOTE: ALL ELECTRICAL MATERIALS AND INSTALLATIONS SHALL  
COMPLY WITH APPLICABLE PROVISIONS OF THE NATIONAL  
ELEC. CODE 250.52 (A)1 TO (6), LOCAL CODES, AND  
THE LOCAL POWER COMPANY.


250.52(A)1 Concrete-Encased Electrodes  
(1/8" x 20" (11X17) 1/4" x 20" (22X34)  
Concrete-encased electrodes can be horizontal or  
vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or  
vertical and must be at least 20 ft. long.

There are two types of concrete-encased  
electrodes: (1) steel reinforcing bars or rods which  
are not less than 1/2 inch in diameter and at least 20  
ft. long, encased in 2 inches of concrete; (2) 20 ft.  
of bare copper conductor not smaller than No. 4  
AWG encased in 2 inches of concrete.

The steel reinforcing rods must be in a location that  
is in direct contact with the earth. The reinforcing  
rods can be connected with ties/wires, and a single  
length of rod can be used as the concrete-encased  
electrode. The reinforcing rods cannot be coated  
with non-conductive material.

Section 250.50 requires a concrete-encased  
electrode to be connected to the grounding  
electrode system (GEC). Several states  
have modified this requirement to say a  
concrete-encased electrode must be used as a  
grounding electrode only if it is available. In those  
jurisdictions, if the footings or foundations have  
been poured before the electrical contractor  
arrives at the site and a reinforcing rod is not  
available for use as a grounding electrode, then a  
grounding connection to the reinforcing rod is not  
required.




BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



NOTE: SEE FINAL COLOR SHEET FOR  
TV, FANS & PHONE LOCATIONS

ELECTRICAL LEGEND

⚡	SINGLE POLE SWITCH	⚡	OUTLET, TV/CABLE
⚡	THREE WAY SWITCH	⚡	OUTLET, PHONE
⚡	OUTLET 110-115	⚡	INTERCOM
⚡	OUT. 110-115, SPLIT WIRED	⚡	CHIMES
⚡	OUT. 110-115, W/ USB	⚡	SMOKE DETECTOR
⚡	OUT. 110-115, CLG. MOUNT.	⚡	CARBON MONOXIDE
⚡	OUT. 110-115, FLR. MOUNT.	⚡	PUSH BUTTON
⚡	SPCL. PURPOSE 220-240	⚡	EXHAUST FAN
⚡	LIGHT FIXT., CLG. MTD.	⚡	EX. FAN/LIGHT COMBO
⚡	LIGHT FIXT., WALL MTD.	⚡	DISPOSAL
⚡	LIGHT FIXT., RECESSED	⚡	ELECTRICAL PANEL
⚡	LIGHT FIXT., REC. ADJUST.	⚡	CEILING FAN, PREWIRE
⚡	LIGHT FIXT., PULL CHAIN	⚡	CEILING FAN, INSTALL
⚡	LIGHT FIXT., FLUORESCENT	⚡	ELECT. JUNCTION BOX
⚡	LIGHT FIXT., EXT. FLOODS	⚡	THERMOSTAT
⚡	LIGHT FIXT., EMERG. EXIT	⚡	DISCONNECT SWITCH
⚡	LIGHT FIXT., EXIT/BACKUP	⚡	ELEC. POWER METER

ELECTRICAL PLAN "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
ELECTRICAL PLAN	
4073	REDWOOD
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	09E.0
OF	SHEETS













MECHANICAL/GENERAL NOTES  
PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL  
1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE  
COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY  
CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR  
INSPECTION, SERVICE, REPAIR AND REPLACEMENT  
WITHOUT REMOVING PERMANENT CONSTRUCTION.  
A) CHAPTER 13 OF THE FBC-R 2020 1TH  
SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE  
COMPLETELY BALANCED. ALL ROOMS ISOLATED  
FROM THE RETURN AIR SHALL BE PROVIDED WITH  
MEANS TO COMPLY WITH SECTION M1602 OF THE  
FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12-ALL 15A OR 20A, 120V  
BRANCH CIRCUITS SUPPLYING OUTLETS OR  
DEVICES IN THE FOLLOWING LOCATIONS REQUIRE  
AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING  
RMS, LIVING RMS, PARLORS, LIBRARIES,  
BEDROOMS, DENS, CLOSETS, SUNROOMS,  
RECREATION RMS, HALLWAYS OR SIMILAR AREAS  
SHALL BE PROTECTED BY A LISTED AFCI DEVICE  
OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V  
RECEPTACLES SHALL BE LISTED AS TAMPER  
RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY  
ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING  
AREAS, SHALL BE INTERCONNECTED, SHALL BE  
WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE  
SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/  
A BATTERY BACKUP. ALARMS MAY NOT BE  
CONNECTED WHERE ALARMS ARE WIRELESS & ALL  
ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3  
& R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION  
SOURCE TO BE ELEVATED SUCH THAT THE SOURCE  
OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR  
UNLESS WATER HEATER IS LISTED AS FLAMMABLE  
VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH  
ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING  
WATER HEATERS HAVING AN IGNITION SOURCE TO  
BE ELEVATED SUCH THAT THE SOURCE OF IGNITION  
IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS  
LISTED AS FLAMMABLE VAPOR IGNITION  
RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH  
SHALL BE DETERMINED BY ONE OF THE METHODS  
SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC  
2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN  
ACCORDANCE WITH NEC 250.53.(AX2)



NOTE:  
N.T.S.  
ELECTRICAL MATERIALS AND INSTALLATIONS SHALL  
COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL  
ELEC. CODE 250.52.(AX1) TO (6), LOCAL CODES, AND  
THE LOCAL POWER COMPANY.


250.52.(AX3) Concrete-Encased Electrode.  
Concrete-encased electrodes can be horizontal or  
vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or  
vertical and must be at least 20 ft. long.

There are two types of concrete-encased  
electrodes: (1) steel reinforcing bars or rods which  
are not less than 1/2 inch in diameter and at least 20  
ft. long, encased in 2 inches of concrete; (2) 20 ft.  
of bare copper conductor not smaller than No. 4  
AWG encased in 2 inches of concrete.



The steel reinforcing rods must be in a location that  
is 1/2 inch (12.7 mm) from the concrete. The reinforcing  
rods can be connected with tie wires, and a single  
length of rod can be used as the concrete-encased  
electrode. The reinforcing rods cannot be coated  
with non-conductive material.

Section 250.50 requires a concrete-encased  
electrode to be connected to the grounding  
electrode system if it is present. Several states  
have modified this requirement to say a  
concrete-encased electrode must be used as a  
grounding electrode only if it is available. In those  
jurisdictions, if the footings or foundations have  
been poured before the electrical contractor  
arrives on the site, and a reinforcing rod is not  
available for use as a grounding electrode, then a  
grounding connection to the reinforcing rod is not  
required.




SHOWER OPT.  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


UPPER ELECTRICAL PLAN "D"  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.  
1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION  
1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.  
1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

ELECTRICAL LEGEND			
⚡	SINGLE POLE SWITCH	⬅	OUTLET, TV/CABLE
⚡	THREE WAY SWITCH	⬅	OUTLET, PHONE
⊕	OUTLET 110-115	☐	INTERCOM
⊕	OUT. 110-115, SPLIT WIRED	☐	CHIMES
⊕	OUT. 110-115, W/ USB	☐	SMOKE DETECTOR
⊕	OUT. 110-115, CLG. MOUNT.	☐	CARBON MONOXIDE
⊕	OUT. 110-115, FLR. MOUNT.	☐	PUSH BUTTON
⊕	SPCL. PURPOSE 220-240	☐	EXHAUST FAN
☐	LIGHT FIXT., CLG. MTD.	☐	EX. FAN/LIGHT COMBO
☐	LIGHT FIXT., WALL MTD.	☐	DISPOSAL
☐	LIGHT FIXT., RECESSED	☐	ELECTRICAL PANEL
☐	LIGHT FIXT., REC. ADJUST.	☐	CEILING FAN, PREWIRE
☐	LIGHT FIXT., PULL CHAIN	☐	CEILING FAN, INSTALL
☐	LIGHT FIXT., FLUORESCENT	☐	ELECT. JUNCTION BOX
☐	LIGHT FIXT., EXT. FLOODS	☐	THERMOSTAT
☐	LIGHT FIXT., EMERG. EXIT	☐	DISCONNECT SWITCH
☐	LIGHT FIXT., EXIT/BACKUP	☐	ELEC. POWER METER

THE PARK SERIES

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park Square  
HOMES

UPPER ELECTRICAL PLAN

4073  
REDWOOD

DATE 05-15-21

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET 10D.1

OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

SUPER BONUS OPTION

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

© COPYRIGHT 2015

MECHANICAL/GENERAL NOTES  
PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL

1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR INSPECTION, SERVICE, REPAIR AND REPLACEMENT WITHOUT REMOVING PERMANENT CONSTRUCTION.

A) CHAPTER 13 OF THE FBC-R 2020 1TH SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE COMPLETELY BALANCED. ALL ROOMS ISOLATED FROM THE RETURN AIR SHALL BE PROVIDED WITH MEANS TO COMPLY WITH SECTION M1602 OF THE FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12-ALL 15A OR 20A, 120V BRANCH CIRCUITS SUPPLYING OUTLETS OR DEVICES IN THE FOLLOWING LOCATIONS REQUIRE AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING RMS, LIVING RMS, PARLORS, LIBRARIES, BEDROOMS, DENS, CLOSETS, SUNROOMS, RECREATION RMS, HALLWAYS OR SIMILAR AREAS SHALL BE PROTECTED BY A LISTED AFCI DEVICE OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V RECEPTACLES SHALL BE LISTED AS TAMPER RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING AREAS, SHALL BE INTERCONNECTED, SHALL BE WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/ A BATTERY BACKUP. ALARMS MAY NOT BE CONNECTED WHERE ALARMS ARE WIRELESS & ALL ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3 & R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS WATER HEATER IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH SHALL BE DETERMINED BY ONE OF THE METHODS SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC 2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN ACCORDANCE WITH NEC 250.53(A)2)



ELECTRICAL RISER DIAGRAM

NOTE: N.T.S.  
ELECTRICAL MATERIALS AND INSTALLATIONS SHALL COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL ELEC. CODE 250.52(A)1) TO (6), LOCAL CODES, AND THE LOCAL POWER COMPANY.


250.52(A)3) Concrete-Encased Electrode.  
Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

There are two types of concrete-encased electrodes: (1) steel reinforcing bars or rods which are not less than 1/2 inch in diameter and at least 20 ft. long, encased in 2 inches of concrete; (2) 20 ft. of bare copper conductor not smaller than No. 4 AWG encased in 2 inches of concrete.

The steel reinforcing rods must be in a location that is in direct contact with the earth. The reinforcing rods can be connected with tie wires, and a single length of rod can be used as the concrete-encased electrode. The reinforcing rods cannot be coated with non-conductive material.

Section 250.50 requires a concrete-encased electrode to be connected to the grounding electrode system if it is present. Several states have modified this requirement to say a concrete-encased electrode must be used as a grounding electrode only if it is available. In those jurisdictions, if the footings or foundations have been poured before the electrical contractor arrives on the site, and a reinforcing rod is not available for use as a grounding electrode, then a grounding connection to the reinforcing rod is not required.





SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


UPPER ELECTRICAL PLAN "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

ELECTRICAL LEGEND

⚡	SINGLE POLE SWITCH	⬅	OUTLET, TV/CABLE
⚡	THREE WAY SWITCH	⬅	OUTLET, PHONE
⊕	OUTLET 110-115	☐	INTERCOM
⊕	OUT. 110-115, SPLIT WIRED	☐	CHIMES
⊕	OUT. 110-115, W/ USB	☐	SMOKE DETECTOR
⊕	OUT. 110-115, CLG. MOUNT.	☐	CARBON MONOXIDE
⊕	OUT. 110-115, FLR. MOUNT.	☐	PUSH BUTTON
⊕	SPCL. PURPOSE 220-240	☐	EXHAUST FAN
☐	LIGHT FIXT., CLG. MTD.	☐	EX. FAN/LIGHT COMBO
☐	LIGHT FIXT., WALL MTD.	☐	DISPOSAL
☐	LIGHT FIXT., RECESSED	☐	ELECTRICAL PANEL
☐	LIGHT FIXT., REC. ADJUST.	☐	CEILING FAN, PREWIRE
☐	LIGHT FIXT., PULL CHAIN	☐	CEILING FAN, INSTALL
☐	LIGHT FIXT., FLUORESCENT	☐	ELECT. JUNCTION BOX
☐	LIGHT FIXT., EXT. FLOODS	☐	THERMOSTAT
☐	LIGHT FIXT., EMERG. EXIT	☐	DISCONNECT SWITCH
☐	LIGHT FIXT., EXIT/BACKUP	☐	ELEC. POWER METER

THE PARK SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

OPT. BEDROOM 7/ BATH 6, LOFT/ OPT. MEDIA

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vireland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

UPPER ELECTRICAL PLAN

4073

REDWOOD

DATE 05-15-21

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET 10D.2

OF SHEETS

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.



MECHANICAL/GENERAL NOTES

PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL  
1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR INSPECTION, SERVICE, REPAIR AND REPLACEMENT WITHOUT REMOVING PERMANENT CONSTRUCTION.  
A) CHAPTER 13 OF THE FBC-R 2020 1TH SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE COMPLETELY BALANCED. ALL ROOMS ISOLATED FROM THE RETURN AIR SHALL BE PROVIDED WITH MEANS TO COMPLY WITH SECTION M1602 OF THE FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12-ALL 15A OR 20A, 120V BRANCH CIRCUITS SUPPLYING OUTLETS OR DEVICES IN THE FOLLOWING LOCATIONS REQUIRE AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING RMS, LIVING RMS, PARLORS, LIBRARIES, BEDROOMS, DENS, CLOSETS, SUNROOMS, RECREATION RMS, HALLWAYS OR SIMILAR AREAS SHALL BE PROTECTED BY A LISTED AFCI DEVICE OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V RECEPTACLES SHALL BE LISTED AS TAMPER RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING AREAS, SHALL BE INTERCONNECTED, SHALL BE WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/ A BATTERY BACKUP. ALARMS MAY NOT BE CONNECTED WHERE ALARMS ARE WIRELESS & ALL ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3 & R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS WATER HEATER IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH SHALL BE DETERMINED BY ONE OF THE METHODS SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC 2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN ACCORDANCE WITH NEC 250.53.(AX2)




NOTE: N.T.S.  
ELECTRICAL MATERIALS AND INSTALLATIONS SHALL COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL ELEC. CODE 250.52.(AX1) TO (6), LOCAL CODES, AND THE LOCAL POWER COMPANY.

250.52.(AX3) Concrete-Encased Electrode.  
Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.  
There are two types of concrete-encased electrodes: (1) steel reinforcing bars or rods which are not less than 1/2 inch in diameter and at least 20 ft. long, encased in 2 inches of concrete; (2) 20 ft. of bare copper conductor not smaller than No. 4 AWG encased in 2 inches of concrete.

The steel reinforcing rods must be in a location that is 18" above the finished floor. The reinforcing rods can be connected with tie wires, and a single length of rod can be used as the concrete-encased electrode. The reinforcing rods cannot be coated with non-conductive material.

Section 250.50 requires a concrete-encased electrode to be connected to the grounding electrode system if it is present. Several states have modified this requirement to say a concrete-encased electrode must be used as a grounding electrode only if it is available. In those jurisdictions, if the footings or foundations have been poured before the electrical contractor arrives on the site, and a reinforcing rod is not available for use as a grounding electrode, then a grounding connection to the reinforcing rod is not required.





SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


UPPER ELECTRICAL PLAN "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

ELECTRICAL LEGEND

⚡	SINGLE POLE SWITCH	⬅	OUTLET, TV/CABLE
⚡	THREE WAY SWITCH	⬅	OUTLET, PHONE
⊕	OUTLET 110-115	☐	INTERCOM
⊕	OUT. 110-115, SPLIT WIRED	☐	CHIMES
⊕	OUT. 110-115, W/ USB	☐	SMOKE DETECTOR
⊕	OUT. 110-115, CLG. MOUNT.	☐	CARBON MONOXIDE
⊕	OUT. 110-115, FLR. MOUNT.	☐	PUSH BUTTON
⊕	SPCL. PURPOSE 220-240	☐	EXHAUST FAN
☐	LIGHT FIXT., CLG. MTD.	☐	EX. FAN/LIGHT COMBO
☐	LIGHT FIXT., WALL MTD.	☐	DISPOSAL
☐	LIGHT FIXT., RECESSED	☐	ELECTRICAL PANEL
☐	LIGHT FIXT., REC. ADJUST.	☐	CEILING FAN, PREWIRE
☐	LIGHT FIXT., PULL CHAIN	☐	CEILING FAN, INSTALL
☐	LIGHT FIXT.,FLUORESCENT	☐	ELECT. JUNCTION BOX
☐	LIGHT FIXT., EXT. FLOODS	☐	THERMOSTAT
☐	LIGHT FIXT., EMERG. EXIT	☐	DISCONNECT SWITCH
☐	LIGHT FIXT., EXIT/BACKUP	☐	ELEC. POWER METER

THE PARK SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

SUPER BONUS OPTION

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
UPPER ELECTRICAL PLAN	
4073	REDWOOD
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	10E.1
OF	SHEETS







MECHANICAL/GENERAL NOTES

PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL  
1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR INSPECTION, SERVICE, REPAIR AND REPLACEMENT WITHOUT REMOVING PERMANENT CONSTRUCTION.  
A) CHAPTER 13 OF THE FBC-R 2020 1TH SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE COMPLETELY BALANCED. ALL ROOMS ISOLATED FROM THE RETURN AIR SHALL BE PROVIDED WITH MEANS TO COMPLY WITH SECTION M1602 OF THE FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12-ALL 15A OR 20A, 120V BRANCH CIRCUITS SUPPLYING OUTLETS OR DEVICES IN THE FOLLOWING LOCATIONS REQUIRE AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING RMS, LIVING RMS, PARLORS, LIBRARIES, BEDROOMS, DENS, CLOSETS, SUNROOMS, RECREATION RMS, HALLWAYS OR SIMILAR AREAS SHALL BE PROTECTED BY A LISTED AFCI DEVICE OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V RECEPTACLES SHALL BE LISTED AS TAMPER RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING AREAS, SHALL BE INTERCONNECTED, SHALL BE WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/ A BATTERY BACKUP. ALARMS MAY NOT BE CONNECTED WHERE ALARMS ARE WIRELESS & ALL ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3 & R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS WATER HEATER IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH SHALL BE DETERMINED BY ONE OF THE METHODS SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC 2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN ACCORDANCE WITH NEC 250.53.(AX2)



NOTE: N.T.S.  
ELECTRICAL MATERIALS AND INSTALLATIONS SHALL COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL ELEC. CODE 250.52.(AX1) TO (6), LOCAL CODES, AND THE LOCAL POWER COMPANY


250.52.(AX3) Concrete-Encased Electrode. Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

There are two types of concrete-encased electrodes: (1) steel reinforcing bars or rods which are not less than 1/2 inch in diameter and at least 20 ft. long, encased in 2 inches of concrete; (2) 20 ft. of bare copper conductor not smaller than No. 4 AWG encased in 2 inches of concrete.



**BR. 6/BA. 5 OPTION**  
The steel reinforcing rods must be in a location that is 18" above the finished floor. The reinforcing rods can be connected with tie wires, and a single length of rod can be used as the concrete-encased electrode. The reinforcing rods cannot be coated with non-conductive material.

Section 250.50 requires a concrete-encased electrode to be connected to the grounding electrode system if it is present. Several states have modified this requirement to say a concrete-encased electrode must be used as a grounding electrode only if it is available. In those jurisdictions, if the footings or foundations have been poured before the electrical contractor arrives on the site, and a reinforcing rod is not available for use as a grounding electrode, then a grounding connection to the reinforcing rod is not required.




SHOWER OPT.  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


UPPER ELECTRICAL PLAN "F"  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



BA. 4 OPTION  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

ELECTRICAL LEGEND			
	SINGLE POLE SWITCH		OUTLET, TV/CABLE
	THREE WAY SWITCH		OUTLET, PHONE
	OUTLET 110-115		INTERCOM
	OUT. 110-115, SPLIT WIRED		CHIMES
	OUT. 110-115, W/ USB		SMOKE DETECTOR
	OUT. 110-115, CLG. MOUNT.		CARBON MONOXIDE
	OUT. 110-115, FLR. MOUNT.		PUSH BUTTON
	SPCL. PURPOSE 220-240		EXHAUST FAN
	LIGHT FIXT., CLG. MTD.		EX. FAN/LIGHT COMBO
	LIGHT FIXT., WALL MTD.		DISPOSAL
	LIGHT FIXT., RECESSED		ELECTRICAL PANEL
	LIGHT FIXT., REC. ADJUST.		CEILING FAN, PREWIRE
	LIGHT FIXT., PULL CHAIN		CEILING FAN, INSTALL
	LIGHT FIXT., FLUORESCENT		ELECT. JUNCTION BOX
	LIGHT FIXT., EXT. FLOODS		THERMOSTAT
	LIGHT FIXT., EMERG. EXIT		DISCONNECT SWITCH
	LIGHT FIXT., EXIT/BACKUP		ELEC. POWER METER

MECHANICAL/GENERAL NOTES  
PER 1TH ED. 2020 FLA BLD. CODE-RESIDENTIAL

1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1

2.)APPLIANCES SHALL BE ACCESSIBLE FOR INSPECTION, SERVICE, REPAIR AND REPLACEMENT WITHOUT REMOVING PERMANENT CONSTRUCTION.

A) CHAPTER 13 OF THE FBC-R 2020 1TH SECTION M1305.1

3.) AIR CONDITIONING SYSTEM SHALL BE COMPLETELY BALANCED. ALL ROOMS ISOLATED FROM THE RETURN AIR SHALL BE PROVIDED WITH MEANS TO COMPLY WITH SECTION M1602 OF THE FBCR CODE 2020 1TH EDITION.

4.) IAW NEC 2017- 210.12-ALL 15A OR 20A, 120V BRANCH CIRCUITS SUPPLYING OUTLETS OR DEVICES IN THE FOLLOWING LOCATIONS REQUIRE AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING RMS, LIVING RMS, PARLORS, LIBRARIES, BEDROOMS, DENS, CLOSETS, SUNROOMS, RECREATION RMS, HALLWAYS OR SIMILAR AREAS SHALL BE PROTECTED BY A LISTED AFCI DEVICE OF THE COMBINATION TYPE.

5.) IAW NEC 2017- 406.12, ALL 15A AND 20A, 125V RECEPTACLES SHALL BE LISTED AS TAMPER RESISTANT.

6.) ALL OUTLETS IN BATHROOMS AND LAUNDRY ROOM SHALL BE GFCI

7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING AREAS, SHALL BE INTERCONNECTED, SHALL BE WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/ A BATTERY BACKUP. ALARMS MAY NOT BE CONNECTED WHERE ALARMS ARE WIRELESS & ALL ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3 & R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:

BRK: SMOKE-9120B, C/O- SC9120B  
KIDDE: SMOKE-21007581, C/O 21006377-N


8.) ALL WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS WATER HEATER IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED. P2801.1

9.) ALL EQUIPMENT & APPLIANCES, INCLUDING WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2020, 1TH ED.

10.)THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH SHALL BE DETERMINED BY ONE OF THE METHODS SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3

11.) ALL ELECTRICAL WORK TO BE DONE PER **NEC 2017**

12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN ACCORDANCE WITH NEC 250.53(A)2)



ELECTRICAL RISER DIAGRAM

NOTE: N.T.S.  
ELECTRICAL MATERIALS AND INSTALLATIONS SHALL COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL ELEC. CODE 250.52(A)1) TO (6), LOCAL CODES, AND THE LOCAL POWER COMPANY.


250.52(A)3) Concrete-Encased Electrode.  
Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

There are two types of concrete-encased electrodes: (1) steel reinforcing bars or rods which are not less than 1/2 inch in diameter and at least 20 ft. long, encased in 2 inches of concrete; (2) 20 ft. of bare copper conductor not smaller than No. 4 AWG encased in 2 inches of concrete.


The steel reinforcing rods must be in a location that is in direct contact with the earth. The reinforcing rods can be connected with tie wires, and a single length of rod can be used as the concrete-encased electrode. The reinforcing rods cannot be coated with non-conductive material.

Section 250.50 requires a concrete-encased electrode to be connected to the grounding electrode system if it is present. Several states have modified this requirement to say a concrete-encased electrode must be used as a grounding electrode only if it is available. In those jurisdictions, if the footings or foundations have been poured before the electrical contractor arrives on the site, and a reinforcing rod is not available for use as a grounding electrode, then a grounding connection to the reinforcing rod is not required.




SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




UPPER ELECTRICAL PLAN "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

ELECTRICAL LEGEND

	SINGLE POLE SWITCH		OUTLET, TV/CABLE
	THREE WAY SWITCH		OUTLET, PHONE
	OUTLET 110-115		INTERCOM
	OUT. 110-115, SPLIT WIRED		CHIMES
	OUT. 110-115, W/ USB		SMOKE DETECTOR
	OUT. 110-115, CLG. MOUNT.		CARBON MONOXIDE
	OUT. 110-115, FLR. MOUNT.		PUSH BUTTON
	SPCL. PURPOSE 220-240		EXHAUST FAN
	LIGHT FIXT., CLG. MTD.		EX. FAN/LIGHT COMBO
	LIGHT FIXT., WALL MTD.		DISPOSAL
	LIGHT FIXT., RECESSED		ELECTRICAL PANEL
	LIGHT FIXT., REC. ADJUST.		CEILING FAN, PREWIRE
	LIGHT FIXT., PULL CHAIN		CEILING FAN, INSTALL
	LIGHT FIXT.,FLUORESCENT		ELECT. JUNCTION BOX
	LIGHT FIXT., EXT. FLOODS		THERMOSTAT
	LIGHT FIXT., EMERG. EXIT		DISCONNECT SWITCH
	LIGHT FIXT., EXIT/BACKUP		ELEC. POWER METER

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

OPT. BEDROOM 7/ BATH 6, LOFT/ OPT. MEDIA

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

Engineering By  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square**  
HOMES

THE PARK SERIES


UPPER ELECTRICAL PLAN

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 10F.2  
OF SHEETS



1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 11TH EDITION (2020) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TP1/WTCA BC51 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R905.1.1 -  
Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

REVISIONS	B
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	

**A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.**  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

## TRUSS LAYOUT

4073

REDWOOD

DATE 05-15-

SCALE AS NOTE



DRAWN RE

JOB	N.
-----	----

SHEET

11D.0  
OF SHEET

1. TYPICAL ROOF GABLE OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 11TH EDITION (2020) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TP/WTCA BCSI 1.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R905.1.1 -  
Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1


$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

**Park Square HOMES**


# TRUSS LAYOUT

4073

REDWOOD

DATE	05-15-2
SCALE AS NOTED	
DRAWN	RDC
JOB	N/A
SHEET	
11D.0	
OF	SHEETS

1. TYPICAL ROOF GABLE OVERHANG  
TO BE **8"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG  
TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND  
ROOFING AS PER NATIONAL ROOFING  
AND SHEET METAL ASSOC. STANDARDS  
AND/ OR ACCEPTABLE INDUSTRY  
PRACTICE AND IN ACCORDANCE WITH  
THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS,  
HEADERS, ETC. TO BE SIZED BY TRUSS  
MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PRE-  
VENT ROTATION & PROVIDE LATERAL  
STABILITY IN ACCORDANCE WITH THE  
REQUIREMENTS SPECIFIED IN THE  
CONSTRUCTION DOCUMENTS FOR  
BUILDING & ON THE INDIVIDUAL TRUSS  
DESIGN DRAWINGS. IN THE ABSENCE OF  
SPECIFIC BRACING REQUIREMENTS,  
TRUSSES SHALL BE BRACED IN  
ACCORDANCE WITH TPI/WTCA BC91 I.
6. REFER TO TRUSS MANUFACTURER'S  
DRAWINGS FOR TRUSS PLACEMENT &  
TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 11TH  
EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 11TH  
EDITION R305.1.1.1

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

THIS STRUCTURE IS DESIGNED TO WITHSTAND HURRICANE WINDS PER THE 10TH EDITION, 2020 OF THE FLORIDA BUILDING CODE. RESIDENTIAL AND IS CERTIFIED AS SUCH.

**SUPER BONUS OPTION**

**THE PARK SERIES**

Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied, reproduced, or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes. © COPYRIGHT 2015

DATE 05-15-2011  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET  
11D.1  
OF SHEETS

4073  
REDWOOD


## TRUSS LAYOUT

**Park Square HOMES**  
A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

REVISIONS	BY
1	1

1. TYPICAL ROOF GABLE OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 11TH EDITION (2020) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC91.1.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.1.1 -  
Underlayment materials required to comply with ASTM D226, D4869 at Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R305.1.1. Underlayment shall be applied and attached in accordance with Table R305.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R305.1.1.]



TRUSS LAYOUT "D"

**Park Square HOMES**

# TRUSS LAYOUT

4073

REDWOOD

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied, reproduced, or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	REVISIONS	B

**A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000**

DATE 05-15-

SCALE AS NOTE



DRAWN RD

JOB	N.
-----	----

SHEET

OF SHEET

1. TYPICAL ROOF GABLE OVERHANG  
TO BE **8"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG  
TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND  
ROOFING AS PER NATIONAL ROOFING  
AND SHEET METAL ASSOC. STANDARDS  
AND/ OR ACCEPTABLE INDUSTRY  
PRACTICE AND IN ACCORDANCE WITH  
THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS,  
HEADERS, ETC. TO BE SIZED BY TRUSS  
MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PRE-  
VENT ROTATION & PROVIDE LATERAL  
STABILITY IN ACCORDANCE WITH THE  
REQUIREMENTS SPECIFIED IN THE  
CONSTRUCTION DOCUMENTS FOR  
BUILDING & ON THE INDIVIDUAL TRUSS  
DESIGN DRAWINGS. IN THE ABSENCE OF  
SPECIFIC BRACING REQUIREMENTS,  
TRUSSES SHALL BE BRACED IN  
ACCORDANCE WITH TPI/WTCA BC91 I.
6. REFER TO TRUSS MANUFACTURER'S  
DRAWINGS FOR TRUSS PLACEMENT &  
TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 1TH  
EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 1TH  
EDITION R305.1.1.1



TRUSS LAYOUT "E"  
1/8"=1'-0" (11x17) 1/4"=1'-0" (22x34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

# THE PARK SERIES

REVISIONS	B
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

## TRUSS LAYOUT

4073

REDWOOD

DATE 05-15-2011

SCALE AS NOTED

DRAWN	RDC
-------	-----



JOB	N/A
-----	-----

SHEET

11E O

OF SHEETS

1. TYPICAL ROOF GABLE OVERHANG TO BE **8'** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12'** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC31 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.1


$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied, reproduced, or changed in any manner or form whatsoever nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

# TRUSS LAYOUT

4013

REDWOOD

DATE 05-15-2011

SCALE AS NOTED


DRAWN RDC

JOB	N/A
-----	-----

SHEET

11E.0  
OF SHEETS

1. TYPICAL ROOF GABLE OVERHANG  
TO BE **8"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG  
TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND  
ROOFING AS PER NATIONAL ROOFING  
AND SHEET METAL ASSOC. STANDARDS  
AND/ OR ACCEPTABLE INDUSTRY  
PRACTICE AND IN ACCORDANCE WITH  
THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS,  
HEADERS, ETC. TO BE SIZED BY TRUSS  
MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PRE-  
VENT ROTATION & PROVIDE LATERAL  
STABILITY IN ACCORDANCE WITH THE  
REQUIREMENTS SPECIFIED IN THE  
CONSTRUCTION DOCUMENTS FOR  
BUILDING & ON THE INDIVIDUAL TRUSS  
DESIGN DRAWINGS. IN THE ABSENCE OF  
SPECIFIC BRACING REQUIREMENTS,  
TRUSSES SHALL BE BRACED IN  
ACCORDANCE WITH TPI/WTCA BC91 I.
6. REFER TO TRUSS MANUFACTURER'S  
DRAWINGS FOR TRUSS PLACEMENT &  
TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 1TH  
EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 1TH  
EDITION R305.1.1.1

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

THE PARK SERIES

DATE	05-15-20
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	11E.1
OF	SHEETS

4073  
REDWOOD

## TRUSS LAYOUT

**Park Square HOMES**  
A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

REVISIONS	BY



<p><b>Engineering By:</b>  <b>DBE and C</b>  <b>MICHAEL A. THOMPSON</b>  <b>PE 47509</b>  <b>PHONE 407-721-2292</b></p>
---

# NOTES

1. TYPICAL ROOF GABLE OVERHANG TO BE 8" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC51.1.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.11.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.11.1

## TRUSS LAYOUT "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





- NOTES
1. TYPICAL ROOF GABLE OVERHANG TO BE 8" UNLESS OTHERWISE NOTED.

2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.

3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.

4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.


5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1.1.

6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.

7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.1.1.2 OR SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.1.1.1

TRUSS LAYOUT "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



12D.0  
OF SHEETS

### ATTIC VENTILATION CALCULATIONS

PER FBC2020 1TH EDITION R306: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{3276 \text{ S.F.}}{300} = 10.92 \text{ S.F.}$  NET FREE VENT. REQUIRED

UPPER PORTION VENTILATION TOTAL:----- **5.82 S.F.**  
PROVIDED W/OFF RIDGE VENTS: **6** VENTS @ **.97 S.F.** /VENT.  
(VENT TYPE: LOMANCO MODEL T70-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL:----- **6.09 S.F.**  
PROVIDED W/ VENTILATED SOFFITS @ EAVE:--  
( **70 L.F.** @ **0.087 S.F.** VENTING PER L.F.)

UPPER PORTION PERCENTAGE: **50%**  
LOWER PORTION PERCENTAGE: **50%**

### NOTES

1. TYPICAL ROOF GABLE OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 1TH EDITION (2020) FLORIDA RESIDENTIAL CODE.

4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.


5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC61 I.

6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.

7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1 - Underlayment materials required to comply with ASTM D226, D4869 of Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R305.1.1. Underlayment shall be applied and attached in accordance with Table R305.1.1.

8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE

9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R305.1.1.



TRUSS LAYOUT "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THE PARK SERIES

TRUSS LAYOUT

4073

REDWOOD

REVISIONS BY

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

TRUSS LAYOUT

4073

REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 12D.0  
OF SHEETS

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH


© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

PER FBC2020 7TH EDITION R806: MIN. 40% - MAX. 50%  
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF  
ATTIC SPACE AND THE BALANCE TO BE IN LOWER  
PORTION (EAVES).

TOTAL VENTED SPACE:  $\frac{3276 \text{ S.F.}}{300} = 10.92 \text{ S.F.}$  NET FREE VENT. REQUIRED

UPPER PORTION PERCENTAGE:	<u>50%</u>
LOWER PORTION PERCENTAGE:	<u>50%</u>

1. TYPICAL ROOF GABLE OVERHANG TO BE **8'** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12'** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/UTCA BC3I 1.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.1

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

THE PARK SERIES

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

**A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000**

**Park Square HOMES**

## TRUSS LAYOUT

4073

REDWOOD

DATE 05-15-2

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET

12D.1  
OF SHEETS


DATE	05-15-20
SCALE AS NOTED	
DRAWN	RDC
JOB	N/A
SHEET	
12D.0	
OF	SHEETS

PER FBC2020 7TH EDITION R806: MIN. 40% - MAX. 50%  
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF  
ATTIC SPACE AND THE BALANCE TO BE IN LOWER  
PORTION (EAVES).

TOTAL VENTED SPACE:  $\frac{3276 \text{ S.F.}}{300} = 10.92 \text{ S.F.}$  NET FREE VENT. REQUIRED

UPPER PORTION PERCENTAGE:	<u>50%</u>
LOWER PORTION PERCENTAGE:	<u>50%</u>

1. TYPICAL ROOF GABLE OVERHANG  
TO BE **8'** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG  
TO BE **12'** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND  
ROOFING AS PER NATIONAL ROOFING  
AND SHEET METAL ASSOC. STANDARDS  
AND/ OR ACCEPTABLE INDUSTRY  
PRACTICE AND IN ACCORDANCE WITH  
THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS,  
HEADERS, ETC. TO BE SIZED BY TRUSS  
MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PRE-  
VENT ROTATION & PROVIDE LATERAL  
STABILITY IN ACCORDANCE WITH THE  
REQUIREMENTS SPECIFIED IN THE  
CONSTRUCTION DOCUMENTS FOR  
BUILDING & ON THE INDIVIDUAL TRUSS  
DESIGN DRAWINGS. IN THE ABSENCE OF  
SPECIFIC BRACING REQUIREMENTS,  
TRUSSES SHALL BE BRACED IN  
ACCORDANCE WITH TPI/WTCA BC51 I.
6. REFER TO TRUSS MANUFACTURER'S  
DRAWINGS FOR TRUSS PLACEMENT &  
TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 1TH  
EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE  
INSTALLED IAW FBCR 2020, 1TH  
EDITION R305.1.1.1

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


THE PARK SERIES

Park Square Homes hereby reserves its common law copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

COPYRIGHT 2015

REVISIONS	BY
<p>Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292</p>	
<p>A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000</p>	
<p><b>Park Square HOMES</b></p>	
<p>TRUSS LAYOUT</p>	
4073	
DATE	05-15-2
SCALE AS NOTED	
DRAWN	RD
DOB	N/A
SHEET	
12E.0	

4073

REDWOOD

## ATTIC VENTILATION CALCULATIONS

PER FBC2020 11TH EDITION R306: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{3276 \text{ S.F.}}{300} = \underline{10.92 \text{ S.F.}}$  NET FREE VENT. REQUIRED

UPPER PORTION VENTILATION TOTAL:----- **582 S.F.**  
PROVIDED W/OFF RIDGE VENTS: **6** VENTS @ **97 S.F.** /VENT.  
(VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL:----- **6.09 S.F.**  
PROVIDED W/ VENTILATED SOFFITS @ EAVE:--  
( **70 LF** @ **0.087 S.F.** VENTING PER LF.)


UPPER PORTION PERCENTAGE: **50%**  
LOWER PORTION PERCENTAGE: **50%**

## NOTES

1. TYPICAL ROOF GABLE OVERHANG TO BE **8"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC51 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.11.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R305.11.1

## TRUSS LAYOUT "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
<b>Park Square HOMES</b>	
TRUSS LAYOUT	
4073	REDWOOD
DATE 05-15-21	
SCALE AS NOTED	
DRAWN RDC	
JOB N/A	
SHEET 12E.0	
OF SHEETS	

PER FBC 2020 3TH EDITION R806: MIN. 40% - MAX. 50%  
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF  
ATTIC SPACE AND THE BALANCE TO BE IN LOWER  
PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF  
VENTED SPACE:


TOTAL VENTED SPACE: 3276 SF. = 10.92 SF. NET FREE VENT.  
300 REQUIRED

UPPER PORTION VENTILATION TOTAL:----- 5.82 SF.  
PROVIDED W/OFF RIDGE VENTS: 6 VENTS @ 97 SF./VENT.  
(VENT TYPE: LOMANCO MODEL TT0-D OR MILLENNIUM  
METAL)

LOWER PORTION VENTILATION TOTAL:----- 6.09 SF.  
PROVIDED W/ VENTILATED SOFFITS @ EAVE:--  
( 70 LF @ 0.087 SF. VENTING PER LF.)

UPPER PORTION PERCENTAGE: 50%  
LOWER PORTION PERCENTAGE: 50%

1. TYPICAL ROOF GABLE OVERHANG TO BE **8'** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12'** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC51 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.1

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


**SUPER BONUS OPTION**

**THE PARK SERIES**

Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	REVISIONS	B
---	-----------	---

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park  
Square  
HOMES**

## TRUSS LAYOUT

4073

REDWOOD

DATE 05-15-

SCALE AS NOTE

DRAWN RE

JOB	N.
-----	----

SHEET

12E.1  
OF SHEET



## ATTIC VENTILATION CALCULATIONS

PER FBC2020 11TH EDITION R806: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{3276 \text{ S.F.}}{300} = \underline{10.92 \text{ S.F.}}$  NET FREE VENT. REQUIRED

UPPER PORTION VENTILATION TOTAL:----- **5.82 S.F.**  
PROVIDED W/OFF RIDGE VENTS: **6** VENTS @ **97 S.F.** /VENT.  
(VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL:----- **6.09 S.F.**  
PROVIDED W/ VENTILATED SOFFITS @ EAVE:---  
( **70 L.F.** @ **0.087 S.F.** VENTING PER L.F.)


UPPER PORTION PERCENTAGE: **50%**  
LOWER PORTION PERCENTAGE: **50%**

## NOTES

1. TYPICAL ROOF GABLE OVERHANG TO BE **8"** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12"** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1.1.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R905.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 11TH EDITION R905.1.1.1

## TRUSS LAYOUT "F"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

## THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.


REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
<b>Park Square</b> HOMES	
TRUSS LAYOUT	
4073	REDWOOD
DATE 05-15-21	
SCALE AS NOTED	
DRAWN RDC	
JOB N/A	
SHEET 12F.0	
OF SHEETS	

PER FBC2020 7TH EDITION R806: MIN. 40% - MAX. 50%  
OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF  
ATTIC SPACE AND THE BALANCE TO BE IN LOWER  
PORTION (EAVES).

TOTAL VENTED SPACE:  $\frac{3276 \text{ S.F.}}{300} = 10.92 \text{ S.F.}$  NET FREE VENT. REQUIRED

UPPER PORTION PERCENTAGE:	<u>50%</u>
LOWER PORTION PERCENTAGE:	<u>50%</u>

1. TYPICAL ROOF GABLE OVERHANG TO BE **8'** UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE **12'** UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 2020 FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BC91 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. TILE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.2  
OR  
SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2020, 1TH EDITION R305.1.1.1

$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>st</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**SUPER BONUS OPTION**

**THE PARK SERIES**

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

## TRUSS LAYOUT

4073

REDWOOD

DATE 05-15-2

SCALE AS NOTED

DRAWN RDC

JOB	N/A
-----	-----


SHEET

12F.1  
OF SHEETS

CAST CRETE / LOTTS / WEKIWA / FLORIDA ROCK PRE CAST LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F34-1B/IT	GARAGE DOOR
L-2	9'-4"	8F34-1B/IT	GARAGE DOOR
L-3	3'-6"	8F16-0B/IT	2/ØX2/Ø F.G.
L-4	7'-6"	8F16-0B/IT	6/ØX2/Ø F.G.
L-5	4'-6"	8F16-0B/IT	SH25
L-6	4'-6"	8F16-0B/IT	SH25
L-7	4'-6"	8F16-0B/IT	SH25
L-8	13'-4"	8F16-0B/IT	12/ØX8/Ø S.G.D.
L-9	21'-4"	8F24-1B/IT	LANAI
L-10	10'-6"	8F16-0B/IT	TRPL. SH25
L-11	7'-6"	8F16-0B/IT	FR. SH25
L-12	4'-6"	8F16-0B/IT	SH25
L-13	5'-10"	8RF12-0B/IT	3/Ø DR. W/ 14" S.L.
L-14	8'-7"	8F8-0B/IT	FRONT ENTRY
L-15	8'-4"	8F8-0B/IT	FRONT ENTRY
L-16	8'-4"	8F8-0B/IT	FRONT ENTRY
L-17	2'-7"	8F8-0B/IT	FRONT ENTRY
L-18			
L-19			
L-20			
L-21	17'-4"	8F22-1B/IT	OPT. 8' HIGH GARAGE DOOR
L-22	9'-4"	8F22-1B/IT	OPT. 8' HIGH GARAGE DOOR
L-23	4'-4"	8RF28-0B/IT	OPT. 2/8 GAR. SVC. DR.
L-24	11'-8"	8F16-0B/IT	OPT. SH25/4Ø5Ø/SH25
L-25	7'-6"	8F16-0B/IT	6/ØX8/Ø S.G.D.
L-26	17'-4"	8F16-0B/IT	16/ØX8/Ø S.G.D.
L-27	9'-4"	8F16-0B/IT	8/ØX8/Ø S.G.D.
L-28	5'-4"	8RF61-1B/IT	OPT. GLASS BLOCK
L-29	5'-4"	8RF61-1B/IT	OPT. GLASS BLOCK
L-30			
L-31			
L-32			
L-33			
L-34			
L-35			
L-36			
L-37			
L-38			
L-39			
L-40			

GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



BUTLER PANTRY OPT.


1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

PRE CAST LINTEL LAYOUT "D"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES


© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
PRE CAST LINTEL LAYOUT	
4073	REDWOOD
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	
13D.0	
OF	SHEETS

CAST CRETE / LOTTS / WEKIWA / FLORIDA ROCK PRE CAST LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F34-1B/IT	GARAGE DOOR
L-2	9'-4"	8F34-1B/IT	GARAGE DOOR
L-3	3'-6"	8F16-0B/IT	2/ØX2/Ø F.G.
L-4	7'-6"	8F16-0B/IT	6/ØX2/Ø F.G.
L-5	4'-6"	8F16-0B/IT	SH25
L-6	4'-6"	8F16-0B/IT	SH25
L-7	4'-6"	8F16-0B/IT	SH25
L-8	13'-4"	8F16-0B/IT	12/ØX8/Ø S.G.D.
L-9	21'-4"	8F24-1B/IT	LANAI
L-10	10'-6"	8F16-0B/IT	TRPL. SH25
L-11	7'-6"	8F16-0B/IT	FR. SH25
L-12	4'-6"	8F16-0B/IT	SH25
L-13	5'-10"	8RF12-0B/IT	3/Ø DR. W/ 14" S.L.
L-14	8'-7"	8F8-0B/IT	FRONT ENTRY
L-15	8'-4"	8F8-0B/IT	FRONT ENTRY
L-16	7'-6"	8F8-0B/IT	FRONT ENTRY
L-17			
L-18			
L-19			
L-20			
L-21	17'-4"	8F22-1B/IT	OPT. 8' HIGH GARAGE DOOR
L-22	9'-4"	8F22-1B/IT	OPT. 8' HIGH GARAGE DOOR
L-23	4'-4"	8RF28-0B/IT	OPT. 2/8 GAR. SVC. DR.
L-24	11'-8"	8F16-0B/IT	OPT. SH25/4Ø5Ø/SH25
L-25	7'-6"	8F16-0B/IT	6/ØX8/Ø S.G.D.
L-26	17'-4"	8F16-0B/IT	16/ØX8/Ø S.G.D.
L-27	9'-4"	8F16-0B/IT	8/ØX8/Ø S.G.D.
L-28	5'-4"	8RF61-1B/IT	OPT. GLASS BLOCK
L-29	5'-4"	8RF61-1B/IT	OPT. GLASS BLOCK
L-30			
L-31			
L-32			
L-33			
L-34			
L-35			
L-36			
L-37			
L-38			
L-39			
L-40			


BUTLER PANTRY OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




GLASS BLOCK OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




S.G.D. OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




PRE CAST LINTEL LAYOUT "E"

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



TRPL. WDW. OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By:		DBE and C
		MICHAEL A. THOMPSON
		PE 47509
		PHONE 407-721-2292
A DIVISION OF PARK SQUARE ENTERPRISES, INC.		
5200 Vineland Road, Suite 200		
Orlando, Florida 32811		
Phone: (407) 529 - 3000		
PRE CAST LINTEL LAYOUT		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	13E.0	
OF	5 SHEETS	




CAST CRETE / LOTTS / WEKIWA / FLORIDA ROCK PRE CAST LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F34-1B/IT	GARAGE DOOR
L-2	9'-4"	8F34-1B/IT	GARAGE DOOR
L-3	3'-6"	8F16-0B/IT	2/0X2/0 F.G.
L-4	7'-6"	8F16-0B/IT	6/0X2/0 F.G.
L-5	4'-6"	8F16-0B/IT	SH25
L-6	4'-6"	8F16-0B/IT	SH25
L-7	4'-6"	8F16-0B/IT	SH25
L-8	13'-4"	8F16-0B/IT	12/0X8/0 S.G.D.
L-9	21'-4"	8F24-1B/IT	LANAI
L-10	10'-6"	8F16-0B/IT	TRPL. SH25
L-11	7'-6"	8F16-0B/IT	FR. SH25
L-12	4'-6"	8F16-0B/IT	SH25
L-13	5'-10"	8RF12-0B/IT	3/0 DR. W/ 14" S.L.
L-14	8'-7"	8F12-0B/IT	FRONT ENTRY
L-15	9'-7"	8F12-0B/IT	FRONT ENTRY
L-16	9'-7"	8F12-0B/IT	FRONT ENTRY
L-17	2'-7"	8F12-0B/IT	FRONT ENTRY
L-18			
L-19			
L-20			
L-21	17'-4"	8F22-1B/IT	OPT. 8' HIGH GARAGE DOOR
L-22	9'-4"	8F22-1B/IT	OPT. 8' HIGH GARAGE DOOR
L-23	4'-4"	8RF28-0B/IT	OPT. 2/8 GAR. SVC. DR.
L-24	11'-8"	8F16-0B/IT	OPT. SH25/4050/SH25
L-25	7'-6"	8F16-0B/IT	6/0X8/0 S.G.D.
L-26	17'-4"	8F16-0B/IT	16/0X8/0 S.G.D.
L-27	9'-4"	8F16-0B/IT	8/0X8/0 S.G.D.
L-28	5'-4"	8RF61-1B/IT	OPT. GLASS BLOCK
L-29	5'-4"	8RF61-1B/IT	OPT. GLASS BLOCK
L-30			
L-31			
L-32			
L-33			
L-34			
L-35			
L-36			
L-37			
L-38			
L-39			
L-40			

GLASS BLOCK OPT.

S.G.D. OPTIONS

PRE CAST LINTEL LAYOUT "F"

BUTLER PANTRY OPT.



TRPL. WDW. OPT.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES  
Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS	BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292	
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000	
PRE CAST LINTEL LAYOUT	
4073	REDWOOD
DATE	05-15-21
SCALE	AS NOTED
DRAWN	RDC
JOB	N/A
SHEET	
13F.0	
OF	SHEETS


SAFE LOAD TABLES  
FOR GRAVITY, UPLIFT & LATERAL LOADS

8" PRECAST & PRESTRESSED U-LINTELS											
GRAVITY											
LENGTH \ TYPE	TYPE	8F8-1B	8F12-1B	8F16-1B	8F20-1B	8F24-1B	8F28-1B	8F32-1B	8F8-1B	8F12-1B	8F16-1B
2'-10" (34')	PRECAST	2302	3166	4473	6039	7526	9004	10472	11936	13400	14864
3'-6" (42')	PRECAST	2302	3166	4473	6039	7526	9004	10472	11936	13400	14864
4'-0" (48')	PRECAST	2029	2646	4473	6039	7526	9004	10472	11936	13400	14864
4'-6" (54')	PRECAST	1651	1187	1913	2651	3403	4149	4896	5644	6392	7140
5'-4" (64')	PRECAST	1184	1665	2889	5051	6296	7541	8786	10031	11276	12521
5'-10" (70')	PRECAST	912	1459	2464	4144	5458	6772	8086	9400	10714	12028
6'-6" (78')	PRECAST	931	1255	2101	3263	4425	5587	6749	7911	9073	10235
7'-6" (90')	PRECAST	167	1025	1675	2325	2975	3625	4275	4925	5575	6225
9'-4" (112')	PRECAST	913	1025	1675	2325	2975	3625	4275	4925	5575	6225
10'-6" (126')	PRECAST	456	658	1025	1675	2325	2975	3625	4275	4925	5575
11'-4" (136')	PRECAST	445	598	935	1365	1854	2343	2832	3321	3810	4299
12'-0" (144')	PRECAST	414	555	864	1254	1699	2144	2589	3034	3479	3924
13'-4" (160')	PRECAST	362	427	726	1029	1331	1635	1939	2243	2547	2851
14'-0" (168')	PRECAST	338	381	648	919	1190	1462	1734	2006	2278	2550
14'-8" (176')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
15'-4" (184')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
17'-4" (208')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
19'-4" (232')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
21'-4" (256')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
22'-0" (264')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
24'-0" (288')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR

8" PRECAST W/ 2" RECESS DOOR U-LINTELS											
GRAVITY											
LENGTH \ TYPE	TYPE	8F8-1B	8F12-1B	8F16-1B	8F20-1B	8F24-1B	8F28-1B	8F32-1B	8F8-1B	8F12-1B	8F16-1B
4'-4" (52')	PRECAST	1489	1951	3053	4382	5711	7040	8369	9698	11027	12356
4'-6" (54')	PRECAST	1351	1787	2782	3951	5120	6289	7458	8627	9796	10965
5'-8" (68')	PRECAST	785	1032	1602	2350	3098	3846	4594	5342	6090	6838
5'-10" (70')	PRECAST	735	1025	1675	2325	2975	3625	4275	4925	5575	6225
6'-8" (80')	PRECAST	822	1025	1675	2325	2975	3625	4275	4925	5575	6225
7'-6" (90')	PRECAST	665	1025	1675	2325	2975	3625	4275	4925	5575	6225
9'-8" (116')	PRECAST	371	535	928	1491	2154	2817	3480	4143	4806	5469

8" PRECAST & PRESTRESSED U-LINTELS											
UPLIFT											
LENGTH \ TYPE	TYPE	8F8-1T	8F12-1T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1T	8F8-1T	8F12-1T	8F16-1T
2'-10" (34')	PRECAST	2121	2818	4101	5332	6563	7794	9025	2021	2021	2021
3'-6" (42')	PRECAST	2165	2289	3260	4237	5219	6204	7182	1251	1251	1251
4'-0" (48')	PRECAST	1878	1989	2832	3680	4532	5381	6234	938	938	938
4'-6" (54')	PRECAST	1660	1762	2501	3251	4000	4761	5525	121	121	121
5'-4" (64')	PRECAST	1393	1431	2050	2610	3173	3736	4299	505	505	505
5'-10" (70')	PRECAST	1272	1351	1930	2509	3084	3665	4241	418	418	418
6'-6" (78')	PRECAST	1141	1200	1733	2250	2769	3290	3812	707	707	707
7'-6" (90')	PRECAST	959	1025	1466	1907	2351	2791	3245	591	591	591
9'-4" (112')	PRECAST	801	855	1192	1550	1910	2271	2634	454	454	454
10'-6" (126')	PRECAST	716	761	1039	1389	1741	2094	2447	396	396	396
11'-4" (136')	PRECAST	666	711	975	1275	1581	1881	2181	363	363	363
12'-0" (144')	PRECAST	607	652	891	1161	1431	1701	1971	340	340	340
13'-4" (160')	PRECAST	500	545	751	991	1231	1471	1711	302	302	302
14'-0" (168')	PRECAST	458	503	693	913	1133	1353	1573	286	286	286
14'-8" (176')	PRESTRESSED	243	285	459	631	805	979	1153	NR	NR	NR
15'-4" (184')	PRESTRESSED	228	270	430	593	757	921	1085	NR	NR	NR
17'-4" (208')	PRESTRESSED	188	236	361	464	567	670	773	NR	NR	NR
19'-4" (232')	PRESTRESSED	165	207	313	401	490	578	667	NR	NR	NR
21'-4" (256')	PRESTRESSED	145	186	278	356	433	512	590	NR	NR	NR
22'-0" (264')	PRESTRESSED	131	169	252	322	391	461	531	NR	NR	NR
24'-0" (288')	PRESTRESSED	121	155	234	302	369	437	505	NR	NR	NR

\*REDUCE VALUE BY 25% FOR GRADE 40 FIELD REBAR



MATERIALS

1. f'c precast lintels = 3500 psi.
  2. f'c prestressed lintels = 6000 psi.
  3. f'c grout = 3000 psi w/ maximum 3/8" aggregate.
  4. Concrete masonry units (CMU) per ASTM C90 w/ minimum net area compressive strength = 1900 psi.
  5. Rebar provided in precast lintel per ASTM A615 GR60. Field rebar per ASTM A615 GR40 or GR60.
  6. Prestressing strand per ASTM A416 grade 270 low relaxation.
  7. T/32 wire per ASTM A510.
  8. Mortar per ASTM C270 type M or S.
- GENERAL NOTES**
1. Provide full mortar head and bed joints.
  2. Shore filled lintels as required.
  3. Installation of lintel must comply with the architectural and/or structural drawings.
  4. Lintels are manufactured with 5-1/2' long notches at the ends to accommodate vertical cell reinforcing and grouting.
  5. All lintels meet or exceed L/360 vertical deflection, except lintels 17'-4" and longer with a nominal height of 8' meet or exceed L/180.
  6. Bottom field added rebar to be located at the bottom of the lintel cavity.
  7. 1/32" diameter wire stirrups are welded to the bottom steel for mechanical anchorage.
  8. Cast-in-place concrete may be provided in composite lintel in lieu of concrete masonry units.
  9. Safe load ratings based on rational design analysis per ACI 318 and ACI 530.

SAFE LOAD TABLE NOTES


1. All values based on minimum 4" bearing. Exception: Safe loads for unfilled lintels must be reduced by 20% if bearing length is less than 6-1/2". Safe loads for all recessed lintels based on 8" nominal bearing.
2. N.R. = Not Rated.
3. Safe loads are total superimposed allowable load on the section specified.
4. Safe loads based on grade 40 or grade 60 field rebar.
5. Additional lateral load capacity can be obtained by the designer by providing additional reinforced masonry above the precast lintel.
6. One #1 rebar may be substituted for two #5 rebars in 8" lintels only.
7. The designer may evaluate concentrated loads from the safe load tables by calculating the maximum resisting moment and shear at d-away from the face of support.
8. For composite lintel heights not shown, use safe load from next lower height.
9. All safe loads in units of pounds per linear foot.

8" PRECAST W/ 2" RECESS DOOR U-LINTELS											
UPLIFT											
LENGTH \ TYPE	TYPE	8F8-1T	8F12-1T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1T	8F8-1T	8F12-1T	8F16-1T
4'-4" (52')	PRECAST	1244	1513	2413	3360	4312	5264	6216	932	932	932
4'-6" (54')	PRECAST	1192	1459	2311	3211	4161	5111	6061	853	853	853
5'-8" (68')	PRECAST	924	1172	1795	2423	3055	3689	4325	501	501	501
5'-10" (70')	PRECAST	836	1095	1630	2288	2931	3571	4211	463	463	463
6'-8" (80')	PRECAST	718	882	1313	1842	2371	2901	3431	830	830	830
7'-6" (90')	PRECAST	688	849	1275	1802	2329	2859	3389	710	710	710
9'-8" (116')	PRECAST	533	621	1009	1369	1728	2088	2447	516	516	516


\*REDUCE VALUE BY 25% FOR GRADE 40 FIELD REBAR

CONNECTOR SCHEDULE


CONNECT. TYPE	SIMPSON		USP		MAX. UPLIFT	LAT. LDS. FI / F2
	DESCRIPTION	FASTENERS PER CONNECTOR	DESCRIPTION	FASTENERS PER CONNECTOR		
4	HETA20	14-10d x 1½"	ETA20	14-10d	1810	65 / 360
5	DETAL20	18-10d x 1½"	N/A	N/A	2480	2000/ 1310
20	H3	RFT: 4-8d / PLT: 4-8d	RT3	RFT: 4-8d / PLT: 4-8d	455	125 / 160
21	H1	RFT:6-8dx1½"/PLT:4-8d	RT15	RFT:5-8dx1½"/PLT:5-8d	475	485 / 165
22	H10S	RFT: 8-8d x 1 1/2"	RT16	RFT: 8-8d x 1½"	930	585/525
		PLT: 8-8d x 1 1/2"		PLT: 8-8d		
23	LU526	HDR: 4-10d/JST: 4-10d	JU526	HDR: 4-10d/JST: 4-10d	935	N/A
24	H7	RFT / TR5: 4-8d	RT20	RFT / TR5: 9-10d	985	400 / N/A
		PLT / STD: 10-8d		PLT / STD: 13-10d		
26	H25	RFT:5-8d / PLT: 5-8d	RT7	RFT:5-8d / PLT: 5-8d	415	150 / 150
34	A34	H:4-8dx1½"/P:4-8dx1½"	MP34	H:4-8dx1½"/P:4-8dx1½"	365	280 / 303
35	A35F	H:4-8dx1½"/P:4-8dx1½"	MPA1F	H:6-8dx1½"/P:6-8dx1½"	440	440 / N/A
37	MTS12	14-10d	MTW12	14-10d	1000	N/A
38	MTS16	14-10d	MTW16	14-10d	1000	N/A
43	LSTA12	10-10d	LSTA12	10-10d	905	N/A
45	ST18	14-16d	ST18	14-16d	1200	N/A
47	LSTA24	18-10d	LSTA24	18-10d	1295	N/A
71	MSTA36	26-10d	MSTA36	26-10d	2135	N/A
72	MSTC66	64-16d SINKERS	N/A	N/A	5495	N/A
79	SF1	STD:6-10d / PLT:4-10d	SPT22	STD:4-10d / PLT:4-10d	535	560 / 260
80	SF2	STD:6-10d / PLT:6-10d	SPT224	STD:6-10d / PLT:6-10d	605	560 / 260
81	SPH468	12-10d x 1½"	TP468	12-10d x 1½"	885	N/A
90	ABU66	12-16d	PAU66	12-16d	2240	N/A
89	CB66	(2) ⅝" BOLTS	PA8X8	4-10d	2300	985
92	ABU44	12-16d	PAU44	12-16d	2200	N/A
93	AC6 (MAX)	28-16d	PB666	24-16d	1815	1070
94	AC4 (MAX)	28-16d	PB644	24-16d	1815	1070
95	HT520	20-10d	HTW20	20-10d	1450	N/A
96	HD8A	SILL: ⅜" BOLT	HHD8A	SILL: ⅜" BOLT	7910	N/A
		STUD:(3) ⅜"X5½" BOLTS		STUD:(3) ⅜"X5½" BOLTS		
97	MTT28B	24-16d	MTS27B	24-16d	4455	N/A
98	HTT16	SILL: ⅝" BOLT	HTT16	SILL: ⅝" BOLT	4175	N/A
		STRAP: 18-16d		STRAP: 18-16d		
99	A35	H:4-8dx1½"/P:4-8dx1½"	MPA1	H:6-8dx1½"/P:6-8dx1½"	440	440 / N/A
100	HTT22	⅝" BOLT/ 32-16d Sinkers	HTT22	¾" BOLT/ 32-16d	5260	N/A
101	HTT4	⅝" BOLT/ 18-16dX2½"	N/A	N/A	3640	N/A
102	HTT5	⅝" BOLT/ 26-10d	N/A	N/A	4275	N/A
103	VGTR/L	32-SDS¼"X3"/(2) ⅝" BLT	N/A	N/A	3930	N/A
104	HDU8-SDS25	7/8" BLT/20-SDS ¼"x2½"	N/A	N/A	5020	N/A
110	HCF2	12-10d x 1½"	HHCF2	20-10d x 1½"	520	260 / N/A
167	HHU546	H:14-16d/J:6-16d	THD46	H:8-18d/J:12-10d	1550	N/A
168	U46	H:8-10d/J:4-10d	SUH46	H:8-16d/J:4-16d	710	N/A
181	HU526	20-16d	THD26	H:20-16d/J:10-10d	1550	N/A
184	HUC28-2	H:14-16d/J:4-10d	N/A	N/A	1085	N/A
214	HUC212-3TF	HD:16-3/16"X1½" TAPCON BM: 6-16d	HDO212-3	HD:18-3/16"X1½" TAPCON BM: 6-10d	1135	N/A
215	HGU5210-2	HDR:46-16d/JST:10-16d	EHUH210-2	HDR:40-16d/JST:16-10d	2720	N/A
216	HU5412	BLOCK: 10-¼"X1½" TC JOIST : 10-16d	HU5412	BLOCK: 10-¼"X1½" TC JOIST : 10-16d	3240	N/A
217	HU5212-2	BLOCK: 10-¼"X1½" TC JOIST : 10-16d	HU5212-2	BLOCK: 10-¼"X1½" TC JOIST : 10-16d	2630	N/A
219	MBHA412	H:1-ATR¾X8 TOP4FACE JOIST: 18-10d	NFM35X12U	H:1-½" J-BOLT J:5-½" BOLTS	3145	N/A
220	N/A	N/A	NFM 3X12	BLK:½"ø J /JST:14-10d	1620	N/A
226	MBHA4.75/12	HDR : (2) ¾"ø x 8" JOIST : 18-10d	NFM45U	HDR : MIN. ½"ø "J" BOLT JOIST : (5) ½"ø BOLTS	2160	N/A
231	MBHA3.56/16	HDR : (2) ¾"ø x 8" JOIST : 18-10d	NFM3.5X16U	HDR :MIN. ½"øxJ-BOLTS JOIST : (5) ½"ø BOLTS	3450	N/A
232	MBHA5.50/16	HDR : (2) ¾"ø x 8" JOIST : 18-10d	NFM5.5X16U	HDR :MIN. ½"øxJ-BOLTS JOIST : (5) ½"ø BOLTS	3450	N/A
240	H15	R:4-10dx1½"/P:4-10dx1½"	N/A	N/A	1300	480 / N/A
241	LGT2	30-16d-sinker	LUGT2	32-10d	2000	1015 / 440
301	MG1	(1) ¾"BLTS/GIR: 22-10d	N/A	N/A	3965	N/A
302	HGT-2 or 3	LTL:¾"BLTS/GIR: 8-10d	USC63	LTL:¾"BLTS/GIR: 8-16d	6485	N/A
303	HGT-4	LTL:¾"BLTS/GIR: 16-10d	N/A	N/A	9250	N/A
401	SUR/L414	FACE:18-16d/JST:8-16d	N/A	N/A	1700	N/A
T	CONNECTORS TO BE SPECIFIED AND PROVIDED BY TRUSS MANUFACTURERS					




4 TYP. STAIR CONNECT. PLATFORM FRAMING  
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34")



1 STAIR DETAIL  
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34") STAIR DATA



5 TYP. HANDRAIL DET.  
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34")



2 TYP. STAIR CONNECT. STRINGER TO FLOOR TRUSS  
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34")

NOTES:  
STAIRWAY CONSTRUCTION TO CONFORM TO FBCR 2020, 7TH EDITION SECTION R311.7


MAX. HGT. OF RISER TO BE 7 3/4"  
MIN. WIDTH OF TREAD TO BE 9"(EXCLUSIVE OF NOSING)  
ALL TREADS LESS THAN 10" IN WIDTH SHALL HAVE APPROX. 1" OF NOSING  
3/16" MAX. VARIATION IN RISERS/TREADS ADJACENT TO EACH OTHER  
3/8" MAX. VARIATION IN ANY RISER/TREAD

HAND RAIL CIRCULAR CROSS SECTION DIA. TO BE 1 1/4" - 2" OR TO PROVIDE EQUIVALENT GRASPABILITY.


WINDERS: MIN. 6" WIDE @ NARROW END

34"MIN.-38"MAX., HANDRAIL HGT.


HEADROOM CLEARANCE MIN. 6'-8"




3 TYP. STAIR CONNECT. STRINGER TO FLOOR  
3/4"= 1'-0" (11X17) 1 1/2"= 1'-0" (22"X34")




7 DETAIL  
1/2"= 1'-0" (11X17) 1"= 1'-0" (22"X34")



9 DETAIL  
1/2"= 1'-0" (11X17) 1"= 1'-0" (22"X34")



6 DETAIL  
1/2"= 1'-0" (11X17) 1"= 1'-0" (22"X34")



8 DETAIL (BRG. W/O UPLIFT)  
1/2"= 1'-0" (11X17) 1"= 1'-0" (22"X34")

THE PARK SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1TH EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292








A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park Square HOMES

PRE CAST LINTEL DATA / CONNECTOR SCHEDULE

4073  
REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 15 OF SHEETS



THE PARK SERIES

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

Park Square  
HOMES

DATE 05-15-21

SCALE AS NOTED

DRAWN RDC

JOB N/A

SHEET 16


OF SHEETS

STRUCTURAL DETAILS


4073

REDWOOD







**3** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')




**2** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')




**1** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')




**9** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')



**6** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')



**5** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')



**4** **DETAIL**  
17 1/2"=1'-0" (11X17) 1"=1'-0" (22'X34')

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES

THESE PLANS, IDEAS, AND DESIGN ARE NOT TO BE COPIED OR REPRODUCED IN ANY MANNER OR FORM WITHOUT THE EXPRESS WRITTEN PERMISSION FROM PARK SQUARE HOMES.

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

REVISIONS BY

DATE 05-15-21

SCALE AS NOTED


DRAWN RDC

JOB N/A


SHEET 17

OF SHEETS


4073 REDWOOD




**6**  
18  
**DETAIL**  
1/2" = 1'-0" (11X17) 1" = 1'-0" (22X34)




**5**  
18  
**DETAIL**  
1/2" = 1'-0" (11X17) 1" = 1'-0" (22X34)




**1**  
18  
**DETAIL**  
1/2" = 1'-0" (11X17) 1" = 1'-0" (22X34)




**3**  
18  
**DETAIL**  
1/2" = 1'-0" (11X17) 1" = 1'-0" (22X34)



**2**  
18  
**DETAIL**  
1/2" = 1'-0" (11X17) 1" = 1'-0" (22X34)



**8**  
18  
**DETAIL**  
1/2" = 1'-0" (11X17) 1" = 1'-0" (22X34)



**7**  
18  
**DETAIL**  
3/4" = 1'-0" (11X17) 1/2" = 1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1st EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**THE PARK SERIES**

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

Engineering By:  
DBE and C  
MICHAEL A. THOMPSON  
PE 47509  
PHONE 407-721-2292

A DIVISION OF PARK SQUARE  
ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square**  
HOMES

STRUCTURAL DETAILS


4073

REDWOOD

DATE 05-15-21  
SCALE AS NOTED  
DRAWN RDC  
JOB N/A  
SHEET 18  
OF 18 SHEETS


FLOOR PLAN W/  
NOTES

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




FLOOR PLAN W/  
DIMENSIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





FOUNDATION PLAN

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




INTERIOR ELEVATIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



ELECTRICAL PLAN

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)






THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 11th EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

GOURMET KITCHEN OPTION

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.


REVISIONS		BY
Engineering By:		DBE and C
		MICHAEL A. THOMPSON
		PE 47509
		PHONE 407-721-2292
A DIVISION OF PARK SQUARE ENTERPRISES, INC.		
5200 Vineland Road, Suite 200		
Orlando, Florida 32811		
Phone: (407) 529 - 3000		
Park Square HOMES		
PLAN OPTIONS		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	19.1	
OF	SHEETS	



- $$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$


$$1/8'' = 1' - 0'' \quad (11 \times 17) \quad 1/4'' = 1' - 0'' \quad (22 \times 34)$$

REDWOOD




BR. 6/ BA. 5 OPTION

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


LIGHTING OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

OPTION LEGEND


- ① OPT. RECESS LIGHTS ILO CEILING FIXTURE
- ② OPT. RECESS LIGHTS ILO FLUORESCENT
- ③ OPT. DBL. CHANDELIER-SEE COLOR SHEET FOR SPACING
- ④ OPT. PENDANTS LIGHTS-SEE COLOR SHEET FOR SPACING
- ⑤ OPT. TOE-KICK LIGHTING UNDER CABINETS
- ⑥ OPT. ABOVE CABINET LIGHTING
- ⑦ OPT. UNDER CABINET LIGHTING

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>ST</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES


Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and design are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
LIGHTING OPTION		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	LO2.0	
OF	SHEETS	




BR. 6/ BA. 5 OPTION

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


LIGHTING OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

OPTION LEGEND

- ① OPT. RECESS LIGHTS ILO CEILING FIXTURE
- ② OPT. RECESS LIGHTS ILO FLUORESCENT
- ③ OPT. DBL. CHANDELIER-SEE COLOR SHEET FOR SPACING
- ④ OPT. PENDANTS LIGHTS-SEE COLOR SHEET FOR SPACING
- ⑤ OPT. TOE-KICK LIGHTING UNDER CABINETS
- ⑥ OPT. ABOVE CABINET LIGHTING
- ⑦ OPT. UNDER CABINET LIGHTING


BONUS ROOM OPTION

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>ST</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

THE PARK SERIES


© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
LIGHTING OPTION		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	LO2.1	
OF	SHEETS	



SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)





SHOWER OPT.

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)


LIGHTING OPTIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)




SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



BA. 4 OPTION

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)



SHOWER OPT.

1/8"=1'-0" (11X17)  
1/4"=1'-0" (22X34)

OPTION LEGEND

- ① OPT. RECESS LIGHTS ILO CEILING FIXTURE
- ② OPT. RECESS LIGHTS ILO FLUORESCENT
- ③ OPT. DBL. CHANDELIER-SEE COLOR SHEET FOR SPACING
- ④ OPT. PENDANTS LIGHTS-SEE COLOR SHEET FOR SPACING
- ⑤ OPT. TOE-KICK LIGHTING UNDER CABINETS
- ⑥ OPT. ABOVE CABINET LIGHTING
- ⑦ OPT. UNDER CABINET LIGHTING

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 1<sup>ST</sup> EDITION, 2020 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

OPT. BEDROOM 7/ BATH 6, LOFT/ OPT. MEDIA

THE PARK SERIES

© COPYRIGHT 2015 Park Square Homes hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from Park Square Homes.

REVISIONS		BY
Engineering By: DBE and C MICHAEL A. THOMPSON PE 47509 PHONE 407-721-2292		
A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
Park Square HOMES		
LIGHTING OPTION		
4073		
REDWOOD		
DATE	05-15-21	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	N/A	
SHEET	LO2.2	
OF	SHEETS	