

FOUNDATION LEGEND

SYMBOL	DESIGN DESCRIPTION
■	INDICATES FILLED CELL w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
□	INDICATES FILLED CELL BELOW WINDOWS w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
F#.#	INDICATES CONCRETE FOOTING w/ MINIMUM SOIL BEARING CAPACITY OF 2000 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SN FOR DESIGN SPECIFICATIONS.
— —	INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE 1/2" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12'x12' SQUARE MAXIMUM
≡	INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET D1
0'-0" FIN. FLR.	4" 2500 PSI CONC. SLAB W/ REINF. PER S0 w/6 MIL VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES. SEE FOUNDATION SCHEDULE ON SN
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT, AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB

GENERAL NOTES:  
1. TYPICAL CORNER FRAMING PER DETAIL FM19/D1  
2. SEE ARCHITECTURAL PLANS FOR ALL SLAB STEP DEPTHS IF SHOW SHOWN WITHIN THESE DOCUMENTS.

FILLED CELL NOTES:  
1. SEE PLAN FOR ZONE MIDDLE AND END DESIGNATIONS  
2. PLACE FILLED CELLS AT ALL BUILDING CORNER, UNDER GIRDERS, BOTH ENDS OF EXTERIOR WALL OPENING, AND WHERE INTERIOR BEARING WALLS ARE PERPENDICULAR TO EXTERIOR MASONRY WALL.  
3. PLACE 1-#5 IN FIRST TWO CELLS ADJACENT TO GARAGE DOOR OPENING & ALL OPENINGS 8'-0" & LARGER. FILL CELLS SOLID.  
4. PLACE 1-#5 WHERE WOOD BEAMS CONNECT TO MASONRY WALL  
5. NO NOT PLACE FILLED CELLS DIRECTLY IN LINE w/ STOVE VENT

PLAN KEY NOTES

1 12" x 12" CMU COL. w/ (2) #5 - T/COL. EL. 9'-4" A.F.F.

**BUILDER NOTE:**  
ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO COMMENCEMENT OF CONSTRUCTION

WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE

KEY PLAN

FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.

4017 W. 1st Street  
Sanford, FL 32771  
ph 407 829 8900  
fax 407 829 2040  
www.badesignstudios.com

N.C.B.D.C.

A.I. AMERICAN INSTITUTE OF BUILDING DESIGN

www.FDSENG.COM

FDS ENGINEERING ASSOCIATES

288 Southall Lane, Suite 200, Maitland, FL 32751  
ph 407 829 8900  
Fax 407 829 2040  
Certificate of Authorization No. 3191  
□ CARL A. BROWN, PE - FL #5628  
□ SCOTT LEWIS, PE - FL #79780  
DATE: September 20, 2023

FDS JOB NO.: \_\_\_\_\_

PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS


title: \_\_\_\_\_

project no. 2022144  
checked: AB  
drawn: \_\_\_\_\_  
date: 05-19-22  
scale: \_\_\_\_\_

S1.1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS

---


title:

---

project no. 2022144  
checked: AB  
date: 05-19-22  
scale:

S1.2

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED



## FOUNDATION LEGEND

SYMBOL	DESIGN DESCRIPTION
■	INDICATES FILLED CELL w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
□	INDICATES FILLED CELL BELOW WINDOWS w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
F#	INDICATES CONCRETE FOOTING w/ MINIMUM SOIL BEARING CAPACITY OF 2000 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SN FOR DESIGN SPECIFICATIONS.
	INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE 1/2" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12"x12" SQUARE MAXIMUM
4"	INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET D1
0'-0" FIN. FLR.	4" 2500 PSI CONC. SLAB W/ REINF. PER S0 w/6 MIL VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES. SEE FOUNDATION SCHEDULE ON SN
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT, AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB

GENERAL NOTES:  
1. TYPICAL CORNER FRAMING PER DETAIL FM19/D1  
2. SEE ARCHITECTURAL PLANS FOR ALL SLAB STEP DEPTHS IF SHOW SHOWN WITHIN THESE DOCUMENTS.


FILLED CELL NOTES:  
1. SEE PLAN FOR ZONE MIDDLE AND END DESIGNATIONS  
2. PLACE FILLED CELLS AT ALL BUILDING CORNER, UNDER GIRDERS, BOTH ENDS OF EXTERIOR WALL OPENING, AND WHERE INTERIOR BEARING WALLS ARE PERPENDICULAR TO EXTERIOR MASONRY WALL.  
3. PLACE 1-#5 IN FIRST TWO CELLS ADJACENT TO GARAGE DOOR OPENING & ALL OPENINGS 8'-0" & LARGER. FILL CELLS SOLID.  
4. PLACE 1-#5 WHERE WOOD BEAMS CONNECT TO MASONRY WALL  
5. NO NOT PLACE FILLED CELLS DIRECTLY IN LINE w/ STOVE VENT

## PLAN KEY NOTES

BUILDER NOTE:  
ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO COMMENCEMENT OF CONSTRUCTION

## WALL TYPE


SYMBOL	DESIGN DESCRIPTION
2x	INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE



## KEY PLAN

## FOUNDATION PLAN

SCALE: 1/4" = 1'-0"



FDS JOB NO.:


PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS

title:

project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:

S1.3





FOUNDATION LEGEND	
SYMBOL	DESIGN DESCRIPTION
	INDICATES FILLED CELL w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
	INDICATES FILLED CELL BELOW WINDOWS w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
	INDICATES CONCRETE FOOTING w/ MINIMUM SOIL BEARING CAPACITY OF 2000 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SN FOR DESIGN SPECIFICATIONS.
	INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE 1/2" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12x12" SQUARE MAXIMUM
	INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET D1
	4" 2500 PSI CONC. SLAB W/ REINF. PER S0 w/6 MIL VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES. SEE FOUNDATION SCHEDULE ON SN
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT, AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB


- GENERAL NOTES:
- TYPICAL CORNER FRAMING PER DETAIL FM19/D1
  - SEE ARCHITECTURAL PLANS FOR ALL SLAB STEP DEPTHS IF SHOW SHOWN WITHIN THESE DOCUMENTS.

- FILLED CELL NOTES:
- SEE PLAN FOR ZONE MIDDLE AND END DESIGNATIONS
  - PLACE FILLED CELLS AT ALL BUILDING CORNER, UNDER GIRDERS, BOTH ENDS OF EXTERIOR WALL OPENING, AND WHERE INTERIOR BEARING WALLS ARE PERPENDICULAR TO EXTERIOR MASONRY WALL.
  - PLACE 1-#5 IN FIRST TWO CELLS ADJACENT TO GARAGE DOOR OPENING & ALL OPENINGS 8'-0" & LARGER. FILL CELLS SOLID.
  - PLACE 1-#5 WHERE WOOD BEAMS CONNECT TO MASONRY WALL
  - NO NOT PLACE FILLED CELLS DIRECTLY IN LINE w/ STOVE VENT

PLAN KEY NOTES	

BUILDER NOTE:  
ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO COMMENCEMENT OF CONSTRUCTION

WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE



KEY PLAN

FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.

N.C.B.D.O.

A.I. AMERICAN INSTITUTE OF DESIGN

4017 W. 1st Street  
Sanford, FL 32771  
ph: 407 829 8900  
fax: 407 829 2040  
www.badesignstudios.com

FDS

FOUNDATIONS DESIGN STUDIOS

288 Southall Lane, Suite 200, Maitland, FL 32751  
Phone: 407-829-8900  
Fax: 407-829-2040  
Email: info@fdeseng.com  
Certificate of Authorization No. 5191

□ CARL A. BROWN, PE - FL #5628  
□ SCOTT LEWIS, PE - FL #79790

DATE: September 20, 2023

FDS JOB NO: \_\_\_\_\_

PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS

title: \_\_\_\_\_


project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:

S1.4

The structural design of this building is in accordance with the FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL and is certified as such.

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





**FRAMING NOTES:**

1. SEE WIND SPEED CHART ON **50** FOR WINDOW PRESSURES
2. AT SECOND FLOOR, FOR TYPICAL CORNER FRAMING SEE DETAIL **FB06/03**

**GENERAL NOTES:**

1. THE FRAMING PLAN SHOWS INDICATES THE "TRUSS AND THE RESPONSIBILITIES OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD), THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESPONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION.
2. ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
3. SEE SHEET SW-1 FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

**BUILDER NOTE:**  
TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON  
TRUSSES PROVIDED BY A1 INDUSTRIES, PROJECT NAME  
CPSMU6 w/ TRUSS DESIGN DATED 4/13/23 IF THE TRUSS  
LAYOUT SHOWN DOES NOT MATCH THE TRUSS  
MANUFACTURERS LAYOUT AND DATE ABOVE

**---STOP---**

AND CALL THE ENGINEER OF RECORD PRIOR TO  
PLACEMENT OF ANY TRUSSES.

WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x. INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE <u>BEARING WOOD BEARING SCHEDULE ON SN</u>
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE

SCALE: 1/4" = 1'-0'

PARK SQUARE  
HORIZONS WEST  
66-UNIT - ADAMS END UNITS

title:

---

project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:

# S2.1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED




**ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):**

**ZONE 1:** ASTM F1667 RSRSS-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C. IN FIELD  
Zone 2e, 2n, 2r: ASTM F1667 RSRSS-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD  
Zone 3, 3e, 3r: ASTM F1667 RSRSS-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD

**ROOF SHEATHING:**  
**SHINGLE:**  $\frac{3}{4}$ " Exp. 1 ( $\frac{5}{8}$ ") or  $\frac{3}{4}$ " Exp. 1 ( $\frac{5}{8}$ ")

**TILE:**  
 $\frac{3}{4}$ " Exp. 1 ( $\frac{5}{8}$ ")

1. PER CODE ASTM F1667 RSRSS-01 REFERENCE TO 8d (2  $\frac{3}{4}$ " x 0.131") NAILS  
2. WHERE THE SHEATHING THICKNESS IS GREATER THAN  $\frac{3}{4}$ " SHINGLE, SHEATHING SHALL BE REPLACED WITH ASTM F1667 RSRSS-03 100 (214" x 0.131") NAILS OR ASTM F1667 RSRSS-04 (3" x 120") NAILS  
3. GABLES- DROP GABLE END & (1) ANTI-DROPPED TRUSS 2x4 8'x2 SYP  
OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 SYP BLOCKING @ 16" O.C. TO 12'x12' 4 BAYS WITH (2) 12d NAILS EA. END, ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.



**FRAMING NOTES:**

1. SEE WIND SPEED CHART ON **S0** FOR WINDOW PRESSURES
2. AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL **FB06/D3**

**GENERAL NOTES:**

1. THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL RESPONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
2. ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
3. SEE SHEET **SN** FOR DESIGN SCHEDULES AND NOTES:  
FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

**BUILDER NOTE:**  
TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON  
TRUSSES PROVIDED BY A1 INDUSTRIES, PROJECT NAME  
CPSMU6 w/ TRUSS DESIGN DATE 4/13/23 IF THE TRUSS  
LAYOUT SHOWN DOES NOT MATCH THE TRUSS  
MANUFACTURERS LAYOUT AND DATE ABOVE

**-----STOP-----**


AND CALL THE ENGINEER OF RECORD PRIOR TO  
PLACEMENT OF ANY TRUSSES.








The structural design of this building is in accordance with the FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL and is certified as such.

## S2.2

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





SYMBOL	DESIGN DESCRIPTION
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES PERFORATED SHEAR WALL, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
	INDICATES NO BOTTOM CONNECTOR REQUIRED
	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

**FRAMING NOTES:**

- SEE WIND SPEED CHART ON S0 FOR WINDOW PRESSURES
- AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL FB06/D3






**GENERAL NOTES:**


- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD), THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
- ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITHIN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
- SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

PLAN KEY NOTES
1 12" SQ CMU COLUMN W/(2)#5 FULLY GROUTED

**BUILDER NOTE:**  
TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON TRUSSES PROVIDED BY A1 INDUSTRIES, PROJECT NAME CPSM06 w/ TRUSS DESIGN DATED 4/13/23 IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND DATE ABOVE


**---STOP---**  
AND CALL THE ENGINEER OF RECORD PRIOR TO PLACEMENT OF ANY TRUSSES.

SYMBOL	DESIGN DESCRIPTION
	2x_ INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE




**KEY PLAN**  
**LOW ROOF & FLOOR FRAMING PLAN**  
SCALE: 1/4" = 1'-0"

RSH	ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft
WIND SPEED (ULTIMATE)	140.0 MPH
WIND SPEED (ALLOWABLE)	108.4 MPH
EXPOSURE CATEGORY	C
EFFECTIVE WIND AREA (SQ FEET)	WIND PRESSURE AND SUCTION (PSF) (+) VALUE DENOTES PRESSURE (-) VALUE DENOTES SUCTION
AREA	ROOF 1 2e 2n 2r 3 3e 3r
10	HIP -35.94 -49.57 -49.57 -49.57 GABLE -38.22 -38.22 -60.99 -60.99 -60.99 -78.58
ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):	
ZONE 1: ASTM F1667 RSR-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C. IN FIELD	
ZONE 2e, 2n, 2r: ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD	
ZONE 3, 3e, 3r: ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD	
ROOF SHEATHING:	
SHINGLE: 3/4" EXP. 1 (2% <sub>10</sub> ) or 1/2" EXP. 1 (2% <sub>10</sub> )	
TILE: 1/2" EXP. 1 (2% <sub>10</sub> )	
NOTE:	
1. PER CODE ASTM F1667 RSR-01 REFERENCE TO 8d (2 3/4" x 0.113") NAILS	
2. WHERE THE SHEATHING THICKNESS IS GREATER THAN 1/2", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSR-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSR-04 (3" x 120") NAILS	
3. GABLES: DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.	



**B&A Design Studio, Inc.**  
4017 W. 1st Street  
Sanford, FL 32771  
ph: 407 829 8900  
fax: 407 829 2040  
www.badesignstudios.com



**FDS ENGINEERING ASSOCIATES**  
288 South Hall Lane, Suite 200, Maitland, FL 32751  
www.fdseng.com  
Carl A. Brown, PE - FL #198790  
Scott Lewkowksi, PE - FL #79790  
DATE: September 20, 2023  
THIS DRAWING IS THE PROPERTY OF FDS ENGINEERING ASSOCIATES. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN PERMISSION OF FDS ENGINEERING ASSOCIATES.


**PARK SQUARE**  
**HORIZONS WEST**  
**6-UNIT - ADAMS END UNITS**

title:  
project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:


**S2.3**








NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





RSH	ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft						
WIND SPEED (ULTIMATE)	140.0 MPH						
WIND SPEED (ALLOWABLE)	108.4 MPH						
EXPOSURE CATEGORY	C						
EFFECTIVE WIND AREA (SQ FEET)	(+) VALUE DENOTES PRESSURE (-) VALUE DENOTES SUCTION						
AREA	ROOF	1	2e	2n	2r	3	3e
10	HIP	-35.94	-49.57	-49.57	-49.57	-49.57	-49.57
	GABLE	-38.22	-38.22	-60.99	-60.99	-60.99	-78.58
ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):							
ZONE 1: ASTM F1667 RSR-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C. IN FIELD							
ZONE 2e, 2n, 2r: ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD							
ZONE 3, 3e, 3r: ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD							
ROOF SHEATHING:							
SHINGLE: 3/8" EXP. 1 (2% <sub>10</sub> ) or 1/2" EXP. 1 (2% <sub>10</sub> )							
TILE: 1/2" EXP. 1 (2% <sub>10</sub> )							
NOTE:							
1. PER CODE ASTM F1667 RSR-01 REFERENCE TO 8d (2 3/4" x 0.113") NAILS							
2. WHERE THE SHEATHING THICKNESS IS GREATER THAN 1/2", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSR-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSR-04 (3" x 120") NAILS							
3. GABLES: DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.							



SYMBOL	DESIGN DESCRIPTION
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES PERFORATED SHEAR WALL, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
	INDICATES NO BOTTOM CONNECTOR REQUIRED
	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

- FRAMING NOTES:
- SEE WIND SPEED CHART ON S0 FOR WINDOW PRESSURES
  - AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL FB06/D3
- GENERAL NOTES:
- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD), THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
  - ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITHIN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
  - SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

#### PLAN KEY NOTES






- 12" SQ CMU COLUMN W(2)#5 FULLY GROUTED


#### BUILDER NOTE:

TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON TRUSSES PROVIDED BY A1 INDUSTRIES, PROJECT NAME CP5M06 w/ TRUSS DESIGN DATED 4/13/23 IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND DATE ABOVE

#### -----STOP-----

AND CALL THE ENGINEER OF RECORD PRIOR TO PLACEMENT OF ANY TRUSSES.

SYMBOL	DESIGN DESCRIPTION
	2x_ INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE




## KEY PLAN LOW ROOF & FLOOR FRAMING PLAN

SCALE: 1/4" = 1'-0"



4017 W. 1st Street  
Sanford, FL 32771  
ph: 407 829 8900  
fax: 407 829 2040  
www.badesignstudios.com



FDS JOB NO.:

PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS

title:

project no. 2022144

checked: AB

drawn:


date: 05-19-22




scale:


# S2.4

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE <u>BEARING WALL SCHEDULE</u> ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE <u>BEARING WOOD BEARING SCHEDULE</u> ON SN
	2x WOOD FRAME WALL @ 9'-0"



# S3.1

The structural design of this building is in accordance with the FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL and is certified as such



RSH

ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft

WIND SPEED (ULTIMATE)  
WIND SPEED (ALLOWABLE)  
EXPOSURE CATEGORY

140.0 MPH  
108.4 MPH  
C

EFFECTIVE WIND AREA (50 FEET)

WIND PRESSURE AND SUCTION (PSF)  
(+) VALUE DENOTES PRESSURE  
(-) VALUE DENOTES SUCTION

AREA	ROOF	1	2a	2n	2r	3	3a	3r
10	HIP	-35.94	-49.57		-49.57	-49.57		
	GABLE	-38.22	-38.22	-60.99	-60.99		-60.99	-78.58

ROOF NAILING SCHEDULE / NAILING ZONES (SHINGLE AND TILE):  
ZONE 1: ASTM F1667 RSRs-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C. IN FIELD  
ZONE 2a, 2n, 2r: ASTM F1667 RSRs-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD  
ZONE 3, 3a, 3r: ASTM F1667 RSRs-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD  
ROOF SHEATHING:  
SHINGLE: 7/16" EXP. 1 (E<sub>1</sub>) or 1/2" EXP. 1 (E<sub>2</sub>)  
TILE: 1/2" EXP. 1 (E<sub>2</sub>)  
NOTE:  
1. PER CODE ASTM F1667 RSRs-01 REFERENCE TO 8d (2 3/8" x 0.113") NAILS  
2. WHERE THE SHEATHING THICKNESS IS GREATER THAN 1/2", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSRs-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSRs-04 (3" x 120") NAILS  
3. GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.  
HIP ROOF > 20 TO 27 DEG.  
[4:12]-[6:12]

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n

2a

2n

2r

2a

2n

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n

2a

2n

2r

2a

2n

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n

2a

2n

2r

2a

2n

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n

2a

2n

2r

2a

2n

GABLE ROOF > 20 TO 27 DEG.  
[4:12]-[6:12]

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n

2a

2n

2r

2a

2n

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n

2a

2n

2r

2a

2n

3

2a

2n

2r

3

1

2

3

2

1

2a

2n

2r

2a

2n


2a








2n

2r

2a

2n






SYMBOL	DESIGN DESCRIPTION
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES PERFORATED SHEAR WALL, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE DETAIL WF37/SN FOR PLY ATTACHMENT AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
	INDICATES NO BOTTOM CONNECTOR REQUIRED
	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

- FRAMING NOTES:
- SEE WIND SPEED CHART ON S0 FOR WINDOW PRESSURES
  - AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL FB06/D3
- GENERAL NOTES:
- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD), THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESPONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
  - ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITHIN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
  - SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

- PLAN KEY NOTES
- SEE DETAIL WS18/D3 FOR RAISED HEEL TYP. U.N.O.

**BUILDER NOTE:**  
TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON TRUSSES PROVIDED BY A1 INDUSTRIES. PROJECT NAME CP5M16 w/ TRUSS DESIGN DATED 4/13/23 IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND DATE ABOVE

**---STOP---**  
AND CALL THE ENGINEER OF RECORD PRIOR TO PLACEMENT OF ANY TRUSSES.

SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	2x WOOD FRAME WALL @ 9'-0"

KEY PLAN

ROOF FRAMING PLAN

SCALE: 1/4" = 1'-0"

title:

project no. 2022144

checked: AB

drawn:

date: 05-19-22

scale:

S3.2

B&A Design Studio, Inc.

4017 W. 1st Street  
Sanford, FL 32771  
ph 407 829 8900  
fax 407 829 2040  
www.badesignstudios.com

N.C.B.D.C.

288 Southhall Lane, Suite 200, Maitland, FL 32751  
Professional Engineer  
Certificate of Authorization No. 5161  
□ CARL A. BROWN, PE - FL # 5628  
□ SCOTT LEWIS, PE - FL # 78790  
DATE: September 20, 2023  
BY: [Signature]  
FOR THE STRUCTURAL ENGINEER OF THIS PROJECT, THE DESIGNER HAS NO LIABILITY FOR THE STRUCTURAL DESIGN OF THIS PROJECT.

FDS

ENGINEERING ASSOCIATES  
288 Southhall Lane, Suite 200, Maitland, FL 32751  
Professional Engineer  
Certificate of Authorization No. 5161  
□ CARL A. BROWN, PE - FL # 5628  
□ SCOTT LEWIS, PE - FL # 78790  
DATE: September 20, 2023  
BY: [Signature]  
FOR THE STRUCTURAL ENGINEER OF THIS PROJECT, THE DESIGNER HAS NO LIABILITY FOR THE STRUCTURAL DESIGN OF THIS PROJECT.



WWW.FDSENGINEERING.COM

FDS JOB NO.:

PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS








NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





LINTEL DESIGNATION SCHEDULE			
MARK	LINTEL DESIGN	MARK	LINTEL DESIGN
(A)	8RF6-0B/1T	(H)	8RF30-1B/1T
(B)	8F8-0B/1T	(J)	8F32-1B/1T
(C)	8RF14-1B/1T	(K)	8RF14-0B/1T
(D)	8F16-1B/1T	(L)	8F16-0B/1T
(E)	8F20-1B/1T	(M)	8F20-0B/1T
(F)	8RF22-1B/1T	(N)	8RF22-0B/1T
(G)	8F24-1B/1T	(P)	8F24-0B/1T

- GENERAL INSTALLATION NOTES:**
1. PROVIDE FULL MORTAR HEAD AND BED JOINTS.
  2. SHARE FILLED LINTELS ARE REQUIRED
  3. INSTALLATION OF LINTEL MUST COMPLY w/ THE ARCHITECTURAL AND STRUCTURAL DRAWINGS
  4. LINTELS ARE LOCATED MANUFACTURED w/ 5/8" LONG NOTCHES AT THE END TO ACCOMMODATE VERTICAL CELL REINFORCING AND GROUTING.
  5. ALL LINTELS MEET OR EXCEED L/360 VERTICAL DEFLECTION, EXCEPT LINTELS 17'-4" AND LONGER w/ NOMINAL HEIGHT OF 8" MEET OR EXCEED L/180
  6. BOTTOM FIELD ADDED REBAR TO BE LOCATED AT THE BOTTOM OF THE LINTEL CAVITY
  7. 1/2" Ø WIRE STIRRUPS ARE WELDED TO THE BOTTOM STEEL FOR MECHANICAL ANCHORAGE
  8. CAST-IN-PLACE CONC. MAY BE PROVIDED IN COMPOSITE LINTELS IN LIEU OF CMU
  9. SAFE LOAD RATING BASED ON RATIONAL DESIGN ANALYSIS PER ACI 318 AND ACI 530
  10. FLORIDA APPROVAL NUMBER 158.1
  11. THE EXTERIOR SURFACE OF LINTELS INSTALLED IN EXTERIOR CONCRETE MASONRY WALLS SHALL HAVE A COATING OF STUCCO APPLIED IN ACCORDANCE WITH ASTM C-926 OR OTHER APPROVED COATING
  12. LINTELS LOADED SIMULTANEOUSLY w/ VERTICAL (GRAVITY AND UPLIFT) AND HORIZONTAL (LATERAL) LOADS SHOULD BE FOR COMBINE LOADING WITH THE FOLLOWING EQUATIONS:  
$$\frac{\text{APPLIED VERTICAL LOAD}}{\text{SAFE VERTICAL LOAD}} + \frac{\text{APPLIED HORIZONTAL LOAD}}{\text{SAFE HORIZONTAL LOAD}} \leq 1.0$$
- GENERAL MATERIAL NOTES:**
1. 7c PRECAST LINTEL = 3500 P.S.I.
  2. 7c PRESTRESSED LINTEL = 6000 P.S.I.
  3. GROUTED PER ASCM C476 fg = 3000 P.S.I. w/ MAX 3/4" AGGREGATE AND 8" TO 11" SUMP
  4. CMU PER ASTM C90 w/ MIN NET AREA COMPRESSION STRENGTH = 2000 P.S.I
  5. REBAR PER ASTM A615 GRADE 60
  6. 270 LOW RELAXATION 1/2" WIRE PER ASTM A510
  7. MORTAR PER ASTM C270 TYPE M OR S
- GENERAL LINTEL NOTES:**
1. AREAS OF BLOCK ABV. MASONRY OPENINGS ARE TO BE GROUTED SOLID TO TIE BEAM.
  2. 1-#5 REBAR IN TIE BEAM IS TO BE CONT. THROUGH OUT INCLUDING ABV. MASONRY OPENINGS. U.N.O.
  3. ALL STANDARD LINTELS TO HAVE MIN. 4" BEARING EACH END BASED ON CAST CRETE, LOTT'S, AND QUALITY LINTEL SPECS.
  4. LINTEL MINIMUM DEPTHS ARE CALLED OUT ON LINTEL PLAN. IF CONTRACTOR INSTALLS A DEEPER LINTEL THAN INDICATED ON THE PLAN, DOING THIS INCREASES THE STRENGTH OF THE LINTEL AND IS APPROVED WITHOUT ENGINEERING LETTER. IF A SMALLER LINTEL IS INSTALLED CONTACT EOR FOR APPROVAL.
  5. (\*) ANY LINTEL DEEPER THAN 32" HAS BEEN VERIFIED TO WORK AS A MIN. 32" FOR THE LOAD CONDITIONS. ANY LINTEL GREATER THAN 32" HAS A GREATER CAPACITY AND THEREFORE IS ADEQUATE FOR THE LOADS
  6. G.C. TO VERIFY ALL LINTEL DIMENSIONS IN FIELD. DIMENSIONS SHOWN ARE CLEAR SPAN ONLY



LINTEL MINIMUM DEPTHS ARE CALLED OUT ON LINTEL PLAN. IF CONTRACTOR INSTALLS A DEEPER LINTEL THAN INDICATED ON THE PLAN, DOING THIS INCREASES THE STRENGTH OF THE LINTEL AND IS APPROVED WITHOUT ENGINEERING LETTER. IF A SMALLER LINTEL IS INSTALLED CONTACT EOR FOR APPROVAL (SEE SHEET L1 FOR LINTEL SCHEDULE).

**B&A Design Studio, Inc.**  
4017 W. 1st Street  
Sanford, FL 32771  
ph: 407 839 8900  
fax: 407 839 2040  
www.badesignstudios.com

**N.C.B.D.C.**  
REGISTERED PROFESSIONAL  
ARCHITECT  
FLORIDA  
A.I. AMERICAN INSTITUTE OF ARCHITECTS  
DATE: September 20, 2023



**FDS**  
FDS ENGINEERING ASSOCIATES  
258 Southall Lane, Suite 200, Maitland, FL 32751  
Tel: 407-839-8900  
Fax: 407-839-2040  
Email: info@fdeseng.com  
Certification of Authorization No. 5161  
□ CARL A. BROWN, PE - FL #5626  
□ SCOTT LEWIS, PE - FL #78780  
DATE: September 20, 2023  
BY: [Signature]  
FOR THE STRUCTURAL ENGINEER OF THIS DRAWING, THE DESIGNER HAS REVIEWED THE DRAWING FOR CONFORMANCE WITH THE FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL AND IS CERTIFIED AS SUCH.

**PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS**

title:  
project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:  
**L1**

COPYRIGHT © 2020 ASHTON WOODS RESERVES COPYRIGHT & OTHER RIGHTS RESTRICTING THESE DOCUMENTS TO THE ORIGINAL SITE OR PURPOSE FOR WHICH THEY WERE PREPARED. REPRODUCTIONS, CHANGES OR ASSIGNMENTS ARE PROHIBITED.





## CAST CRETE OR QUALITY/ LOTTS LINTEL LOAD SPECIFICATIONS

### SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS








LENG.T.H	TYPE	SAFE LOAD - POUNDS PER LINEAR FOOT	SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS							
			8F8-0B	8F12-0B	8F16-0B	8F20-0B	8F24-0B	8F28-0B	8F32-0B	8F32-1B
2'-10" (34")	PRECAST	2231	3069	4605	6113	7547	8974	10394	11809	11809
3'-6" (42")	PRECAST	2231	3069	4605	6113	7547	8974	10394	11809	11809
4'-0" (48")	PRECAST	1966	2561	2751	3820	4890	5961	7034	8107	8107
4'-6" (54")	PRECAST	1599	2189	2379	3448	4518	5589	6661	7734	7734
5'-4" (64")	PRECAST	1217	1349	1438	1999	2560	3123	3686	4249	4249
5'-10" (70")	PRECAST	1062	1105	1173	1631	2090	2549	3009	3470	3470
6'-6" (78")	PRECAST	908	1238	2177	3480	5381	8360	10394	8825	8825
7'-6" (90")	PRECAST	743	1011	1729	2632	2205	2698	3191	3685	3685
9'-4" (112")	PRECAST	554	699	1160	1625	2564	3486	2818	3302	3302
10'-6" (126")	PRECAST	475	535	890	1247	2093	2777	2163	2536	2536
11'-4" (136")	PRECAST	362	582	945	1366	1846	2423	3127	4006	4006
12'-0" (144")	PRECAST	337	540	873	1254	1684	2193	2805	3552	3552
13'-4" (160")	PRECAST	296	471	755	1075	1428	1838	2316	2883	2883
14'-0" (168")	PRECAST	279	424	706	1002	1326	1697	2127	2630	2630
14'-8" (176")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
15'-4" (184")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
17'-4" (208")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
19'-4" (232")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
21'-4" (256")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
22'-0" (264")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
24'-0" (288")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR

(#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GR40 FIELD ADDED REBAR.

### SAFE UPLIFT LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS

LENG.T.H	TYPE	SAFE UPLIFT LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS							
		8F8-1T	8F12-1T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1T	8F32-2T
2'-10" (34")	PRECAST	1972	3173	4460	5747	7034	8321	9608	9608
3'-6" (42")	PRECAST	1569	2524	3547	4569	5591	6613	7636	7636
4'-0" (48")	PRECAST	1363	2192	3079	3966	4853	5740	6627	6627
4'-6" (54")	PRECAST	1207	1940	2724	3508	4292	5077	5861	5861
5'-4" (64")	PRECAST	1016	1632	2290	2949	3607	4265	4924	4924
5'-10" (70")	PRECAST	909	1492	2093	2694	3295	3897	4498	4498
6'-6" (78")	PRECAST	835	1340	1880	2419	2959	3498	4038	4038
7'-6" (90")	PRECAST	727	1166	1634	2102	2571	3039	3508	3508
9'-4" (112")	PRECAST	591	851	1326	1705	2084	2463	2842	2842
10'-6" (126")	PRECAST	530	686	1183	1526	1865	2204	2544	2544
11'-4" (136")	PRECAST	470	599	1028	1422	1738	2053	2369	2369
12'-0" (144")	PRECAST	470	543	928	1349	1649	1948	2247	2247
13'-4" (160")	PRECAST	428	455	770	1145	1444	1718	1993	1993
14'-0" (168")	PRECAST	384	323	519	671	823	976	1129	1129
14'-8" (176")	PRESTRESSED	246	390	655	968	1324	1625	1874	1874
15'-4" (184")	PRESTRESSED	224	302	485	626	767	909	1052	1052
17'-4" (208")	PRESTRESSED	187	255	404	520	637	754	872	872
19'-4" (232")	PRESTRESSED	162	222	347	446	546	646	746	746
21'-4" (256")	PRESTRESSED	142	198	306	393	480	567	654	654
22'-0" (264")	PRESTRESSED	137	192	295	378	461	545	629	629
24'-0" (288")	PRESTRESSED	124	175	267	341	416	491	566	566

(#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GR40 FIELD ADDED REBAR.





FOUNDATION SCHEDULE				
MARK	SIZE	DEPTH	REINFORCING	GRAVITY CAP. (lbs)
F1.5	1'-6" x 1'-6"	1'-0"	(2) #5 E.W. BOT.	3500
F2.0	2'-0" x 2'-0"	1'-0"	(3) #5 E.W. BOT.	7200
F2.5	2'-6" x 2'-6"	1'-0"	(3) #5 E.W. BOT.	11000
F3.0	3'-0" x 3'-0"	1'-0"	(4) #5 E.W. BOT.	15600
F3.5	3'-6" x 3'-6"	1'-0"	(4) #5 E.W. BOT.	21500
F4.0	4'-0" x 4'-0"	1'-0"	(5) #5 E.W. BOT.	28000
F4.5	4'-6" x 4'-6"	1'-4"	(5) #5 E.W. BOT.	34500
F5.0	5'-0" x 5'-0"	1'-4"	(6) #5 E.W. BOT.	42500
F6.0	6'-0" x 5'-0"	1'-6"	(8) #5 E.W. BOT.	

FOUNDATION DETAIL NOTE:


- INTERIOR PAD DEPTHS AS LISTED IN THE SCHEDULE ARE THE TOTAL DEPTH AND MEASURED FROM THE TOP OF THE SLAB.
- EXTERIOR PAD DEPTHS AS LISTED IN THE SCHEDULE ARE TOTAL DEPTH WITH THE BOTTOM OF THE FOOTING TO MATCH THE BOTTOM OF THE CONTINUOUS MONOLITHIC POUR WHICH RUNS THROUGH IT.

GENERAL FOUNDATION NOTES:

- PROVIDE MIN. 6 MIL. APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MIN. 6" AND SEALED.
- 4" 2500 PSI CONC. SLAB WITH W1:4XW1.4 OVER 6 MIL. VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES.
- GC/BUILDER, SEE ARCH PLANS FOR ROUGH OPENING LOCATIONS AND ADDITIONAL INFORMATION REQ'D FOR DOOR/WINDOW.
- INSTALLATION ALONG W/ DIMENSIONS NOT SHOWN ON FOUNDATION CONSULT W/ MANUFACTURER SPECIFICATIONS PRIOR TO POURING OR RECESSING DRAIN SILLS OR SLIDING GLASS DOOR SILLS.
- NO WOOD STAKES PERMITTED IN FOUNDATION.
- PENDING SITE CONDITIONS, FOUNDATION MAY HAVE TO BE STEPPED DOWN. SEE **FM1801** FOR ADDITIONAL INFORMATION. G.C. TO DETERMINE STEP LOCATIONS, IF REQUIRED.
- STEEL BENDS AND LAP SPICE: SEE **FM1801** AND **FM19D1**.
- ALL EQUIPMENT AND/OR APPLIANCES HAVING AN IGNITION SOURCE SHALL BE ELEVATED A MIN OF 18" CONTRACTOR TO PROVIDE SUCH PLATFORM W/ EITHER MASONRY OR WOOD CONSTRUCTION.
- ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 2000 PSF (SEE SOILS REPORT AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS). IF SOIL CONDITIONS ON THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY, THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF SOIL CONDITIONS. SOIL TO BE FREE OF ORGANIC MATERIAL AND COHESIVE SOLS. COMPACTION IN 12" LIFTS TO AT LEAST 95% OF MAX. DRY DENSITY AS DETERMINED BY ASTM D 1557 (MODIFIED PROCTOR).
- R-403 1/4" MINIMUM DEPTH EXTERIOR FINISHES SHALL BE PLACED NOT LESS THAN 12 INCHES (305mm) BELOW THE FINISHED GRADE OF GROUND SURFACE.

COLUMN SCHEDULE				
MARK	COLUMN SIZE	FIRST FLOOR BASE CONNECTIONS, SEE PLAN FOR SECOND FLOOR CONNECTIONS	UPLIFT(lb)	
C1	(3) 2x #2 SPF	(4)12d TOENAILS	NO UPLIFT	
C2	(3) 2x #2 SPF	DTT22 W/ 1/2" ATR & (8) 3/4" x 1 1/2" SDS SCREWS	1835	
C3	(3) 2x #2 SPF	(4)12d TOENAILS	NO UPLIFT	
C4	(3) 2x #2 SPF	DTT22 W/ 1/2" ATR & (8) 3/4" x 1 1/2" SDS SCREWS	1835	
C5	4x4 P.T.#2 SYP POST	ABU44 w/ 3/4" ATR & (12)16d NAILS FIRST/SECOND FLOOR CONN.	G = 6665 U = 1782	
C6	6x6 P.T.#2 SYP POST	ABU66 w/ 3/4" ATR & (12)16d NAILS FIRST/SECOND FLOOR CONN.	G = 12000 U = 2070	
C7	8x8 P.T.#2 SYP POST	ABU88 w/2 3/4" ATR & (18)16d NAILS FIRST/SECOND FLOOR CONN.	G = 24335 U = 2088	
C8	3.5" x 3.5" P.L. 1.8E Fb=2400 PSI (W/UNMANAGED IF EXT.)	HDU5-SDS2.5 w/ 7/4" ATR AND (14) 1/2"x2 1/2" SDS WOOD SCREWS	5080	
C9	3.5" x 2.5" P.L. 1.8E Fb=2400 PSI (W/UNMANAGED IF EXT.)	HDU5-SDS2.5 w/ 7/4" ATR AND (14) 1/2"x2 1/2" SDS WOOD SCREWS	5080	
C10	3.5" x 7" P.L. 1.8E Fb=2400 PSI (W/UNMANAGED IF EXT.)	HDU8-SDS2.5 w/ 7/4" ATR AND (20) 1/2"x2 1/2" SDS WOOD SCREWS	6372	
C11	5.25" x 5.25" P.L. 1.8E Fb=2400 PSI (W/UNMANAGED IF EXT.)	HDU8-SDS2.5 w/ 7/4" ATR AND (20) 1/2"x2 1/2" SDS WOOD SCREWS	7082	


- GENERAL COLUMN NOTES:
- ALL STRUCTURAL LUMBER TO BE SYP#2 OR SPF#2 UNO ON PLAN.
  - MINIMUM BLOCK EMBEDMENT: 5" EMBEDMENT FOR 1/2" ATR. 6" EMBEDMENT FOR 3/4" ATR. 8" EMBEDMENT FOR 1" ATR.
  - P.L. COL. TO BRG DIRECTLY ON FOUNDATION. CUT BASE PLATE AS REQ'D. G.C. TO PROVIDE MOISTURE BARRIER.
  - IF COL. IS CALLED OUT ON 2ND FLOOR, THE BASE CONNECTION IS NOT REQ'D. SEE PLANS FOR BASE CONNECTION.
  - VALUES HAVE BEEN REDUCED FOR NARROW FACE APPLICATION. CONNECTIONS SHALL BE INSTALLED ON NARROW OR WIDE FACE PER SIMPSON TC-SCLCLM




WOOD BEARING WALL SCHEDULE				
MARK	STUD SPACING	CONNECTION & FASTENERS	LUMBER SPECIES	UPLIFT CAP. (lb)
BW1	16"	(2)16d TOENAILS (3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SPF	NO UPLIFT
BW2	16"	SP2 w/ (6)10d NAILS SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF	402
BW3	16"	(2) SP2 w/ (6)10d NAILS (2) SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF	804
BW4	16"	(2)16d TOENAILS (3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SYP	NO UPLIFT
BW5	16"	SP2 w/ (6)10d NAILS SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP	439
BW6	16"	(2) SP2 w/ (6)10d NAILS (2) SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP	878
BW7	12"	(2)16d TOENAILS (3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SPF	NO UPLIFT
BW8	12"	SP2 w/ (6)10d NAILS SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF	535
BW9	12"	(2) SP2 w/ (6)10d NAILS (2) SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF	1070
BW10	12"	(2)16d TOENAILS (3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SYP	NO UPLIFT
BW11	12"	SP2 w/ (6)10d NAILS SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP	585
BW12	12"	(2) SP2 w/ (6)10d NAILS (2) SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP	1170

CROSS REFERENCE CHART

(2) 2x HEADER (U.N.O.) SEE FLOOR PLAN FOR MIN. SIZE. SEE HD/NS FOR CONNECTION INFO. IF HEADER IS WITHIN A WALL, NO UPLIFT AS INDICATED IN THE WOOD BEARING WALL SCHEDULE, THE CONNECTORS INDICATED IN WF09 & HD CAN BE IGNORED.




- ANCHOR BOLTS(S): 1/2" A.B. OR A.T.R. w/ SIMPSON SET. 2x TOP PLATE SEE PLAN. WF17/NS FOR ADDITIONAL INFO. 2x MID-SPAN BLOCKING w/ (2) 12d TOENAIL @ EA. END ONLY FOR WALLS TALLER THAN 8'-0". SIMPSON SP4 w/ (6) 10d NAILS @ 24" O.C. (SP8 FOR 2'x6" SP8 FOR 2'x8"). \*\*CONNECT ORDER TRUSS DIRECTLY TO HEADER W/ (2) SIMPSON HTS20, U.N.O.
- GENERAL BEARING WALL NOTES:
- ALL STRUCTURAL LUMBER DESIGNATED AS SYP SHALL BE SYP #2 AND ALL STRUCTURAL LUMBER DESIGNATED AS SPF SHALL BE SPF #2 U.N.O.
  - SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED UNO.
  - CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
  - CONTACT E.O.R. IF SPR#3, SPR#8 OR SPR#9 CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
  - IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO BE IGNORED. SEE WF06 AND FB06 OR INDICATED FOR PROPER CONNECTIONS FOR 2ND FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY)
  - IF "SVP" IS INDICATED ON PLAN THE WALL IS CONSIDERED A SHEAR WALL AND REQUIRES MIN. 7/16" OSB / PLYWOOD W/8d NAILS @ 4" O.C. IN FIELD AND EDGE TO ONE SIDE OF WALL, U.N.O. ON PLANS.
  - ALL 2x EXTERIOR WALLS W/ SHEATHING ATTACHED PER NAILING SCHEDULE TB13/NS ACTS AS SHEAR WALLS, SEE PLAN AND WALL SECTIONS FOR STUD SPACING AND GRADE.
  - ALL TOP PLATES AND SILL PLATES SHALL BE THE SAME SPECIES AS THE WOOD STUDS.
  - IF THE BEARING WALL IS INDICATED WITH THE BW1, BW4, BW7, BW10, THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT, THE STUDS ARE TOE NAILED TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.



HEADER SCHEDULE		HEADER NOTES	
MARK	HEADER SIZE		
H1	2x6 #2 SYP w/ 7/16" FLITCH PLATE	1. VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED.	
H2	(2) 2x8 #2 SYP w/ 7/16" FLITCH PLATE	2. IF HEADER IS ON THE 1ST FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. ON PLAN.	
H3	(2) 2x10 #2 SYP w/ 7/16" FLITCH PLATE	3. IF HEADER IS ON THE 2ND FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.	
H4	(2) 2x12 #2 SYP w/ 7/16" FLITCH PLATE	4. ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WF03/NS.	
H5	(2) 1 3/4" x 11 1/4" LVL 2.0E Fb=2600	5. FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" O.C. OR (3) ROWS IF 2x10 OR LARGER TYP. EACH SIDE OR (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE.	
H6	(2) 1 3/4" x 9 1/4" LVL 2.0E Fb=2600	6. FASTEN ALL HEADERS TO KING STUDS W/ (3) 10d TOENAILS PER SIDE.	
H7	(2) 2x10 #2 SYP w/ 1" FLITCH PLATE	7. IF HEADER IS NOT SPECIFIED CONTACT E.O.R.	
H8			

HEADER SUPPORT - NUMBER OF JACKS & STUDS REQUIRED AT OPENINGS			
OPENING SIZE	2x4 WALL	2x6 OR 2x8 WALL	
1'-0" - 3'-11"	(1)	(1)	(2)
4'-0" - 8'-11"	(2)	(3)	(4)
10'-0" - 16'-0"	(3)	(4)	(4)




- NOTES:
- OPENINGS GREATER THAN 4'-0" PROVIDE (2) 2x SILL PLATE W/ A35 CLIPS EACH SIDE.
  - NO TOP PLATE SPLICES SHALL OCCUR OVER OR WITHIN 2 FEET OF HEADER.
  - HOLD DOWN CONNECTIONS NOT REQUIRED AT BEARING WALLS WITHOUT UPLIFT.

CROSS REFERENCE CHART

SIMPSON LSTA30 / USP LSTA30  
SIMPSON SP4 / USP SP4  
SIMPSON SP6 / USP SP6  
SIMPSON SP8 / USP SP8  
SIMPSON HTS20 / USP HTW20  
SIMPSON SP2 / USP SP2  
SIMPSON A35 / USP MPA1  
SIMPSON HTT4 / USP HTT45




















BEAM SCHEDULE			
MARK	BEAM SIZE	SIMPSON - CONNECTIONS	USP - CONNECTIONS
BM1	(2) 2x8 #2 SYP w/ 3/4" OSB FLITCH PLATE	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN
BM2	(2) 2x10 #2 SYP w/ 3/4" OSB FLITCH PLATE	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL
BM3	(2) 2x12 #2 SYP w/ 3/4" OSB FLITCH PLATE	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL
BM4	(2) 1 1/2"x11 1/4" LVL 2.0E Fb=2600 PSI	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN
BM5	(2) 1 1/2"x11 1/4" LVL 2.0E Fb=2600 PSI	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE
BM6	(2) 1 1/2"x16" LVL 2.0E Fb=2600 PSI	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE
BM7	(2) 2x10 #2 SYP w/ 3/4" OSB FLITCH PLATE	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL
BM8	(2) 1 1/2"x9 1/4" LVL 2.0E Fb=2600 PSI	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE

- GENERAL BEAM NOTES:
- VERIFY W/ PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN 4" BEARING EACH END)
  - SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
  - BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.



SIMPSON STRONG TIE (C-C-2021)				USP MANUF. INC. (60th EDITION)			
MARK	TYPE	CONNECTOR & FASTENERS	SYP	SPF	CONNECTOR & FASTENERS	SYP	SPF
A	FRAME TO MASONRY	HETA16 w/ (9)10d x 1 1/2" OR HETA20 w/ (9)10d x 1 1/2"	1810		HTA16 w/ (9)10d x 1 1/2" OR HTA20 w/ (9)10d x 1 1/2"	1870	1730
B	FRAME TO FRAME	H2.5d w/ (10)8d x 2-1/2" NAILS	700	615	RT7A w/ (10)8d x 1-1/2" NAILS	630	510
C	FRAME TO FRAME	H10d w/ (18)10d x 1 1/2" RT16d w/ (18)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	1040 1015 1080 930	1015 930 850	RT16d w/ (18)10d x 1 1/2" & 8-10d RT16d w/ (18)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	1025 900 825	900
D	FRAME TO FRAME	MTS12 w/ (16)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	990	850	MTW12 w/ (16)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	965	810
E	FRAME TO MASONRY	MGT w/ (22)10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY	3965	3330	MUGT15 w/ (28)10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY	4240	3730
F	FRAME TO FRAME	HTS32 w/ (16)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	1415	1215	HTW20 w/ (24)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	1355	1140
F1	FRAME TO FRAME	(2) HTS20 w/ (36)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (6) 12d TOENAILS)	2830	2430	(2) HTW20 w/ (48)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (6) 12d TOENAILS)	2710	2280
G	FRAME TO MASONRY	HGT-2 w/ (16)10d NAILS AND (2) 3/4" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY (HGT-3 FOR 3-PLY)	10690	10690	RUFS w/ (12) W33 WOOD SCREWS AND (4) 3/4" x 5" WEDGE-BOLT	9575	6925
H	FRAME TO MASONRY	FGTR w/ (18) 1/4" x 3" SDS WOOD SCREWS AND (2) 1/2" x 5" TITEN HD ANCHOR BOLTS	4725	3400	RFUS w/ (12) W33 WOOD SCREWS AND (4) 3/4" x 5" WEDGE-BOLT	7100	
J2	FRAME TO MASONRY / FRAME	(2) LGT2 w/ (32) 16d SINKERS & (14) 1/4" x 1 1/4" TITEN TURBO (2 PLY TRUSS) OR (28) 16d SINKERS FOR FRAME (EA)	4060-M 4060-F	3500-M 3510-F	(2) LGT2 w/ (32) 16d SINKERS & (10) 1/4" x 3" WEDGE-BOLT (2 PLY TRUSS) OR (32) 16d SINKERS FOR FRAME (EA)	3100-M 4060-F	2920-M 3560-F
J3	FRAME TO MASONRY / FRAME	(2) LGT3 w/ (32) 16d x 3" SDS SCREWS & (8) 3/8" x 5" TITEN (2 PLY TRUSS) OR (28) 16d SINKERS FOR FRAME (EA)	6570-M 6960-F	4730-M 5010-F	(2) LGT3 w/ (32) 16d x 3" SDS SCREWS & (4) 3/8" x 5" WB (3 PLY TRUSS) OR (28) 16d SINKERS FOR FRAME (EA)	6760-M 7000-F	6760-M 6160-F
K	BEAM TO BEAM	HU410 OPT HU410 w/ (18) 16d x 10d NAILS	G43250 UH1795	G42800 UH1635	HD410 OPT HD410F w/ (20) 16d & (10) 10d NAILS	G43080 UH1950	
L	BEAM TO MASONRY	HU410 OPT HU410 w/ (18) TITEN TURBO 1/4" x 2 3/4" x (10) 10d NAILS	G44500 UH1800		HD410 OPT HD410F w/ (20) 3/16" x 1 3/4" WEDGE-BOLT & (10) 10d NAILS	G43080 UH1950	
L2	BEAM TO MASONRY / FRAME	HU46 OPT HU46 w/ (6) 10d NAILS & (2) 1/4" x 2 3/4" TAPER (10) 10d NAILS	G43000 UH1135	G42165 UH1135 SYP-F	HD46 OPT HU46 w/ (6) 10d NAILS & (2) 3/16" x 1 3/4" TAPER (10) 10d NAILS OR (12) 16d & (6) 10d (FOR FRAME)	G43000 UH1170	G41850 SYP-F
M	FRAME TO MASONRY	(2) HETA16 OPT (2) HETA20 1-PLY w/ (10) 10d x 1 1/2" OR 2-PLY w/ (12) 16d	1920 2365		(2) HTA16 OPT (2) HTA20 1-PLY w/ (10) 10d x 1 1/2" OR 2-PLY w/ (12) 16d	2430 2430	-
N	FRAME TO MASONRY	HTSM16 w/ (8)10d NAILS AND (4) 1/4"x2 1/4" TITEN TURBO OR HTSM20 w/ (10)10d 1/4"x5 & (4) 1/4"x2 1/4" TITEN TURBO	1110 955		HTWM16 w/ (8)10d NAILS AND (4) 1/4"x1 3/4" WEDGE-BOLT OR HTWM20 w/ (10)10d NAILS AND (4) 1/4"x1 3/4" WEDGE-BOLT	1225 1145	
P	FRAME TO MASONRY	H10S w/ (8) 8d x 1 1/2" NAILS AND (2) 3/8"x4" TITEN HD	910 785		DLGT12 w/ (8) 8d x 1 1/2" NAILS AND (2) 3/8"x4" WEDGE-BOLT	1045 920	
Q	FRAME TO MASONRY	DTT22 w/ (8) 16d x 1 1/2" SDS WOOD SCREWS AND (1) 1/2" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4)	2145 1835		DTT22 w/ (8) 16d x 1 1/2" SDS WOOD SCREWS AND (1) 1/2" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4)	1835 1510	
R	FRAME TO MASONRY	HTTS w/ (26) 10d x 1 1/2" NAILS AND (1) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4 BELOW)	4350 3740		HTT45 w/ (26) 16d x 1 1/2" NAILS AND (1) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4 BELOW)	5005	-
S	FRAME TO MASONRY	HTT4 w/ (18) 16d x 1 1/2" NAILS AND (1) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4 BELOW)	4235 3640		HTT45 w/ (18) 16d x 1 1/2" NAILS AND (1) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4 BELOW)	4160	-
T	FRAME TO FRAME	H10S w/ (24) 10d x 1 1/2" NAILS	910 785		LGUT1 w/ (23) 8d x 1 1/2" NAILS	1045 920	
U	FRAME TO MASONRY	HMMKT w/ (8) 10d x 1 1/2" SDS WOOD SCREWS & (5) 1/4"x2 1/4" TAPCONS	760 760		RT16M w/ (8) 10d x 1 1/2" NAILS & (4) 1/4" x 1 3/4" TAPCONS	1395 1225	
V	FRAME TO MASONRY	VGT w/ (16) 1/4"x3" SDS WOOD SCREWS & (2) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" w/ 12" MIN. EMBEDMENT	4940 3555		RT16M w/ (8) 10d x 1 1/2" NAILS & (4) 1/4" x 1 3/4" TAPCONS	1395 1225	
W	FRAME TO MASONRY	VGT w/ (16) 1/4"x3" SDS WOOD SCREWS & (2) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" w/ 12" MIN. EMBEDMENT	7185 5170		MUGT15 w/ (28) 10d NAILS & HTT45 w/ (18) 10d NAILS & (1) 5/8" A.T.R.	4215	
X	FRAME TO FRAME	VGT w/ (16) 1/4"x3" SDS WOOD SCREWS & HDU4-SDS2.5 w/ (10) 1/4"x2 1/2" SDS WOOD SCREWS & (1) 5/8" A.T.R.	4940 3555		(2) HTT45 w/ (28) 16d x 1 1/2" NAILS EA. & (1) 5/8" A.T.R. (SEE NOTE #4)	5005	-
Y	FRAME TO FRAME	(2) HTTS w/ (52) 16d x 1 1/2" NAILS & (2) 5/8" A.T.R. (SEE NOTE #4)	10180 8750				





**B&A Design Studio, Inc.**

4017 W. 1st Street  
Sanford, FL 32771  
ph 407 829 8900  
fax 407 829 2040  
www.badesignstudios.com

**NCBDO**

**AI**

**AMERICAN**

**INSTITUTE OF**

**BUILDING DESIGN**

**FDS**

288 Southall Lane, Suite 200, Maitland, FL 32751  
www.fdseng.com  
Office of Architecture No. 5951  
CARLA A. BROWN, PE, LE 45628  
SCOTT LEWIS, PE, LE 45628  
DATE: September 20, 2023  
PROJECT: PARK SQUARE HORIZONS WEST 6-UNIT - ADAMS END UNITS

**PARK SQUARE HORIZONS WEST 6-UNIT - ADAMS END UNITS**














title:

project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:

**D1**

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





**B&A Design Studio, Inc.**

4017 W. 1st Street  
Sanford, FL 32771  
ph: 407 823 8900  
fax: 407 823 2040  
www.badesignstudios.com

N.C.B.D.C. AMERICAN INSTITUTE OF BUILDING DESIGN

WWW.FDSBENG.COM

**FDS** ENGINEERING ASSOCIATES

288 Southall Lane, Suite 200, Maitland, FL 32751  
☐ CARL A. BROWN, PE - FL #5626  
☐ SCOTT LEWIS, PE - FL #79790  
 DATE: September 20, 2023  
THIS DRAWING IS THE PROPERTY OF FDS ENGINEERING ASSOCIATES. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN PERMISSION OF FDS ENGINEERING ASSOCIATES.

**PARK SQUARE**

**HORIZONS WEST**

**6-UNIT - ADAMS END UNITS**

title: \_\_\_\_\_

project no. 2022144

checked: AB

















drawn: \_\_\_\_\_

date: 05-19-22

scale: \_\_\_\_\_

D2





**B&A Design Studio, Inc.**

4017 W. 1st Street  
Sanford, FL 32771  
ph: 407 839 8900  
fax: 407 839 2040  
www.badesignstudios.com

project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:







# D3

**PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS**

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

COPYRIGHT © 2020 ASHTON WOODS RESERVES COPYRIGHT & OTHER RIGHTS RESTRICTING THESE DOCUMENTS TO THE ORIGINAL SITE OR PURPOSE FOR WHICH THEY WERE PREPARED. REPRODUCTIONS, CHANGES OR ASSIGNMENTS ARE PROHIBITED.





**B&A Design Studio, Inc.**

4017 W. 1st Street  
Seaford, FL 32771  
ph 407 829 8900  
fax 407 829 2040  
www.badesignstudios.com

**FDS**

288 Southall Lane, Suite 200, Maitland, FL 32751  
www.fdseng.com  
FDS JOB NO.:  
DATE: September 20, 2023

**PARK SQUARE  
HORIZONS WEST  
6-UNIT - ADAMS END UNITS**

project no. 2022144  
checked: AB  
drawn:  
date: 05-19-22  
scale:

**D4**

COPYRIGHT © 2020 ASHTON WOODS RESERVES COPYRIGHT & OTHER RIGHTS RESTRICTING THESE DOCUMENTS TO THE ORIGINAL SITE OR PURPOSE FOR WHICH THEY WERE PREPARED. REPRODUCTIONS, CHANGES OR ASSIGNMENTS ARE PROHIBITED.



