


(SUBDIVISION NAME) TOWNHOMES



4-UNIT PRESIDENTIAL TH (RAISED HEEL)

(LINCOLN-REV., WASHINGTON-REV., KENNEDY, REAGAN-REV.)

PAD SIZE 82'-0"x 55'-0"



REVISION SCHEDULE:

NO:	DATE:	DESCRIPTION:	BY:
1	05/17/22	NEW MODEL CREATED: PARAPET WALL DESIGN	C.C.
2	09/08/23	REVISED PER MODEL PER REVISIONS RECEIVED ON 09/05/2023	C.C.
3	11/27/23	ADJUSTED WINDOW HDR. HT. @ WASHINGTON UNIT, ADDED DIMS TO EXT. O.H. @ SGD, AND REVISED CRICKET @ KENNEDY / WASHINGTON UNITS	C.C.
4	11/29/23	UPDATED LOAD CALCULATION AND METER BANK	G.P.
5	12/11/23	UPDATED MASTER CHANGES	G.P.



GENERAL PRESSURE NOTES

"a" END ZONE IS ONLY WITHIN 5'-0" OF ALL EXTERIOR

(FBC) 2023 (8TH EDITION

2023 FLORIDA BUILDING CODE (EXISTING BUILDING) 8TH

2020 FLORIDA FIRE PREVENTION CODE (7TH EDITION).

OCCUPANCY CLASSIFICATION: GROUP R-3 (TOWNHOMES)

2017 NATIONAL ELECTRICAL CODE (NEC)

CONSTRUCTION TYPE: TYPE VB (FBC-R 602.3)

CONSTRUCTION WOOD FRAME CONSTRUCTION AMERICAN SOCIETY OF CIVIL ENGINEERS


NUMBER OF STORIES: 2 STORIES


2023 FLORIDA BUILDING CODE (ACCESSIBILITY) 8TH EDITION.


2023 FLORIDA BUILDING CODE (ENERGY CONSERVATION) 8TH

INDICATED PRESSURES CAN BE INTERPOLATED FOR OTHE

GOBA DRAWN BY: C.C. DESIGNED BY: MJS COVER PAGE







GENERAL NOTES KEY:

OBS - OBSCURED GLASS TEMP - TEMPERED GLASS FR - FRENCH DOORS SH - SINGLE HUNG SL - SIDE LIGHT DH - DOUBLE HUNG FG - FIXED GLASS CSMT- CASEMENT TR - TRANSOM HR - HORIZONTAL ROLLER GB - GLASS BLOCK BP - BYPASS BF - BIFOLD PKT - POCKET DOOR

- TYP. TYPICAL SVC - SERVICE DOOR CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE. DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR
- ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.

A/C CONDENSER UNIT TO BE ANCHORED TO SLAB PER CODE

- FBC-R M1307.2 & FBC-M 304. PROVIDE RECESS H&C WATER W/ DRAIN @ WASHER SPACE.
- VENT DRYER THRU EXTERIOR WALL U.N.O.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF.
- PROVIDE RECESS H&C WATER W/ DRAIN @ WASHER SPACE SAG RESISTANT DRYWALL ON ALL CEILINGS.
- D. PULL ALL DIMENSIONS FROM THE REAR OF PLAN.
- . REFER TO EXTERIOR ELEVATIONS & TYP. DETAIL SHEETS FOR EXTERIOR WALL FINISH SPEC'S.
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES.
- 3. ALL INTERIOR FRAME WALL DIMENSIONS TO BE $3\frac{1}{2}$ " U.N.O.
- 4. ALL EXTERIOR BLOCK WALL DIMENSIONS TO BE $7\frac{1}{2}$ " U.N.O. 5. C.M.U. & FRAME WALL SYSTEM SEGMENTS WHICH HAVE AN UNINTERRUPTED LENGTH OF 12'-0" OR MORE SHALL BE

CONSIDERED SHEAR WALL SWS = SHEAR WALL SEGMENTS

- OPENING BETWEEN GARAGE AND RESIDENCE SHALL BE EQUIPPED w/ A 20 MIN. FIRE RATED SOLID WOOD OR HONEYCOMB CORE STEEL DOOR NOT LESS THAN 1 3/8" THICKNESS AS PER FBC-R302.5.1.
- ENCLOSED SPACE UNDER STAIRS THAT IS ACCESSED BY A DOOR OR ACCESS PANEL SHALL HAVE WALLS, UNDER-STAIR SURFACE AND ANY SOFFITS PROTECTED ON THE ENCLOSED SIDE WITH 1/2-INCH (12.7 MM) GYPSUM BOARD.
- . GARAGE DOOR TO BE CERTIFIED BY MFR. FOR MIN. 150 M.P.H. . ALL TUB & SHOWER UNITS WILL HAVE ANTI-SCALDING DEVICES
- INSTALLED. O. ALL OPERABLE WINDOWS LOCATED MORE THAN 72" ABV.
- SURFACE BELOW SHALL HAVE THE LOWEST PORTION OF WINDOW CLEAR OPENING A MIN. OF 24" ABOVE FINISHED FLOO BEING SERVER PER (FBC-R312.2).
- 1. SEE COLOR SHEET FOR INTERIOR DOOR HEIGHT REQUIREMENTS.
- . SPECIALTY WINDOWS/DOORS, FIXED GLASS WINDOWS, AND TRANSOMS ARE NOTED ON PLANS.
- . ALL DOORS & WINDOWS THAT ARE EGRESS WILL BE LABELED AS SUCH AND CONFORM TO FBC R310.2 EERO 4. SOIL TESTING IS RECOMMENDED, BUT IS NOT REQUIRED. THE
- DESIGN TEAM AT MJS & E.O.R STRONGLY RECOMMEND A SOIL TEST TO CONFIRM SOIL BEARING CAPACITY AND SURFACE GEO-TECHNICAL CONDITIONS. FOOTINGS SHALL BEAR ON UNDISTURBED SOIL A/O PROPERLY COMPACTED FILL (2000 PS MIN.). FILL MATERIAL SHALL BE COMPACTED TO 95% DENSITY OF A STANDARD PROCTOR. TO BE VERIFIED BY GENERAL
- EQUIPPED WITH A 20 MIN. FIRE RATED SOLID WOOD OR HONEYCOMB CORE STEEL DOOR NOT LESS THAN 1 3/8" THICKNESS AS PER FBC-R302.5.1.

OPENING BETWEEN GARAGE AND RESIDENCE SHALL BE

. 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE OF WALL UNDERSIDE OF DECKING.

THERMAL BARRIER: FOAM PLASTIC SHALL BE SEPARATED FROM

- . 5/8" TYPE X DRYWALL ON GARAGE CEILING BELOW ANY HABITABLE SPACE
- THE INTERIOR OF A BUILDING BY NOT LESS THAN 1/2-INCH (12.7 MM) GYPSUM WALLBOARD, 23/32-INCH (18.2 MM) WOOD STRUCTURAL PANEL OR A MATERIAL THAT IS TESTED IN ACCORDANCE WITH AND MEETS THE ACCEPTANCE CRITERIA (BOTH THE TEMPERATURE TRANSMISSION FIRE TEST AND THE INTEGRITY FIRE TEST OF NFPA 275.
- ADDRESS NOTIFICATION SHALL BE IN ACCORDANCE w/ SECTION FBC-R319.
- ANY EXTERIOR WALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATIONS SHOULD BE FITTED WITH QUICKFLASH PANELS
- ATTIC ACCESS OPENING SHOULD BE WEATHERSTRIPPED AND INSULATED TO LEVEL EQUIVALENT TO INSULATION ON THE SURROUNDING AREAS PER FBCEC R402.2.4.
- . FILL VOIDS OF UNDERSIDE OF TUBS & SHOWERS WITH INSULATION FOR ACOUSTIC DAMPENING.
- ADD ACOUSTIC OR VIBRATION ISOLATION DEVICES AT GARAGE DOOR OPENERS THAT ARE ADJACENT TO HABITABLE SPACES
- WHERE WALL TILE IS INSTALLED IN TUB AND SHOWER AREAS, GLASS MAT GYPSUM BACKING PANELS (ASTM C1178), FIBER-REINFORCED GYPSUM PANELS (ASTM C1278), NON-ASBESTOS FIBER-CEMENT BACKER BOARD (ASTM C1288) OR NON-ASBESTOS FIBER MAT REINFORCED CEMENTITIOUS BACKER UNITS (ASTM C1325) SHALL BE USED PER FBCR R702.4. PAPER-FACED GYPSUM BOARD SHALL NOT BE USED.

VINDOW / DOOR NOTE KEY

050 = 2'-0" x 5'-0" 060 = 2'-0" x 6'-0"

ALL WINDOW CALLOUTS ARE MEASURED IN FEET & INCHES AS PER THE EXAMPLE TABLE ABOVE.

0 = 2'-0" 40 B.F. = 4'-0" BI-FOLD 24 = 2'-4" 50 B.F. = 5'-0" BI-FOLD 26 = 2'-6" 60 B.F. = 6'-0" BI-FOLD

Area Tabulations

1st floor:

2nd floor:

mechanical:

opt. cov. patio:

Living:

Total Living:

Total Area:


ALL INTERIOR DOOR HEIGHTS ARE TO BE DETERMINED BY THE BUILDER.

OIME MODELS/TOWITIONES (OTIAND	2
icion of Dark Carres	- '
rsion of rain aquale prises Inc.	
Vineland Rd. Suite #200	
ndo, Fl. 32811	

2,780	sf	V:∖Park Square Homes\MODELS\TC		ATEIN
3,881	sf	÷ S		
6,661		:\Par	ISSUE DATE	(
0,001		>	REVIS	SIO
90	_sf_	ဝင္ပ		

DRAWN BY: C.C. DESIGNED BY: MJS FIRST FLR. OVERALL **A**1

First Floor Plan SCALE: 1/4" = 1'-0"




FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

GENERAL NOTES KEY: TEMP - TEMPERED GLASS FR - FRENCH DOORS

SH - SINGLE HUNG

SCALE: AS NOTED DRAWN BY: C.C. DESIGNED BY: MJS Second Floor Plan

SCALE: 1/4" = 1'-0"



houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

GOBA
GREATER ORLANDO BUILDERS ASSOCIATION PROJECT: 00-0000

SCALE: AS NOTED

DRAWN BY: C.C.


Slab Plan

SCALE: 1/4" = 1'-0"

SLAB PLAN

A3

DESIGNED BY: MJS



houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

GOBA
GREATER ORLANDO BUILDERS ASSOCIATION PROJECT: 00-0000

SCALE: AS NOTED


DRAWN BY: C.C. DESIGNED BY: MJS


Slab Plan


SCALE: 1/4" = 1'-0"

SLAB PLAN

A3







houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

GENERAL NOTES KEY:


EXTEND JACK POST "C" TO CMU BOND BEAM & LEDGER BELOW AND SECURE w/ (2) HTS-20 AT TOP

CONNECTION & w/ (2) MSTA-30 OR (2) HTS-20 TO

A > (2) 2x JACK POST

B > (3) 2x JACK POST

A6 SCALE: 1/4" = 1'-0"





SCALE: 1/4" = 1'-0"

THOMPSON ENGINEERING GROUP, INC.

4401 Vineland Road Suite A6 Orlando, FL. 32811

Ph: (407) 734-1790

www.tegfl.com

Contractors shall verify and be responsible for dimensions and conditions of the job and MJS, inc. must be notified in writing of any changes in the LECTUAL PROPERTY and specifications

Ph: (407) 629-6711

Fax: (407) 629-6776

www.mjsdesignersgroup.com

COPYRIGHT NOTICE: THESE PLANS, DESIGNS, AND
DEAS ARE THE EXCLUSIVE INTELLECTUAL PROPER

designers group

GOBA

GREATER ORLANDO BUILDERS ASSOCIATION

ington-Raised Heel)
ington-Rev., Kennedy, Reagan-Rev.
ng Pad #XX
XX, Subdivision

dels: Lincoln-Rev., Washington-Rev., Ker Building Pad #XX Lot# XX-XX, Subdivision Street Address

> nterprises Inc. 200 Vineland Rd. Suite #200 Irlando, Fl. 32811 hone: (407) 529-3000

A divisor A divi

ISSUE DATE 02/10/2023
REVISIONS
PROJECT: 00-0000

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C.
DESIGNED BY: MJS

ELEVATIONS

A8




Front Elevation

(Opt. French Drs.) SCALE: 1/4" = 1'-0"



(Opt. French Drs.) SCALE: 1/4" = 1'-0"



1 Detail
A8 SCALE: 1/2" = 1'-0"

houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS









REVISIONS

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C. DESIGNED BY: MJS

ELEVATIONS



SCALE: 1/4" = 1'-0"





9'-0"

A8 SCALE: 1/2" = 1'-0"

Detail

(TYP.)

Rear Elevation

(Opt. Covered Lanai) SCALE: 1/4" = 1'-0"









REVISIONS

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C. DESIGNED BY: MJS ELEVATIONS







9'-0"

A8 SCALE: 1/2" = 1'-0"

Detail

(TYP.)

Rear Elevation

(Opt. Covered Lanai) SCALE: 1/4" = 1'-0"











REVISIONS

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C. DESIGNED BY: MJS

ELEVATIONS





Right Elevation

(Standard)

SCALE: 1/4" = 1'-0"


houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

REVISIONS PROJECT: 00-0000
SCALE: AS NOTE
DRAWN BY: C.C. AS NOTED

GOBA

DESIGNED BY: MJS **ELEVATIONS**

A9





Right Elevation


(Standard)

SCALE: 1/4" = 1'-0"














REVISIONS

PROJECT: 00-0000
SCALE: AS NOTE
DRAWN BY: C.C. AS NOTED DESIGNED BY: MJS

ELEVATIONS


A9





GOBA REVISIONS PROJECT: 00-0000
SCALE: AS NOTE
DRAWN BY: C.C. DESIGNED BY: MJS

ELEVATIONS












REVISIONS

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C.

DESIGNED BY: MJS SECTIONS/ROOF

A10














PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C. DESIGNED BY: MJS

SECTIONS/ROOF A10











Lincoln: Building Section

SCALE: 1/4" = 1'-0"





A D O

GOBA

SSUE DATE | 02/10/2023

DRAWN BY: C.C.


DESIGNED BY: MJS

SECTIONS

A12











__U/C GFCI FOR


DISPOSAL &













Lincoln Second Floor (Opt. Bdrm.#4 ilo Loft)

4 UNIT TOWNHOUSE





FAULT CURRENT CALCULATION
I _{SC1} = 14633 AIC
L = 25 FEET
C = 11185 (4/0 AL)
E = 240 VOLT
$f = \frac{2 \times L \times I_{SC1}}{C \times E} = \frac{2 \times 25 \times 14633}{11185 \times 240} = .27$
$M = \frac{1}{1 + f} = \frac{1}{1 + .27} = .78$
$I_{SC2} = M \times I_{SC1} = .78 \times 14633 = 11414 \text{ AIC}$

TRANSFORMER TO METERCENTER #2 - 2 UNITS
FAULT CURRENT CALCULATION
I _{SC1} = 23988 AIC (50 KVA TX)
L = 140 FEET
C 21395 (500 AL)
E = 240 VOLT
$f = \frac{2 \times L \times I_{SC1}}{C \times E} = \frac{2 \times 140 \times 23988}{21395 \times 240} = 1.3$ $M = \frac{1}{1+f} = \frac{1}{1+1.3} = .43$
$I_{SC2} = M \times I_{SC1} = .43 \times 23988 = 10315 AIC$

METERCENTER #2 TO CLOSEST TOWNHOUSE PANEL - 2 UNITS

FAULT CURRENT CALCULATION
SC1 = 10315 AIC
. = 25 FEET
= 11185 (4/0 AL)
= 240 VOLT
$f = \frac{2 \times L \times I_{SC1}}{C \times E} = \frac{2 \times 25 \times 10315}{11185 \times 240} = .19$
$M = \frac{1}{1 + f} = \frac{1}{1 + .19} = .84$
$I_{SC2} = M \times I_{SC1} = .84 \times 10315 = 8665 AIC$

GENERAL NOTES KEY

- . BUILDER TO VERIFY EXACT LOCATION OF FLOOR OUTLETS IN FIELD.
- ALL OUTLETS ARE TO BE AFCI PROTECTED.
 - ALL 15A AND 20A 120V BRANCH CIRCUITS WILL BE AFCI
 - . ALL 15A AND 20A 120V BRANCH CIRCUITS LOCATED IN
 - THE GARAGE AND LAUNDRY WILL BE GFCI PROTECTED.
 - ALL GARAGE BAYS WILL HAVE DEDICATED GFCI OUTLET.
- ALL OUTLETS LOCATED IN THE KITCHEN AND BATHROOMS ARE TO BE GFCI PROTECTED.
- DW. AND GARBAGE DISPOSAL ARE TO BE GFCI
- . EXCEPTIONS TO THE GFCI STIPULATION WILL BE ALLOWED ONLY IF ALLOWED PER CURRENT NFPA / NEC.
- OUTLETS LOCATED IN THE LAUNDRY ARE TO BE GFCI AND AFCI PROTECTED.

0. OUTLETS LOCATED WITHIN 6'-0" OF A WET AREA ARE TO

- BE GFCI PROTECTED.
- 1. ALL OUTLETS OVER COUNTERTOPS TO BE 42" A.F.F.
- 2. ALL SMOKE/CARBON MONOXIDE DETECTORS ARE TO BE HARD WIRED, INTERCONNECTED AND AFCI PROTECTED.
- 13. 8'-0" HEIGHT VANITY LIGHTS IN MASTER BATHROOM AND 7'-0" IN ALL OTHER BATHROOMS.
- 14. ANY EXTERIOR WALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATIONS SHOULD BE FITTED WITH QUICKFLASH PANELS (OR SIMILAR).
- 5. RECESSED LUMINAIRES INSTALLED IN THE BUILDING THERMAL ENVELOPE ARE SUBJECT TO THE PROVISIONS OF FBCEC R402.4.5. FIXTURES SHALL BE IC-RATED (FOR
- ZERO CLEARANCE INSULATION CONTACT) AND SEALED AIR TIGHT. ALSO SEE FBCE 410.116. THIS DIAGRAMMATIC PLAN IS INTENDED TO SHOW
- LIGHTING AND CONVENIENCE OUTLETS ONLY. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO VERIFY THE REQUIREMENT AND LOCATIONS OF ALL ELECTRICAL EQUIPMENT, (INCLUDING KITCHEN EQUIPMENT) AND PROVIDE AND INSTALL COMPLETE ELECTRICAL SERVICE AS REQUIRED PER NFPA, NEC, FBC CODES AND ALL REIGNING MUNICIPALITY CODES, STANDARDS AND
- LOCATION OF FIXTURES AND / OR OUTLETS ARE SUGGESTED LOCATIONS AND MEET MOST LOCAL CODE REQUIREMENTS. ADDITIONS OR ADJUSTMENTS MAY BE MADE BETWEEN THE OWNER AND BUILDER IN THE FIELD. ALL ELECTRICAL WORK AND APPLIANCES ARE IN FULL COMPLIANCE WITH N.F.P.A., N.E.C., F.B.C. 8TH EDITION (2023) RESIDENTIAL, AND ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES. VARIOUS SYMBOLS ON ELECTRICAL LEGEND MAY OR MAY NOT BE USED ON THIS PLAN.
- LL SMOKE/CARBON DETECTOR LOCATIONS MUST BE A MINNIMUM OF 3' FROM ANY BATHROOM PER FBC-R314.3 (4). THEY MUST ALSO BE LOCATED NO MORE THAN 10' FROM

ELECTRICAL KEY:

_		РÉ				_1		
-	CEILING MOUNTED LIGHT			4	_ <u> </u>			
-\rightarrow_PC	PULL CHAIN LIGHT	Series\4-Unit Presidential TH (Raised						
	FLUSH-MOUNT LED	dent						
\mapsto	WALL MOUNTED LIGHT	resi		G (3	P	Λ	
	WALL WASH RECESSED	nit P						
\Rightarrow	DUPLEX RECEPTACLE	4-U	GRE	ATER ORLA	NDO BOIL	DENS AS	SUCIAT	IUN
#	220 V RECEPTACLE	ries\						
	1/2 HOT, 1/2 SWITCHED			·				
₩P	WATER PROOF RECEPTACLE	- 55'	Heel)	ev.				
	FLOOR RECEPTACLE	leel)	ΙĔ	Reagan-Rev.				
=	PRE-WIRE FOR CLG. FAN	ed F		keag				
⊕ _{GFI}	GROUND FAULT INTERRUPT	Rais	l S	λ, F				
\$	WALL SWITCH) se	<u>i</u> S	Kennedy,		n		4
\$ ₃	3-WAY SWITCH	lom(a	Ke	♉	ViSi	(0	g
\$□	DIMMER SWITCH	wn	14	ev.,	#	bd	res	
M	TELEPHONE JACK	E TC	0	on-F	Pad	Su	βb	į,
\leftarrow I	CABLE JACK	s\Presidential Townhomes (Raised Heel)-	rlando-Raised	Washington-Rev.,	Building Pad #XX	t# XX-XX, Subdivision	Street Address	City, State, 7in Code
$\overline{\Rightarrow}$	PRE-WIRE GARAGE DOOR OPENER	esid	a۲	/ash	ij	≾	Stre	ζ.
	FLUORESCENT LIGHT	s/Pr	Ī	≶ .	В	t#	0,	<u>:</u>

ELECTRICAL PANEL

L DISCONNECT SWITCH

WALL SCONCE

FAN / LIGHT COMBINATION

JUNCTION BOX

A.F. ARC FAULT PROTECTION

• L.V. LOW VOLTAGE

V.P. VAPOR PROOF

以 IC INTERCOM

GARBAGE DISPOSAL MOTOR

• S.D. | SMOKE DETECTOR

⇒⊭⇒ | CEILING FAN

ELECTRICAL METER

Ho DOOR BELL / GARAGE DOOR SWITCH

C.M.S.D. CARBON MONOXIDE / SMOKE DETECTOR

FLUSH MOUNT FLUORESCENT LIGHT

PROJECT: 00-0000
SCALE: AS NOTE
DRAWN BY: C.C.

ELECTRICAL LAYOUT E1

Electrical Plan SCALE: 1/4" = 1'-0"

ELEC. METERS TO BE SPLIT ON EACH END UNIT,

BASED ON BLDG. CONFIGURATION (M)

6-UNIT: 3EA.SIDE 5-UNIT: 3 & 2\EA. SIDE: FIELD VERIFY

> Lincoln-Rev. First Floor SCALE: 1/4" = 1'-0"

OPT. | 40 AMP /240\ GFI OUTLET FOR EV |


CHARGING

CLG. FAN/LITE


SCALE: 1/4" = 1'-0"

Washington-Rev.- First Floor (Opt. Cov. Patio w/ S.G.D.)


SCALE: 1/4" = 1'-0"



Washington-Rev.- First Floor (Opt. Cov. Patio w/ Opt. FR. DR.) SCALE: 1/4" = 1'-0"




Washington-Rev.- First Floor (Standard)
SCALE: 1/4" = 1'-0"




Washington-Rev.- First Floor (Opt. FR. DR.)

SCALE: 1/4" = 1'-0"



Washington-Rev.- Second Floor (Standard)
SCALE: 1/4" = 1'-0"

GENERAL NOTES KEY: ALL OUTLETS ARE TO BE AFCI PROTECTED. . ALL 15A AND 20A 120V BRANCH CIRCUITS WILL BE AFCI PROTECTED. ALL 15A AND 20A 120V BRANCH CIRCUITS LOCATED IN THE GARAGE AND LAUNDRY WILL BE GFCI PROTECTED. ALL GARAGE BAYS WILL HAVE DEDICATED GFCI OUTLET. ALL OUTLETS LOCATED IN THE KITCHEN AND BATHROOMS ARE TO BE GFCI PROTECTED. DW. AND GARBAGE DISPOSAL ARE TO BE GFCI EXCEPTIONS TO THE GFCI STIPULATION WILL BE ALLOWED ONLY IF ALLOWED PER CURRENT NFPA / NEC. OUTLETS LOCATED IN THE LAUNDRY ARE TO BE GFCI AND AFCI PROTECTED. 0. OUTLETS LOCATED WITHIN 6'-0" OF A WET AREA ARE TO BE GFCI PROTECTED. . ALL OUTLETS OVER COUNTERTOPS TO BE 42" A.F.F. 2. ALL SMOKE/CARBON MONOXIDE DETECTORS ARE TO BE HARD WIRED, INTERCONNECTED AND AFCI PROTECTED. 8. 8'-0" HEIGHT VANITY LIGHTS IN MASTER BATHROOM AND 7'-0" IN ALL OTHER BATHROOMS. 4. ANY EXTERIOR WALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATIONS SHOULD BE FITTED WITH QUICKFLASH PANELS (OR SIMILAR). 5. RECESSED LUMINAIRES INSTALLED IN THE BUILDING THERMAL ENVELOPE ARE SUBJECT TO THE PROVISIONS OF FBCEC R402.4.5. FIXTURES SHALL BE IC-RATED (FOR ZERO CLEARANCE INSULATION CONTACT) AND SEALED AIR TIGHT. ALSO SEE FBCE 410.116. THIS DIAGRAMMATIC PLAN IS INTENDED TO SHOW LIGHTING AND CONVENIENCE OUTLETS ONLY. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO VERIFY THE REQUIREMENT AND LOCATIONS OF ALL ELECTRICAL EQUIPMENT, (INCLUDING KITCHEN EQUIPMENT) AND PROVIDE AND INSTALL COMPLETE ELECTRICAL SERVICE AS REQUIRED PER NFPA, NEC, FBC CODES AND ALL REIGNING MUNICIPALITY CODES, STANDARDS AND SUGGESTED LOCATIONS AND MEET MOST LOCAL CODE REQUIREMENTS. ADDITIONS OR ADJUSTMENTS MAY BE MADE BETWEEN THE OWNER AND BUILDER IN THE FIELD ALL ELECTRICAL WORK AND APPLIANCES ARE IN FULL COMPLIANCE WITH N.F.P.A., N.E.C., F.B.C. 8TH EDITION (2023) RESIDENTIAL, AND ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES. VARIOUS SYMBOLS ON ELECTRICAL LEGEND MAY OR MAY NOT BE USED ON THIS PLAN. LL SMOKE/CARBON DETECTOR LOCATIONS MUST BE A MINNIMUM OF 3' FROM ANY BATHROOM PER FBC-R314.3 (4). THEY MUST ALSO BE LOCATED NO MORE THAN 10' FROM **ELECTRICAL KEY:** M W CEILING MOUNTED LIGHT PULL CHAIN LIGHT FLUSH-MOUNT LED WALL MOUNTED LIGHT WALL WASH RECESSED DUPLEX RECEPTACLE 220 V RECEPTACLE 1/2 HOT, 1/2 SWITCHED WATER PROOF RECEPTACLE FLOOR RECEPTACLE PRE-WIRE FOR CLG. FAN GROUND FAULT INTERRUPT WALL SWITCH



CHANDELIER

JUNCTION BOX

A.F. ARC FAULT PROTECTION

• L.V. LOW VOLTAGE

以 IC INTERCOM


FLUSH MOUNT FLUORESCENT LIGHT


FAN / LIGHT COMBINATION GARBAGE DISPOSAL MOTOR

DRAWN BY: C.C.


Electrical Plan

DESIGNED BY: MJS E2 SCALE: 1/4" = 1'-0"





Kennedy First Floor SCALE: 1/4" = 1'-0"



Kennedy Second Floor SCALE: 1/4" = 1'-0"

GENERAL NOTES KEY

- . BUILDER TO VERIFY EXACT LOCATION OF FLOOR OUTLETS IN FIELD.
- . ALL OUTLETS ARE TO BE AFCI PROTECTED.
 - ALL 15A AND 20A 120V BRANCH CIRCUITS WILL BE AFCI PROTECTED.
- ALL 15A AND 20A 120V BRANCH CIRCUITS LOCATED IN THE GARAGE AND LAUNDRY WILL BE GFCI PROTECTED.
- ALL GARAGE BAYS WILL HAVE DEDICATED GFCI OUTLET. ALL OUTLETS LOCATED IN THE KITCHEN AND
- BATHROOMS ARE TO BE GFCI PROTECTED.
- . DW. AND GARBAGE DISPOSAL ARE TO BE GFCI PROTECTED.
- 8. EXCEPTIONS TO THE GFCI STIPULATION WILL BE ALLOWED ONLY IF ALLOWED PER CURRENT NFPA / NEC. OUTLETS LOCATED IN THE LAUNDRY ARE TO BE GFCI
- AND AFCI PROTECTED.

0. OUTLETS LOCATED WITHIN 6'-0" OF A WET AREA ARE TO

11. ALL OUTLETS OVER COUNTERTOPS TO BE 42" A.F.F.

7'-0" IN ALL OTHER BATHROOMS.

BE GFCI PROTECTED.

- 2. ALL SMOKE/CARBON MONOXIDE DETECTORS ARE TO BE
- HARD WIRED, INTERCONNECTED AND AFCI PROTECTED. 13. 8'-0" HEIGHT VANITY LIGHTS IN MASTER BATHROOM AND
- 14. ANY EXTERIOR WALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATIONS SHOULD BE FITTED WITH
- QUICKFLASH PANELS (OR SIMILAR). 5. RECESSED LUMINAIRES INSTALLED IN THE BUILDING
- THERMAL ENVELOPE ARE SUBJECT TO THE PROVISIONS OF FBCEC R402.4.5. FIXTURES SHALL BE IC-RATED (FOR ZERO CLEARANCE INSULATION CONTACT) AND SEALED
- AIR TIGHT. ALSO SEE FBCE 410.116. THIS DIAGRAMMATIC PLAN IS INTENDED TO SHOW LIGHTING AND CONVENIENCE OUTLETS ONLY. IT IS THE
- ELECTRICAL CONTRACTORS RESPONSIBILITY TO VERIFY THE REQUIREMENT AND LOCATIONS OF ALL ELECTRICAL EQUIPMENT, (INCLUDING KITCHEN EQUIPMENT) AND PROVIDE AND INSTALL COMPLETE ELECTRICAL SERVICE AS REQUIRED PER NFPA, NEC, FBC CODES AND ALL REIGNING MUNICIPALITY CODES, STANDARDS AND ORDINANCES. LOCATION OF FIXTURES AND / OR OUTLETS ARE
- SUGGESTED LOCATIONS AND MEET MOST LOCAL CODE REQUIREMENTS. ADDITIONS OR ADJUSTMENTS MAY BE MADE BETWEEN THE OWNER AND BUILDER IN THE FIELD. ALL ELECTRICAL WORK AND APPLIANCES ARE IN FULL COMPLIANCE WITH N.F.P.A., N.E.C., F.B.C. 8TH EDITION (2023) RESIDENTIAL, AND ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES. VARIOUS SYMBOLS ON ELECTRICAL LEGEND MAY OR MAY NOT BE USED ON THIS PLAN.

SMOKE DETECTOR REQUIREMENTS: ALL SMOKE/CARBON DETECTOR LOCATIONS MUST BE A MINNIMUM OF 3' FROM ANY BATHROOM PER FBC-R314.3 (4). THEY MUST ALSO BE LOCATED NO MORE THAN 10' FROM NY BEDROOM DOOR OPENING PER FBC-R315.1.

ELECTRICAL KEY:

CEILING MOUNTED LIGHT

PULL CHAIN LIGHT

FLUSH-MOUNT LED

WALL MOUNTED LIGHT WALL WASH RECESSED DUPLEX RECEPTACLE 220 V RECEPTACLE

1/2 HOT, 1/2 SWITCHED

FLOOR RECEPTACLE PRE-WIRE FOR CLG. FAN

GFI GROUND FAULT INTERRUPT

WALL SWITCH 3-WAY SWITCH

FLUORESCENT LIGHT

L DISCONNECT SWITCH M ELECTRICAL METER

> WALL SCONCE CHANDELIER SPOT LIGHT

SPEAKER

• L.V. | LOW VOLTAGE V.P. VAPOR PROOF

以 IC INTERCOM

JUNCTION BOX

A.F. ARC FAULT PROTECTION

FAN / LIGHT COMBINATION

GARBAGE DISPOSAL MOTOR

S.D. | SMOKE DETECTOR

CEILING FAN

ELECTRICAL PANEL

\$□ DIMMER SWITCH ▼ TELEPHONE JACK

<→ CABLE JACK

OO CHIME

WATER PROOF RECEPTACLE

PRE-WIRE GARAGE DOOR OPENER

Ho DOOR BELL / GARAGE DOOR SWITCH

C.M.S.D. CARBON MONOXIDE / SMOKE DETECTOR

FLUSH MOUNT FLUORESCENT LIGHT










REVISIONS


PROJECT: 00-0000
SCALE: AS NOTE
DRAWN BY: C.C.

DESIGNED BY: MJS ELECTRICAL LAYOUT **E**3

Electrical Plan SCALE: 1/4" = 1'-0"




Reagan-Rev. (Opt.) Patio




Reagan-Rev. First Floor

SCALE: 1/4" = 1'-0"




Reagan-Rev. (Opt.) Bath WITH SOAKING TUB SCALE: 1/4" = 1'-0"



Reagan-Rev. Second Floor

SCALE: 1/4" = 1'-0"



Reagan-Rev. Second Floor (Opt. Bdrm.#4 ilo Loft)

SCALE: 1/4" = 1'-0"

GENERAL NOTES KEY

. BUILDER TO VERIFY EXACT LOCATION OF FLOOR OUTLETS IN FIELD.

ALL OUTLETS ARE TO BE AFCI PROTECTED. ALL 15A AND 20A 120V BRANCH CIRCUITS WILL BE AFCI

ALL 15A AND 20A 120V BRANCH CIRCUITS LOCATED IN

THE GARAGE AND LAUNDRY WILL BE GFCI PROTECTED.

ALL GARAGE BAYS WILL HAVE DEDICATED GFCI OUTLET. ALL OUTLETS LOCATED IN THE KITCHEN AND

BATHROOMS ARE TO BE GFCI PROTECTED. . DW. AND GARBAGE DISPOSAL ARE TO BE GFCI

. EXCEPTIONS TO THE GFCI STIPULATION WILL BE ALLOWED ONLY IF ALLOWED PER CURRENT NFPA / NEC. OUTLETS LOCATED IN THE LAUNDRY ARE TO BE GFCI

AND AFCI PROTECTED. 0. OUTLETS LOCATED WITHIN 6'-0" OF A WET AREA ARE TO BE GFCI PROTECTED.

1. ALL OUTLETS OVER COUNTERTOPS TO BE 42" A.F.F.

7'-0" IN ALL OTHER BATHROOMS.

QUICKFLASH PANELS (OR SIMILAR).

2. ALL SMOKE/CARBON MONOXIDE DETECTORS ARE TO BE HARD WIRED, INTERCONNECTED AND AFCI PROTECTED. 13. 8'-0" HEIGHT VANITY LIGHTS IN MASTER BATHROOM AND

14. ANY EXTERIOR WALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATIONS SHOULD BE FITTED WITH

5. RECESSED LUMINAIRES INSTALLED IN THE BUILDING THERMAL ENVELOPE ARE SUBJECT TO THE PROVISIONS OF FBCEC R402.4.5. FIXTURES SHALL BE IC-RATED (FOR

ZERO CLEARANCE INSULATION CONTACT) AND SEALED AIR TIGHT. ALSO SEE FBCE 410.116.

THIS DIAGRAMMATIC PLAN IS INTENDED TO SHOW LIGHTING AND CONVENIENCE OUTLETS ONLY. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO VERIFY THE REQUIREMENT AND LOCATIONS OF ALL ELECTRICAL EQUIPMENT, (INCLUDING KITCHEN EQUIPMENT) AND PROVIDE AND INSTALL COMPLETE ELECTRICAL SERVICE AS REQUIRED PER NFPA, NEC, FBC CODES AND ALL REIGNING MUNICIPALITY CODES, STANDARDS AND

LOCATION OF FIXTURES AND / OR OUTLETS ARE SUGGESTED LOCATIONS AND MEET MOST LOCAL CODE REQUIREMENTS. ADDITIONS OR ADJUSTMENTS MAY BE MADE BETWEEN THE OWNER AND BUILDER IN THE FIELD. ALL ELECTRICAL WORK AND APPLIANCES ARE IN FULL COMPLIANCE WITH N.F.P.A., N.E.C., F.B.C. 8TH EDITION (2023) RESIDENTIAL, AND ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES. VARIOUS SYMBOLS ON ELECTRICAL LEGEND MAY OR MAY NOT BE USED ON THIS PLAN.

LL SMOKE/CARBON DETECTOR LOCATIONS MUST BE A MINNIMUM OF 3' FROM ANY BATHROOM PER FBC-R314.3 (4). THEY MUST ALSO BE LOCATED NO MORE THAN 10' FROM NY BEDROOM DOOR OPENING PER FBC-R315.1.

ELECTRICAL KEY:

CEILING MOUNTED LIGHT

PULL CHAIN LIGHT

FLUSH-MOUNT LED

WALL MOUNTED LIGHT

WALL WASH RECESSED DUPLEX RECEPTACLE 220 V RECEPTACLE 1/2 HOT, 1/2 SWITCHED

WATER PROOF RECEPTACLE

FLOOR RECEPTACLE

WALL SWITCH 3-WAY SWITCH

DIMMER SWITCH

── | FLUORESCENT LIGHT ELECTRICAL PANEL

L DISCONNECT SWITCH

WALL SCONCE

FAN / LIGHT COMBINATION

JUNCTION BOX

A.F. ARC FAULT PROTECTION

• L.V. | LOW VOLTAGE

V.P. VAPOR PROOF

以 IC INTERCOM

GARBAGE DISPOSAL MOTOR

• S.D. | SMOKE DETECTOR

⇒⊭⇒ | CEILING FAN

ELECTRICAL METER

▼ TELEPHONE JACK

< ⊢ CABLE JACK

PRE-WIRE FOR CLG. FAN GROUND FAULT INTERRUPT

PRE-WIRE GARAGE DOOR OPENER

Ho DOOR BELL / GARAGE DOOR SWITCH

C.M.S.D. CARBON MONOXIDE / SMOKE DETECTOR

FLUSH MOUNT FLUORESCENT LIGHT









PROJECT: 00-0000
SCALE: AS NOTE
DRAWN BY: C.C.

ELECTRICAL LAYOUT E4

Electrical Plan

houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

SCALE: 1/4" = 1'-0"

VERIFICATION OF FIELD CONDITIONS:

CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS AND DIMENSIONS RELATIVE TO SAME. WHERE THERE ARE CONFLICTS BETWEEN ACTUAL FIELD CONDITIONS AND DATA PRESENTED IN THE DRAWINGS, SUCH CONDITIONS SHALL BE CALLED TO THE ARCHITECT'S AND OR TO THE ENGINEER OF RECORD'S (EOR) ATTENTION AND NECESSARY ADJUSTMENTS MADE PER THEIR INSTRUCTIONS.

FIELD REPAIR NOTES

- MISSED FOOTING DOWELS MAY BE SUBSTITUTED W/ A STRAIGHT #5 REBAR SET IN A 3/4" DIA. x 6" DEEP HOLE FILLED W/ UNITEX PROPOXY 300 OR SIMPSON SET OR ETF ADHESIVES.

2- BLOCK WALL OVERHANGING SLAB CONDITION: UP TO 7/8" - NO REPAIR NECESSARY 7/8" TO 11/4" - ADD FILLED CELL (NO VERTICAL STEEL) MIDPOINT OF WALL BETWEEN EXISTING FILLED CELLS (WITH STEEL) IN AREAS AFFECTED. 11/4"+ - REQUIRE SPECIAL ENGINEERING

3- PENETRATION OF PLUMBING PIPES/DRYER VENTS THRU PLATES OF A LOAD BEARING WALL MAY OCCUR PROVIDED DBL. STUDS ARE ADDED ON EITHER SIDE OF PENETRATION WITHIN 3" AND TRUSS/FLOOR TRUSS IS NO CLOSER THAN 3" FROM PENETRATION. ADD (I) MTS I 2 @ TOP AND BOTTOM PLATE.

TO SUIT EQUIP. FURN 4" TYP. SIDES SHT. ANGLE BRACKETS OR 2" WIDE 20GA. GALV. STEEL - STRAPS PAD ABOVE BASE FLOOD ELEVATION CONDENSER 4" THICK CONC. PAD SEE UNIT PLAN FOR UNIT LOCATION REFRIGERANT PIPING TO AIR

HANDLING UNIT — CONNECT TO UNIT W/ #14 SHEET METAL SCREWS W/ GASKETED WASHERS & CONNECT TO PAD W/1/4"x 11/4" TAPCON SCREW OR 3/8" BOLT. SEE TABLE FOR QTY. PER SIDE

ANCHOR SPACING TABLE								
LENGTH/SIDE	No. OF ANCHORS/SIDES							
LESS THAN 12"	ONE / SIDE							
12" - 24"	TWO / SIDE							
36" UP \$ 5 TONS \$ UP	FOUR / SIDE							

COND. ANCHOR DETAIL

FOUNDATION NOTES

- CONTRACTOR VERIFY ALL DIMENSIONS ON JOB SITE.
- DENOTES FILL CELL REINF. W/ CONC. W/ (1) #5 REBAR. GRADE 60 DENOTES FILL CELL REINF. W/ CONC. W/ (2) #5 REBAR. GRADE 60.
- DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S. I. 4" THICK WITH 6X6 10/10 GAUGE REINFORCING MAT. W/ MIN. I" COVER TERMITE TREATED SOIL WITH 0.006mm (6mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WWF SHALL BE PLACE IN MIDDLE TO UPPER THIRD OF SLAB AND SUPPORTED ON APPROVED SLAB BOLSTERS. *FIBER MESH
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPER-VISOR FOR CLARIFICATION.


REINFORCEMENT MAY USED AS ALTERNATIVE TO WIRE.

WATER HEATER T&P RELIEF VALVE SHALL E FULL SIZE TO EXTERIO WATER HEATER AT OR ABOVE FLOOR LEVEL 61-FALL E IN A FAN WITH DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED

THERMAL EXPANSION DEVICE

COMMUNITY AND COUNTY CODES.

- PAVERS MAY BE USED ILO CONCRETE SLABS IN PATIO, PORCH, DRIVE AND WALKWAY AREAS. DELETE SLAB IN AREAS PAVERS AR
- MECHANICAL EQUIP. LOCATIONS WILL BE DETERMINED BY
- IN LIEU OF TREATING THE SOIL, AN ALTERNATIVE TO TERMITE
- TREATED SOIL CA BE PREMISE 75 WP TERMICIDE.
- BORA -CARE TO BE APPLIED ON INTERIOR WALLS W/ MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS, PURSUANT FLORIDA BUILDING CODE LATEST EDITION.
-). WOOD STAIRS STRINGERS IN CONTACT WITH CONCRETE SHALL E PROTECTED BY AN IMPERVIOUS MOISTURE BARRIER OR SHALL BE OF NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD PER FBC R317.1









AS NOTED DRAWN BY: C.C. DESIGNED BY: MJS

FOUNDATION PLAN

S1

Foundation Plan

FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

SCALE: 1/4" = 1'-0"

CAST CF	_	TS / WEKIWA / F ST LINTEL SCHI	
LINTEL NO.	LENGTH	TYPE	COMMENTS
L-1	17'-4"	8F32-1B/1T	GARAGE DOOR
L-2	9'-4"	8F32-1B/1T	GARAGE DOOR
L-3	4'-6"	8RF14-1B/1T	FRONT DOOR
L-4	5'-4"	8F16-1B/1T	FRONT ENTRY
L-5	4'-6"	8F16-1B/1T	WINDOW
L-6	7'-6"	8F16-1B/1T	WINDOW
L-7	9'-4"	8F16-1B/1T	S.G.D.
L-8	5'-4"	8F16-1B/1T	ENTRY

SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS

SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS									
SAFE LOAD - POUNDS PER LINEAR FOOT									
LENGTH	TYPE	8U8	8F8-0B 8F8-1B				8F24-0B 8F24-1B		8F32-0B 8F32-1B
3'-6" (42")	PRECAST	2231	3069 3069	3719 4605	5163 6113	6607 7547	8054 8974	9502 10394	10951 11809
4'-0" (48")	PRECAST	1966	2561 2693	2751 4605	3820 6113	4890 7547	5961 8974	7034 10394	8107
4'-6" (54")	PRECAST	1599	1969	2110	2931	3753	4576	5400	11809 6224
5'-4" (64")	PRECAST	1217	2189 1349	4375 1438	6113 1999	7547 ₍₇₎ 2560	3123	10294 3686	11809 4249
5'-10" (70")			1663 1105	3090 1173	5365 1631	7547 ₍₃₆₎ 2090	7342 ₍₁₉₎ 2549	8733 ₍₁₉₎ 3009	10127 ₍₁₉₎ 3470
		1062	1451 1238	2622 2177	4360 3480	7168 ₍₄₅₎ 3031	6036 ₍₁₉₎ 3707	7181 ₍₁₉₎ 4383	8328 ₍₂₀₎ 5061
, ,	PRECAST	908	1238 1011	2177 1729	3480 2632	5381 2205	8360 2698	10394 ₍₃₇₎ 3191	
7'-6" (90")	PRECAST	743	1011	1729	2661	3898	5681	8467 (44)	6472 (15)
9'-4" (112")	PRECAST	554	699 752	1160 1245	1625 1843	2564 2564	3486 3486	2818 4705 ₍₃₇₎	3302 6390 ₍₄₇₎
10'-6" (126")	PRECAST	475	535 643	890 1052	1247 1533	2093 2093	2777 2781	2163 3643 ₍₃₈₎	2536 4754 ₍₄₅₎
11'-4" (136")	PRECAST	362	582 582	945 945	1366 1366	1846 1846	2423 2423	3127 3127	4006 4006
12'-0" (144")	PRECAST	337	540	873	1254	1684	2193	2805	3552
13'-4" (160")		296	540 471	873 755	1254 1075	1684 1428	2193 1838	2805 2316	3552 2883
14'-0" (168")		279	471 424	755 706	1075 1002	1428 1326	1838 1697	2316 2127	2883 2630
, ,			442 NR	706 NR	1002 NR	1326 NR	1697 NR	2127 NR	2630 NR
14'-8" (176")		N.R.	458 NR	783 NR	1370 NR	1902 NR	2245 NR	2517 NR	2712 NR
15'-4" (184")	PKESTKESSED	N.R.	412	710	1250	1733	2058	2320	2513
17'-4" (208")	PRESTRESSED	N.R.	NR 300	NR 548	950	NR 1326	NR 1609	NR 1849	NR 2047
19'-4" (232")	PRESTRESSED	N.R.	NR 235	NR 420	NR 750	NR 1037	NR 1282	NR 1515	NR 1716
21'-4" (256")	PRESTRESSED	N.R.	NR 180	NR 340	NR 598	NR 845	NR 1114	NR 1359	NR 1468
22'-0" (264")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR
24'-0" (288")	PRESTRESSED	N.R.	165 NR	315 NR	550 NR	784 NR	1047 NR	1285 NR	1399 NR
	DEDC IN DADENTI		129	250	450	654 D 6DADE	884	1092	1222

	ERS IN PARENTHESI JPLIFT LOADS							
		SAFE	LOAD	- POUN	IDS PE	R LINE	AR FO	TC
	TYPE	8F8-1T	8F12-1T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1T
LENGTH		8F8-2T	8F12-2T	8F16-2T	8F20-2T	8F24-2T	8F28-2T	8F32-2T
-' -" (40")	=====	1569	2655	3524	4394	5263	6132	7001
3'-6" (42")	PRECAST	1569	2655	3524	4394	5263	6132	7001
4' O" (AQ")	DDECACT	1363	2305	3060	3815	4570	5325	6079
4'-0" (48")	PRECAST	1363	2305	3060	3815	4570	5325	6079
4'-6" (54")	PRECAST	1207	2040	2707	3375	4043	4711	5379
4 -0 (5+)	PREUASI	1207	2040	2707	3375	4043	4711	5379
5'-4" (64")	DDECACT	1016	1715(11)	2276 (4)	2838	3399	3961	4522
5 -4 (04)	PRECAST	1016	1715	2276	2838	3399	3961	4522
E' 10"(70")	DDECACT	909	1567(18)	2080(13)	2593 (9)	3107 ₍₆₎	3620 ₍₄₎	4133 (
5'-10" (70")	PRECAST	929	1567	2080	2593	3107	3620	4133
6'-6" (78")	PRECAST	835 (12)	1407(26)	1868(21)	2329 (18)	2790(16)	3251(14)	+
0 -0 (70)	PRECASI ,	835	1407	1868	2329	2790	3251	3712
7' 0" (00")	DDECACT	727 (23)	1065(26)) 1624 (31)	2025 (28)	2426(26)	2827 (25)	3228 (2
7'-6" (90")	PRECAST	727	1224	1624	2025	2426	2827	3228
9'-4" (112")	- DDECACT	591	708 (25)	1136 (34)	1474 (34)	1815 (34)	2157 (34)	2500 (3
9 -4 (112)	PRECASI ,	591	862	1318	1643	1969	2294	2619
10' 6" (106")	DDECACT	530	575 (24)	916 (33)	1188 (33)	1461(33)	1736 (33)	2011 (3
10'-6" (126")	PRECASI I	530	695	1180 (8)			†	2346
4" (470")	COLOT	474	504 (23)			· · · · · ·		
11'-4" (136")	PRECASI	494	607	1042(10)				
-1 -7 /4 4 4 7		470 (9)						
12'-0" (144")	PRECASI	470	550	940 (10)				
		418 (15)						
13'-4" (160")	PRECASI	428	460	780 (9)				
	====	384 (15)		1	1		1	-
14'-0" (168")	PRECAST	410	425	717 (9)	1 1	· · · ·		·
* - " / : ¬ o "		239	334 (21)	1	` '			· ·
14'-8" (176")	PRESTRESSED	246	395	663 (9)	1			
	SOCIOTOCOCO	224	313 (20)			· · · ·	(/	+
15'-4" (184")	PRESTRESSED	230	368	616 (9)				
	=======================================	187	263 (19)					1
17'-4" (208)	PRESTRESSED	192	306	506 (8)				
		162	229 (17)					
19'-4 (232)	PRESTRESSED	166	263	429 (8)				
- '1 '" (050")		142	204 (16)					
21'-4" (256)	PRESTRESSED	142	232	373 (7)				
		137	197 (15)					
22'-0" (264")	PRESTRESSED	137	223	358 ₍₇₎				
		124	179 (14)		1			1
24'-0" (288")	PRESTRESSED	124	202	319 (7)				·
							757 ₍₂₇₎ R U-LIN1	

		SAFE	LOAD	- POUN	IDS PE	R LINE	AR FOO	TC
TYPE	ODUG	8RF6-0B	8RF10-0B	8RF14-0B	8RF18-0B	8RF22-0B	8RF26-0B	8RF30-0
LENGTH	8RU6	8RF6-1B	8RF10-1B	8RF14-1B	8RF18-1B	8RF22-1B	8RF26-1B	8RF30-1
4' 4" (EO") DDCOACT	1675	1749	3355	3280	4349	5421	6493	7567
4'-4" (52") PRECAST	1635	1891	3699	5206	6639	8060	9479	10893
4' 6" (E4") DDCCAST	1404	1596	3063	2992	3968	4946	5924	6904
4'-6" (54") PRECAST	1494	1756	3699	5206	6639	8060	9479	10893
5'-8" (68") PRECAST	966	920	1770	1716	2277	2839	3402	3966
3 -8 (88) FILEASI	866	1167	2481	4567	6389	8060(34)	7917(19)	9311 (1
5'-10" (70") PRECAST	010	859	1653	1600	2124	2649	3174	3700
9 10 (70) TREGAST	810	1113	2342	4242	6639 (10)	8060(39)	7402(19)	8706 ₍₁
6'-8" (80") PRECAST	707	901	1825	3120	5048	7747	9448	7360
0 -8 (80) FRECASI	797	901	1825	3120	5048	7915	9479	10893(3
7'-6" (90") PRECAST	660	755	1490	2459	3776	5743	7239	5623
7 -0 (90) FRECASI	669	755	1490	2459	3776	5743	8998(19)	10893(4
9'-8" (116") PRECAST	111	466	999	1568	2253	3129	4091	3146
5 6 (110) TREGAST	411	526	999	1568	2253	3129	4150	5891 (4
(#) THE NUMBERS IN PAREN	THESIS ARI	E PERCEN	NT REDUC	TIONS FO	R GRADE	40 FIELD	ADDED	REBAR.

CAFELOAD DOUNDS DED LINEAL	
AFE UPLIFT LOADS FOR 8" PRECAST w/ 2" RECESS DOOR	U-LINT
#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GRADE 40 FIELD	ADDED RE

		SAFE LOAD - POUNDS PER LINEAR FOOT								
	TYPE	8RF6-1T	8RF10-1T	8RF14-1T	8RF18-1T	8RF22-1T	8RF26-1T	8RF30-1T		
LENGTH		8RF6-2T	8RF10-2T	8RF14-2T	8RF18-2T	8RF22-2T	8RF26-2T	8RF30-2T		
A' A" (EO")	PRECAST	905	1668	2362	3056	3751	4445	5140		
4 -4 (52)		905	1668	2362	3056	3751	4445	5140		
A' 6" (5A")	PRECAST	867	1604	2272	2939	3607	4275	4943		
4'-6" (54")		867	1604	2272	2939	3607	4275	4943		
5' 0" (60")	PRECAST	675	1269 ₍₁₆₎	1797	2326 ₍₅₎	2854 (2)	3382	3911		
3 -6 (66)		675	1269	1797	2326	2854	3382	3911		
5'-10" (70")	PRECAST	655	1207 ₍₁₆₎	1746(11)	2259 ₍₇₎	2773 ₍₅₎	3286 ₍₃₎	2799 ₍₁₎		
3 - 10 (70)		655	1233	1746	2259	2773	3286	2799		
6' 0" (00")	PRECAST	570	929 (16)	1530(22)	1980 (19)	2429(16)	2879(15)	3329 ₍₁₄₎		
0 -0 (00)		570	1080	1530	1980	2429	2879	3329		
7'-6" (90")	DDECAST	506	742 (16)	1364 (30)	1765 (27)	2166(25)	2567 (24)	2968 (23)		
/ -0 (90)	FREGASI	506	898	1364	1765	2166	2567	2968		
9'-8" (116")) DDFCAST	395	468 (15)	884 (32)	1222 (33)	1540 (34)	1859 (34)	2180 (34)		
3-0 (110)	/ I NECASI	395	560	1072	1386	1701	2016	2331		

GENERAL NOTES	
Provide full mortar bed and head joints.	
2. Shore filled lintels as required.	
Installation of lintel must comply with the architectural and/or structure documents.	اد
4. U-Lintels are manufactured with 5 1/2" long notches at the ends to	

accomodate vertical cell reinforcing and grouting.

5. Reference the CAST—CRETE Load Deflection Graph brochure for lintel

6. Bottom field added rebar to be located at the bottom of the lintel cavity. field rebar. 7. 7/32" diameter wire stirrups are welded to the bottom steel for mechanical 5. One #7 rebar may be substituted for two anchorage.
8. Cast—in—place concrete may be provided in composite lintel in lieu of #5 rebars in 8" lintels only The designer may evaluate concentrated concrete masonry units.

9. Safe load rating based on rational design analysis per ACI 318 and ACI loads from the safe load tables by calculating the maximum resisting moment and shear at d-away from face of support. 10. The exterior surface of lintels installed in exterior concrete masonry walls
7. For composite lintel heights not shown, use

shall have a coating of stucco applied in accordance with ASTM C-296 or other approved coating. 8. For lintels lengths not shown, use safe load 11. Lintels loaded simultaneously with vertical (gravity or uplift) and horizontal (lateral) loads should be checked for the combined loading with the

O. For littles lengths not shown, use safe load from next longest length shown

9. All safe loads in units of pounds per linear following equation: Applied vertical load Safe horizontal load Safe horizontal load

10. All safe loads based on simply supported span. 11. The number in the the parenthesis indicates the percent reduction for grade 40 field added rebar. Example 7'-6" lined type 12. Additional lateral load capacity can be obtained by the designer by providing additional reinforced concrete masonry above the lintel. See detail 8F32-1B safe gravity load = 6472

safe load from next lower height shown.

SAFE LOAD TABLE NOTES 1. All values based on minimum 4 inch nominal bearing. Exception: Safe loads for unfilled lintels must be reduced by 20% if


MATERIALS


1. f'c 8" precast lintel = 4000 psi f'c prestressed lintel = 6000 psi 3. Grout per ASTM C476 f'g = 3000 psi w/ maximum 3/8 inch aggregate & 8 to 11 inch slump bearing length is less than 6 1/2 inches. 2. N.R. = Not Rated Concrete Masonry Units (CMU) per ASTM C90 w/minimum net area compressive strength = 1900 psi 3. Safe loads are superimposed allowable 5. Rebar per ASTM A615 grade 60 4. Safe loads based on grade 40 or grade 60 6. Prestressing strand per ASTM A416 grade 270 low

7. Mortar per ASTM C270 type M or S

8" NOMINAL WIDTH

7 REBAL MIN. (1) L 1-1/2" CLEAR GROUT #5 REBAR AT BOTTOM OF LINTEL CAVITY BOTTOM REINFORCING PROVIDED IN LINTEL (VARIES)





ALL LINTELS OVER 9'-0" IN LENGTH NEED TO BE SHORED DURING GROUTING. CONTRACTOR SHALL FOLLOW PRECAST MANUFACTURER'S RECOMMENDATIONS REGARDING THE SHORING OF GROUTED LINTELS

2. INSTALLATION AND REMOVAL OF SHORING FOR PRE-CAST LINTELS NEED TO FOLLOW LINTEL MANUFACTURER'S SPECIFICATIONS AT ALL TIMES. AT A MINIMUM, ALL PRE-STRESSED LINTELS 14'-0" IN LENGTH OR LONGER WILL NEED TO BE SHORED WHILE CMU BLOCK IS BEING LAID AND BEFORE BOND GROUT IS POURED. SHORING WILL CONSIST OF 2x4's NAILED TOGETHER TO CREATE AN "L" OR "T" SHAPE COLUMN, AND WILL BE INSTALLED UNDERNEATH THE PRE-STRESSED LINTEL @ 8'-0" O.C. MAX. INSTALL COLUMN TO ENSURE EQUAL SUPPORT SPACING.

L-3 L-8 L-1 L-1 L-1

Lincoln-Rev.
Unit-E: LOT# XX

Washington-Rev.
Unit-D: LOT# XX

Kennedy Unit-B: LOT# XX

Reagan-Rev.
Unit-A: LOT# XX

Lintel Plan

SCALE: 1/4" = 1'-0"



GOBA

ISSUE DATE | 02/10/2023 REVISIONS

PROJECT: 00-0000 SCALE: AS NOTED DRAWN BY: C.C. DESIGNED BY: MJS

FLOOR TRUSSES

houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

L NOMINAL WIDTH

							011 7/01 00 7		
CONN	CONNECTOR SCHEDULE		98	HTT4	SILL: 7/8" BOLT	4,235	N/A		
OCIVITED TOTAL CONTEDUCE				99	A25	STRAP: 18-16d H:4-8dx1½"/P:4-8dx1½"	140	440 / 11/1	
CONNECT.	SIMPSON		NAN	LAT. LDS.	102	A35 HTT5	7/8" BOLT/ 26-10d	440	440 / N/A N/A
TYPE		FASTENERS	MAX. UPLIFT	F1/F2	102	VGTR/L	32-SDS½"X3"/(2) 7/8" BLT	3,990	N/A N/A
· · · · <u> </u>	DESCRIPTION	PER CONNECTOR	0		103	HDU8-SDS2.5	7/8" BLT/20-SDS 1/4"x21/2"	5,020	N/A
4	HETA20	14-10d x 1½"	1,810	65 / 960	110	HCP2	12-10d x 1½"	520	260 / N/A
5	DETAL20	18-10d x 1½"	2,480	2000/ 1370	167	HHUS46	H:14-16d/J:6-16d	1,550	N/A
20	H3	RFT: 4-8d / PLT: 4-8d	455	125 / 160	168	U46	H:8-10d/J:4-10d	710	N/A
21	H1	RFT:6-8dx1½"/PLT:4-8d	475	485 / 165	181	HUS26	20-16d	1,550	N/A
00	H10A OR	RFT: 8-8d x 1½"	1010	000/550	184	HUC28-2	H:14-16d/J:4-10d	1,085	N/A
22	MTS12	PLT: 8-8d x 1½"	1000	660/550	104	HUC26-2	H:12-1/4"x2-1/2" SDS"	1,000	IN/A
23	LUS26	HDR: 4-10d/JST: 4-10d	935	N/A	186	HUCQ210-2-SDS	J:6-1/4"x2-1/2" SDS	2,345	N/A
24	H7	RFT / TRS: 4-8d	985	400 / N/A				1,800 U.	
24	117	PLT / STD: 10-8d	903	400 / IN/A	190	HU210-2	J:10-0.148x3"	5,095 D.	N/A
26	H2.5	RFT:5-8d / PLT: 5-8d	415	150 / 150	190		CMU:6-1/4"x2-1/2" TITEN T."	545 U.	
34	A34	H:4-8dx1½"/P:4-8dx1½"	365	280 / 303	191	HU28	J:10-0.148x1 1/2"	1,700 D.	N/A
35	A35F	H:4-8dx1½"/P:4-8dx1½"	440	440 / N/A			LID 40.0/400V41/U TA DOOM		
37	MTS12	14-10d	1,000	N/A	214	HUC212-3TF	BM: 6-16d	1,135	N/A
38	MTS16	14-10d	1,000	N/A	215	HGUS210-2	HDR:46-16d/JST:10-16d	2,720	N/A
39	MTS30	14-10d	1000	N/A			BLOCK: 10-1/4"X11/2" TC	,	
43	LSTA12	10-10d	905	N/A	216	HUS412	JOIST : 10-16d	3,240	N/A
45	ST18	14-16d	1,200	N/A			BLOCK: 10-1/4"X11/2" TC		
47	LSTA24	18-10d	1,295	N/A	217	HUS212-2	JOIST : 10-16d	2,630	N/A
71	MSTA36	26-10d	2,135	N/A			H:1-ATR3/4X8 TOP&FACE	3,145	
72	MSTC66	64-16d SINKERS	5,495	N/A	219	MBHA412	JOIST: 18-10d		N/A
79	SP1	STD:6-10d / PLT:4-10d	535	560 / 260			HDR : (2) 3/4" φ x 8"	1 1	
80	SP2	STD:6-10d / PLT:6-10d	605	560 / 260	226	MBHA4.75/12	JOIST : 18-10d	2,160	N/A
81	SPH4,6,8	12-10d x 1½"	885	N/A			HDR : (2) 3/4" φ x 8"		
90	ABU66	12-16d	2,240	N/A	231	MBHA3.56/16	JOIST : 18-10d	3,450	N/A
89	CB66	(2) 7/8" BOLTS	2,300	985			HDR : (2) 3/4" φ x 8"		
92	ABU44	12-16d	2,200	N/A	232	MBHA5.50/16	JOIST : 18-10d	3,450	N/A
93	AC6 (MAX)	28-16d	1,815	1,070	240	H16	R:2-10dx1½"P:10-10dx1½"	1,470	480 / N/A
94	AC4 (MAX)	28-16d	1,815	1,070	241	LGT2	30-16d-sinker	2000	1015 / 440
95	HTS20	20-10d	1,450	N/A	301	MGT	(1) 5/8"BLTS./GIR: 22-10d	3,965	N/A
96	HD8A	SILL: 7/8" BOLT	7,910	N/A	302	HGT-2 or 3	LTL:3/4"BLTS./GIR: 8-10d	6485	N/A
	1150/	STUD:(3) 7/8"X51/2" BOLTS	7,515	13//	303	HGT-4	LTL:3/4"BLTS./GIR: 16-10d	9,250	N/A
		BLOCK: 4-1/4"X21/4" TC			401	SUR/L414	FACE:18-16d/JST:8-16d	1,700	N/A
97	MTSM16	JOIST : 7-10d	860	N/A	Т		BE SPECIFIED & PROVIDED BYTI	RUSS MAN	UFACTURERS

COMPONENT & CLADDING DESIGN WIND PRESSURES

SEE PLAN DESIGN WIND PRESSURE

+ XXX ULTIMATE DESIGNED POSITIVE PRESSURE
- XXX ULTIMATE DESIGNED NEGATIVE PRESSURE

NOTE: DESIGN PRESSURES BASED ULTIMATE WIND SPEED TO OBTAIN NOMINAL "ASD" WIND PRESSURES MULTIPLY VALUES

FIELD REPAIR NOTES

ENGINEERING LETTER.

@ TOP AND BOTTOM PLATE

SHOWN BY A FACTOR OF 0.6

1- MISSED FOOTING DOWELS MAY BE SUBSTITUTED W/ A STRAIGHT #5 REBAR SET IN A 3/4" DIA. x 6" DEEP HOLE FILLED W/ UNITEX PROPOXY 300 OR SIMPSON SET OR ETF ADHESIVES.

2- BLOCK WALL OVERHANGING SLAB CONDITION: UP TO 7/8" - NO REPAIR NECESSARY 7/8" TO 11/4" - ADD FILLED CELL (NO VERTICAL STEEL) MIDPOINT OF WALL BETWEEN EXISTING FILLED CELLS (WITH STEEL) IN AREAS AFFECTED. 11/4"+ - REQUIRE SPECIAL

3- PENETRATION OF PLUMBING PIPES/DRYER VENTS THRU PLATES OF A LOAD BEARING WALL MAY OCCUR PROVIDED DBL. STUDS ARE ADDED ON EITHER SIDE OF PENETRATION WITHIN 3" AND TRUSS/FLOOR TRUSS IS NO CLOSER THAN 3" FROM PENETRATION. ADD (1) MTS12

NOTES

TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.

2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.

B. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC.STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH 8TH EDITION (2023)FLORIDA RESIDENTIAL CODE.

4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZE BY TRUSS MANUFACTURER OR FL. REG. ENG.

5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY KIN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCSI 1.

6. REFER TO TRUSS MANUFACTURERS DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS


7. ROOF UNDERLAYMENT TO BE USED IS 30 LBS. SYNTHETIC FELT.

CONNECTIONS.

8. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1. UNDERLAYMENT MATERIALS REQUIRED TO COMPLY WITH ASTM D226, D1970, D4869 AND D6757 SHALL BEAR A LABEL INDICATING COMPLIANCE TO THE STANDARD DESIGNATION AND, IF APPLICABLE, TYPE CLASSIFICATION INDICATED IN TABLE R905.1.1.1 UNDERLAYMENT SHALL BE APPLIED AND ATTACHED IN ACCORDANCE WITH TABLE R905.1.1.1

9. OFF RIDGE VENTS MAXIMUM OPENING SIZES: - LOMANCO: (2) 91/3" DIA.CIRCLES

-MILLENNIUM METAL: 2½"x46" HOLE



Floor Trusses

SCALE: 1/4" = 1'-0"

FLOOR TRUSSES S3

REVISIONS

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C.

DESIGNED BY: MJS

GOBA

				Г		T T			
CONN	NNECTOR SCHEDULE		98	HTT4	SILL: 7/8" BOLT	4,235	N/A		
CONNECTOR SOFILDOLL							STRAP: 18-16d	,	
	SIMPSON				99	A35	H:4-8dx1½"/P:4-8dx1½"	440	440 / N/A
CONNECT. TYPE		FASTENERS	MAX.	LAT. LDS.	102	HTT5	7/8" BOLT/ 26-10d	4,275	N/A
ITPE	DESCRIPTION	PER CONNECTOR	UPLIFT	F1 / F2	103	VGTR/L	32-SDS1/4"X3"/(2) 7/8" BLT	3,990	N/A
4	HETA20	14-10d x 1½"	1,810	65 / 960	104	HDU8-SDS2.5	7/8" BLT/20-SDS ½"x2½"	5,020	N/A
5	DETAL20	18-10d x 1½"	2,480	2000/ 1370	110	HCP2	12-10d x 1½"	520	260 / N/A
20	H3	RFT: 4-8d / PLT: 4-8d	455	125 / 160	167	HHUS46	H:14-16d/J:6-16d	1,550	N/A
21	H1	RFT:6-8dx1½"/PLT:4-8d	475	485 / 165	168	U46	H:8-10d/J:4-10d	710	N/A
21	+	RFT: 8-8d x 1½"		4037 103	181	HUS26	20-16d	1,550	N/A
22	H10A OR	PLT: 8-8d x 1½"	1010	660/550	184	HUC28-2	H:14-16d/J:4-10d	1,085	N/A
23	MTS12 LUS26	HDR: 4-10d/JST: 4-10d	1000 935	N/A	186	HUCQ210-2-SDS	H:12-1/4"x2-1/2" SDS" J:6-1/4"x2-1/2" SDS	2,345	N/A
0.4		RFT / TRS: 4-8d	005	400 (1)(4			CMU:18-1/4"x2-1/2" TITEN T."	4 000 11	
24	H7	PLT / STD: 10-8d	985	400 / N/A	190	HU210-2-SDS	J:10-0.148x3"	1,800 U. 5,095 D.	N/A
26	H2.5	RFT:5-8d / PLT: 5-8d	415	150 / 150			CMU:6-1/4"x2-1/2" TITEN T."	545 U.	
34	A34	H:4-8dx1½"/P:4-8dx1½"	365	280 / 303	191	HU28	J:10-0.148x1 1/2"	1,700 D.	N/A
35	A35F	H:4-8dx1½"/P:4-8dx1½"	440	440 / N/A			HD:16-3/16"X1½" TAPCON		
37	MTS12	14-10d	1,000	N/A	214	HUC212-3TF	BM: 6-16d	1,135	N/A
38	MTS16	14-10d	1,000	N/A	215	HGUS210-2	HDR:46-16d/JST:10-16d	2,720	N/A
39	MTS30	14-10d	1000	N/A			BLOCK: 10-1/4"X11/2" TC	,	
43	LSTA12	10-10d	905	N/A	216	HUS412	JOIST : 10-16d	3,240	N/A
45	ST18	14-16d	1,200	N/A			BLOCK: 10-1/4"X11/2" TC		
47	LSTA24	18-10d	1,295	N/A	217	HUS212-2	JOIST : 10-16d	2,630	N/A
71	MSTA36	26-10d	2,135	N/A			H:1-ATR3/4X8 TOP&FACE		
72	MSTC66	64-16d SINKERS	5,495	N/A	219	MBHA412	JOIST: 18-10d	3,145	N/A
79	SP1	STD:6-10d / PLT:4-10d	535	560 / 260			HDR : (2) 3/4" φ x 8"		
80	SP2	STD:6-10d / PLT:6-10d	605	560 / 260	226	MBHA4.75/12	JOIST : 18-10d	2,160	N/A
81	SPH4,6,8	12-10d x 1½"	885	N/A			HDR : (2) 3/4" φ x 8"		
90	ABU66	12-16d	2,240	N/A	231	MBHA3.56/16	JOIST : 18-10d	3,450	N/A
89	CB66	(2) 7/8" BOLTS	2,300	985			HDR : (2) 3/4" φ x 8"		
92	ABU44	12-16d	2,200	N/A	232	MBHA5.50/16	JOIST : 18-10d	3,450	N/A
93	AC6 (MAX)	28-16d	1,815	1,070	240	H16	R:2-10dx1½"P:10-10dx1½"	1,470	480 / N/A
94	AC4 (MAX)	28-16d	1,815	1,070	241	LGT2	30-16d-sinker	2000	1015 / 440
95	HTS20	20-10d	1,450	N/A	301	MGT	(1) 5/8"BLTS./GIR: 22-10d	3,965	N/A
96	HD8A SILL: 7/8" BOLT	7,910	N/A	302	HGT-2 or 3	LTL:3/4"BLTS./GIR: 8-10d	6485	N/A	
90	TIDOA	STUD:(3) 7/8"X51/2" BOLTS	7,810	IN/A	303	HGT-4	LTL:3/4"BLTS./GIR: 16-10d	9,250	N/A
		BLOCK: 4-1/4"X21/4" TC			401	SUR/L414	FACE:18-16d/JST:8-16d	1,700	N/A
97	MTSM16	JOIST : 7-10d	860	N/A	T		BE SPECIFIED & PROVIDED BYTE		

COMPONENT & CLADDING DESIGN WIND PRESSURES

SEE PLAN DESIGN WIND PRESSURE + XXX ULTIMATE DESIGNED POSITIVE PRESSURE
- XXX ULTIMATE DESIGNED NEGATIVE PRESSURE

NOTE: DESIGN PRESSURES BASED ULTIMATE WIND SPEED TO OBTAIN NOMINAL "ASD" WIND PRESSURES MULTIPLY VALUES

FIELD REPAIR NOTES

SHOWN BY A FACTOR OF 0.6

1- MISSED FOOTING DOWELS MAY BE SUBSTITUTED W/ A STRAIGHT #5 REBAR SET IN A 3/4" DIA. x 6" DEEP HOLE FILLED W/ UNITEX PROPOXY 300 OR SIMPSON SET OR

2- BLOCK WALL OVERHANGING SLAB CONDITION: UP TO 7/8" - NO REPAIR NECESSARY 7/8" TO 11/4" - ADD FILLED CELL (NO VERTICAL STEEL) MIDPOINT OF WALL BETWEEN EXISTING FILLED CELLS (WITH STEEL) IN AREAS AFFECTED. 11/4"+ - REQUIRE SPECIAL ENGINEERING LETTER.

3- PENETRATION OF PLUMBING PIPES/DRYER VENTS THRU PLATES OF A LOAD BEARING WALL MAY OCCUR PROVIDED DBL. STUDS ARE ADDED ON EITHER SIDE OF PENETRATION WITHIN 3" AND TRUSS/FLOOR TRUSS IS NO CLOSER THAN 3" FROM PENETRATION. ADD (1) MTS12 @ TOP AND BOTTOM PLATE

NOTES

1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.

2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.

3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC.STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH 8TH EDITION (2023)FLORIDA RESIDENTIAL CODE.

4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZE BY TRUSS MANUFACTURER OR FL. REG. ENG.

5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY KIN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCSI 1.

6. REFER TO TRUSS MANUFACTURERS DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.


7. ROOF UNDERLAYMENT TO BE USED IS 30 LBS. SYNTHETIC FELT.

INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1. UNDERLAYMENT MATERIALS REQUIRED TO COMPLY WITH ASTM D226, D1970, D4869 AND D6757 SHALL BEAR A LABEL INDICATING COMPLIANCE TO THE STANDARD DESIGNATION AND, IF APPLICABLE, TYPE CLASSIFICATION INDICATED IN TABLE R905.1.1.1 UNDERLAYMENT SHALL BE APPLIED AND ATTACHED IN ACCORDANCE WITH TABLE R905.1.1.1

8. SHINGLE ROOF: UNDERLAYMENT TO BE

9. OFF RIDGE VENTS MAXIMUM OPENING SIZES: - LOMANCO: (2) 9½" DIA.CIRCLES

-MILLENNIUM METAL: 2½"x46" HOLE





GOBA



REVISIONS

PROJECT: 00-0000
SCALE: AS NOTED
DRAWN BY: C.C. DESIGNED BY: MJS ROOF TRUSSES

S4

STRUCTURAL NOTES

I. THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH THE 8TH EDITION, FBCR 2023 (WIND LOAD @ 140 MPH.)

LIVE LOAD ROOF: 20 PSF. FLOOR: 40 PSF, BALCONIES & STAIRS: 40 PSF OCCUPANCY= 1.0

BUILDING CATEGORY R3. WIND EXPOSURE B INTERNAL PRESSURE COEFFICIENTS = +0.18 AND -0.18

- WINDOWS, DOORS, AND GARAGE DOORS TO BE DESIGNED TO MEET FBCR SECTION R301
- 3. ALL FLOOR SLABS TO BE OF 2,500 PSI CONC. PLANT MIX MIN. 5" THICK WITH 6x6 10/10 WIRE MESH 6 MIL. POLY. VAPOR-BARRIER OVER TERMITE TREATED COMPACTED CLEAN FILL.
- 4. CONCRETE MASONRY UNITS SHALL MEET: CH. 1-3 OF ACI 530-02/ ASCE 5-02/TMS 402-02 OR BIA BUILDING CODE REQUIREMENTS.
- 5. MORTAR TO BE TYPE "M" OR "S", GROUT 2,500 PSI @ 28 DAYS.
- MASONRY CLEAN OUTS REQUIRED @ GROUT GREATER THAN FIVE (5) FEET IN HEIGHT AND ALL VERTICALS.
- REBAR TO BE # 5'S GRADE 60, W/ MIN. LAP OF 25". USE "L" BARS @ CORNERS AND USE STANDARD HOOKS @ CHANGE IN DIRECTION WITH MIN. LAP 12"
- 6. GYP. BD. CEILING SHALL BE INSTALLED PERP. TO FRAMING & NAILED @ 7" O.C. WITH 5d NAILS. GYP. BD. WALLS SHALL BE NAILED @8" O.C. WITH 5d NAILS
- 9. UPLIFT CONNECTOR'S TO PROVIDE CONTINUITY FROM ROOF TRUSSES THRU PLATES TO SLAB AND FOUNDATION PER ENCLOSED DETAILS.
- 0. EPOXY ANCHOR ALTERNATIVE:

THREADED ANCHOR ROD MAY BE USED IN LIEU OF ANCHOR BOLTS FOR USE AS PLATE ANCHORS OR HURRICANE ANCHORS. THE FOLLOWING CRITERIA MUST BE MET:

CONC. HOLE SIZE **ANCHOR SIZE** MIN. HOLE DEPTH 1-1/8" -7/8"

AFTER HOLE IS DRILLED. ALL CONCRETE DUST MUST BE REMOVED PRIOR TO EPOXY INSTALLATION. THREADED ROD TO BE MIN. A36 STEEL AND FREE OF DIRT OR GREASE. LOAD ON ROD CANNOT BE APPLIED UNTIL 12 HOURS AFTER INSTALLATION. 2 COMPONENT EPOXY RESIN MATERIAL TO BE MIXED PER MFG. DIRECTIONS.

1. SOIL BEARING CAPACITY 2000 PSF MINIMUM

WOOD STRUCTURAL NOTES

- ALL WOOD TO BE SPECIES, GROUP, AND GRADE AS NOTED BELOW. DAMAGED WOOD NOT TO BE USED.
- 2. ALL STRUCTURAL LUMBER SHALL BE SPF (SPRUCE-PINE-FIR) #2 OR BETTER UNLESS OTHERWISE NOTED. (PRE ENG. TRUSSES EXCLUDED)
- END JOINT IN STRUCTURAL DOUBLE TOP PLATE TO BE OFFSET AT LEAST 4". STRUCTURAL DOUBLE PLATES TO BE NAILED @ 6" O.K..
- 4. PLYWOOD OR OSB. WALL SHEATHING NAIL PATTERN TO BE 10d @ 6" O.C., UNLESS OTHERWISE NOTED.
- 5. NUMBER OF HEADER STUDS AND ADJACENT FULL LENGTH STUDS PER WALL AND HEADER STUD REQUIREMENT SCHEDULE
- 6. MAX. 1" HOLE DRILLED INTO EXTERIOR STRUCTURAL STUDS.
- 7. DBL. STUDS @ EA. END OF SHEAR WALL.
- 8. WHEN ANCHORING MULTIPLE WD. ITEMS TOGETHER, THE LENGTH OF HURRICANE STRAP MUST BE CENTERED
- 9. NAIL PATTERN

-DOUBLE PLATE 12" O.C., OUTSIDE SPLICE ZONE (SEE NOTE 4)

-DOUBLE STUDS @ 12" O.C.. -DOUBLE OR TRIPLE HEADER @ 6" O.C.. @ EDGE @ 12" O.C.. INTERMEDIATE.

-HEADER TO STUD @ 4" O.C.. EA. HEADER MEMBER. -STUD TO TOP OR BOTTOM PLATE : (2) 16d THRU PLT. OR (2) 16d EA. SIDE TOE NAILED TO PLT

10. -ROOF SHEATHING FOR SHINGLE ROOF TO BE MIN. 7/16" OSB. NAILED TO ROOF TRUSSES SPACED @ 24" O.C. (MAX) WITHOUT BLOCKING.


-ROOF SHEATHING FOR TILE ROOF TO BE MIN. 7/16" OSB. 1/2" CDX PLYWOOD OR 1/2" ADVANTECH. NAILED TO ROOF TO ROOF TRUSS SPACED @ 24" O.C. (MAX) WITHOUT BLOCKING.


- 11. FLOOR SHEATHING TO BE MIN. 23/32" PLYWOOD NAILED @ 6" O.C. W/ #8 RING SHANK NAILS AND LIQUID NAIL ADHESIVE.
- 12. ALL FLOOR TRUSSES TO BE END BLOCKED @ BEARING LOCATIONS
- 13. TRUSS BRACING PER TRUSS MANUFACTURE'S DRAWINGS. 14. ALL NAILING SPECIFIED TO BE APPLIED BY NAIL GUN OR MANUALLY

- ALL WOOD IN DIRECT CONTACT WITH MASONRY SHALL BE PRESSURE TREATED.
- 16. 2000 PSF MINIMUM SOIL BEARING CAPACITY

FIELD REPAIR NOTES

- MISSED LINTEL STRAPS FOR MASONRY CONSTRUCTION MAY BE SUBSTITUTED W/ (1) USP MTW16 OR HC10 OR SIMPSON MTSM16 W/ (4) -1/4" X 2-1/4" TAPCONS TO BOND BEAM AND (7) 10d NAILS TO TRUSS FOR UPLIFTS LESS THAN 860 LBS (USE (2) MTSM16 FOR UPLIFTS LESS THAN 1720#). NO MORE THAN 10 STRAPS MAY BE SUBSTITUTED OR NO MORE THAN 3 IN A ROW. IF GIRGER TRUSS CONNECTIONS ARE MISSED CONTACT ENGINEER FOR SUBTITUTION
- MISSED J-BOLTS FOR FRAMED EXTERIOR/ BEARING WALLS MAY BE SUBSTITUTED W/ 1/2" DIA. x 7" LONG WEDGE ANCHORS (REDHEADS).
- MISSED FOOTING DOWELS MAY BE SUBSTITUTED W/ A STRAIGHT #5 REBAR SET IN A 3/4" DIA. x 6" DEEP HOLE FILLED W/ UNITEX PROPOXY 300 OR SIMPSON SET OR ETF ADHESIVES.
- 4. BLOCK WALL OVERHANGING SLAB CONDITION: UP TO -7/8" - NO REPAIR NECESSARY -7/8" TO 1-1/4" - ADD FILLED CELL (NO VERTICAL STEEL) MIDPOINT OF WALL BETWEEN EXISTING FILLED CELLS (WITH STEEL) IN AREAS AFFECTED 1-1/4"+ - REQUIRE SPECIAL ENGINEERING LETTER
- 5. PENETRATION OF PLUMBING PIPES/DRYER VENTS THRU PLATES OF A LOAD BEARING WALL MAY OCCUR PROVIDED DBL. STUDS ARE ADDED ON EITHER SIDE OF PENETRATION WITHIN 3" AND TRUSS/ FLOOR TRUSS IS NO CLOSER THAN 3" FROM PENETRATION






½"X6" (4½" EMB.) HILTI KWIK -2X6 P.T. WOOD "BUCK" **BOLT WITH 2" WASHERS LOCATED** (TOP AND SIDES) @ 1',4',&7' (WITHIN 6" OF SUPPORT - GARAGE DOOR BRACKET FOR GARAGE DOOR) FROM THE BOTTOM & MIN. EDGE DISTANCE. -8" MASONRY WALL

- DETAIL TO SATISFY 150 MPH WIND LOAD - MASONRY FRAME SHALL BE MIN 8X16 ASTM C-9D - GROUT FILLED CELL W/1/2" ASTM 2 #5 REBAR (GRADE 60) @ EA. SIDE OF GARAGE DOOR OPENING - MAX. DISTANCE TO CORNER OF C.B.S. WALL REINF. 48" - REINF. TO BE CONT. FROM FTG. TO TIE BEAM W/ ALL "ACI" DETAILS & DEVELOPMENT LENGTHS ADHERED TO - GARAGE DOOR MANUF. TO PROVIDE ATTACHMENT TO "BUCK"

1.) THE GARAGE DOOR ASSEMBLY SHALL BE DESIGNED FOR POSITIVE AND NEGATIVE WIND PRESSURES OF 25 PSF IN ACCORDANCE WITH SECTION R301 OF THE FLORIDA RESIDENTIAL CODE CERTIFICATION SHALL BE SUBMITTED FROM THE GARAGE DOOR MANUFACTURER TO THE BUILDING DEPARTMENT FOR THE **FOLLOWING ITEMS:**


- A.) THE DESIGN OF THE DOOR CAN WITHSTAND POSITIVE AND NEGATIVE WIND PRESSURES OF 25 PSF
- B.) THE DESIGN OF THE DOOR COMPLIES WITH THE CRITERIA SPECIFIED IN SECTION R609 OF THE 2023 FLORIDA BUILDING CODE RESIDENTIAL, 8TH EDITION
- C.) DOOR SIZE, TYPE AND GLAZING
- D.) TRACK SIZE AND FASTENER DETAILS.
- E.) TRACK BRACKET QUANTITY, SPACING AND FASTENER DETAILS.
- F.) REINFORCING MEMBER QUANTITY, LOCATION, SIZE, TYPE AND FASTENER DETAILS. (IF REQUIRED)


GARAGE BUCK DETAIL



MIN. WALL AND HEADER REQUIREMENTS

		MAXIMUM HEADER SPAN (ft.)								
		3'	6'	9'	12'	15'	18'			
UNSUPPORTED WALL HEIGHT STUD SPACING	9 C	NUMBER OF HEADER STUDS SUPPORTING END OF HEADER								
	TUE	1	1	2	2	2	2			
	S	NUMBER OF FULL-LENGTH STUDS @ EACH END OF HEADER								
10' OR LESS		2	2	3	3	3	3			
GREATER THAN 10'		2	2	3	4	5	5			






PANEL ANCHOR CONSTRUCTION

PC PANEL REINFORCING (TOP): USED IN PANELS OVER 25"S.F. IN AREA, IS EMBEDDED HORIZONTALLY IN THE MORTAR JOINTS BETWEEN EVERY OTHER COURSE. PANEL REINFORCING IS FORMED OF TWO PARALLEL WIRES, EITHER 1-5/8" O.C. (FOR USE WITH "THINLINE" SERIES GLS. BLK.) OR 2" O.C. (FOR USE W/ "PREMIERE" SERIES GLS. BLK.), W/ BUTT WELDED CROSSWIRES AT REGULAR INTERVALS. 4' AND 10' LENGTHS AVAILABLE.


PC PANEL ANCHORS (MIDDLE): ARE USED TO TIE PITTSBURGH CORNING GLASS BLOCK PANELS INTO THE SURROUNDING FRAMEWORK WHEN CHANNELS ARE NOT USED. FORMED FROM 20 GAUGE PERFORATED- THEN GALVANIZED STEEL STRIPS, PANEL ANCHORS ARE AVAIL. IN 1-3/4" WIDTHS X 24" LENGTHS.


PC EXPANSION STRIPS (BOTTOM): MADE OF WHITE POLYETHYLENE. ARE INSERTED AT THE HEAD AND THE STRIPS REPLACE MORTAR AT THESE POINTS TO CUSHION THE GLASS BLOCK AND ALLOW THE PANEL TO EXPAND & CONTRACT FREELY. FOR METAL CHANNEL OR MASONRY CHASE CONSTRUCTION. PC EXPANSION STRIPS ARE AVAILABLE 3/8" THICK X 4" WIDE X 24" LONG. FOR PANEL ANCHOR CONSTRUCTION. STD. 4" WIDE STRIPS ARE EASILY CUT TO 3" WIDTH, FOR 3-7/8" "PREMIERE" SERIES BLK., AND TO 2-1/4" WIDTH, FOR 3-1/8" "THINLINE" SERIES BLOCK.


G GLASS BLOCK DETAIL





D1
















GOBA

PROJECT: 00-0000 AS NOTED DRAWN BY: C.C. DESIGNED BY: MJS

STRUCTURAL DETAILS D6







-(2) 2X12'S W/ 1/2" PLYWD

FLITCH PLATE OR

REINFORCED CONC. FTG.

SEE FOUNDATION PLAN

DETAIL

1/2"=1'-0" (11X17) 1"=1'-0" (22X34)

ROOF PLAN

PRE-ENG. BEAM, SEE

(22)@ TRUSS TO

(45) (2) @ POST TO

STRUCTURAL POST

SEE FLOOR PLAN

BEAM TO POST

CONNECTION

HB&G PRE- FAB

COLUMN OR EQ.


91 @ POST TO

SLAB (6X6)


89 @ POST TO SLAB (8X8)


@ TRUSS TO BEAM @ CORNER

BEAM



1/2"=1'-0" (11X17) 1"=1'-0" (22X34)









GOBA


AS NOTED DRAWN BY: C.C. DESIGNED BY: MJS **DETAILS**


D8


houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

DETAIL

1/2"=1'-0" (11X17) 1"=1'-0" (22X34)









PER PRESCRIPTIVE FBC 721.1 (3) ITEM 21-1.1 CONT BASE LAYER 5/8" TYPE X GYPSUM WALL BOARD APPLIED @ RIGHT ANGLES TO JOIST OR TRUSS 24" O.C. W/ 1 1/4" TYPE S OR W DRY WALL SCREW 24" O.C. FACE LAYER 5/8" TYPE X GYPSUM WALL BOARD OR VENEER BASE APPLIED AT RIGHT ANGLES TO JOIST OR TRUSS THROUGH


END JOINTS 12" O.C.





CONV. FRAME OVERHANG 1/2"=1'-0" (11X17) 1"=1'-0" (22X34)




CONV. FRAME OVERHANG D9 1/2"=1'-0" (11X17) 1"=1'-0" (22X34)









PARTY WALL SECTION







REVISIONS

GOBA

PROJECT: 00-0000 SCALE: AS NOTED DRAWN BY: C.C. DESIGNED BY: MJS

FLOOR TRUSSES **D**9

houzz FIND US ON FACEBOOK, HOUZZ & ZILLOW AT MJS CUSTOM HOME DESIGNS

D9 N.T.S.

