

# 1501 DELIGHT 30' THRIVE 30' X 75'

REVISION SCHEDULE			
NO.	DATE	DESCRIPTION	BY
1	03-29-23	-RE-DESIGN KITCHEN -RECESS CANS ILO LIGHT FIXTURES	ME
2	03-29-23	-ADD (2) PENDANT LTS PREWIRE OVER KITCHEN ISLAND	ME
3	01-26-24	-UPDATE TO 2023 CODE	ME
4	02-20-24	-REPLACE CABINET PANTRY W/BUILT-IN	ME
5	06-19-24	-REDESIGN KITCHEN CABINETS	ME
6	07-12-24	-MOVE LAUNDRY WALL 10' TOWARDS KITCHEN	ME
7	08-20-25	-RELOCATE KITCHEN ISLAND	MR

**SHEET INDEX:**

- 00 COVER SHEET
- 01.0 FOUNDATION PLAN A
- 02.0 FLOOR PLAN W/ DIMENSIONS A
- 03.0 FLOOR PLAN W/ NOTES A
- 04A.0 EXTERIOR ELEVATIONS- FRONT/ REAR "A"
- 05A.0 EXTERIOR ELEVATIONS- LEFT/ RIGHT "A"
- 06 CROSS SECTION AND INTERIOR ELEVATIONS
- 07.0 ELECTRICAL PLAN A
- 08A.0 TRUSS LAYOUT "A"
- 09.0 PRECAST LINTEL LAYOUT A
- 10 TYPICAL DETAILS
- 11 TYPICAL DETAILS/CONNECTOR SCHEDULE
- D1 TYPICAL STRUCTURAL DETAILS
- D2 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 NOT USED
- D5 TYPICAL STRUCTURAL DETAILS
- D6 TYPICAL STRUCTURAL DETAILS
- D7 TYPICAL STRUCTURAL DETAILS

**SHEET INDEX:**

- 00 COVER SHEET
- 01.0 FOUNDATION PLAN B
- 02.0 FLOOR PLAN W/ DIMENSIONS B
- 03.0 FLOOR PLAN W/ NOTES B
- 04B.0 EXTERIOR ELEVATIONS- FRONT/ REAR "B"
- 05B.0 EXTERIOR ELEVATIONS- LEFT/ RIGHT "B"
- 06 CROSS SECTION AND INTERIOR ELEVATIONS
- 07.0 ELECTRICAL PLAN B
- 08B.0 TRUSS LAYOUT "B"
- 09.0 PRECAST LINTEL LAYOUT B
- 10 TYPICAL DETAILS
- 11 TYPICAL DETAILS/CONNECTOR SCHEDULE
- D1 TYPICAL STRUCTURAL DETAILS
- D2 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 NOT USED
- D5 TYPICAL STRUCTURAL DETAILS
- D6 TYPICAL STRUCTURAL DETAILS
- D7 TYPICAL STRUCTURAL DETAILS

**SHEET INDEX:**

- 00 COVER SHEET
- 01.0 FOUNDATION PLAN C
- 02.0 FLOOR PLAN W/ DIMENSIONS C
- 03.0 FLOOR PLAN W/ NOTES C
- 04C.0 EXTERIOR ELEVATIONS- FRONT/ REAR "C"
- 05C.0 EXTERIOR ELEVATIONS- LEFT/ RIGHT "C"
- 06 CROSS SECTION AND INTERIOR ELEVATIONS
- 07.0 ELECTRICAL PLAN C
- 08C.0 TRUSS LAYOUT "C"
- 09.0 PRECAST LINTEL LAYOUT C
- 10 TYPICAL DETAILS
- 11 TYPICAL DETAILS/CONNECTOR SCHEDULE
- D1 TYPICAL STRUCTURAL DETAILS
- D2 TYPICAL STRUCTURAL DETAILS
- D3 TYPICAL STRUCTURAL DETAILS
- D4 NOT USED
- D5 TYPICAL STRUCTURAL DETAILS
- D6 TYPICAL STRUCTURAL DETAILS
- D7 TYPICAL STRUCTURAL DETAILS

THRIVE PRODUCT

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 2023 EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

LOT: 0000, COMMUNITY

© COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.


REVISIONS	BY

  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000


COVER SHEET

1501 DELIGHT	THRIVE SERIES
DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	1501
SHEET	00
OF	SHEETS

- FOUNDATION NOTES**
- CONTRACTOR TO VERIFY ALL DIMENSIONS ON JOB SITE.
  - DENOTES FILLED CELL REINFORCED W/ CONC. & (1) #5 REBAR, GRADE 60
  - DENOTES FILLED CELL REINFORCED W/ CONC. & (2) #5 REBAR, GRADE 60
  - DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY AND ALL DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION
  - WATER HEATER T&P RELIEF VALVE SHALL BE FULL SIZE TO EXTERIOR. WATER HEATER AT OR ABOVE FLOOR LEVEL SHALL BE IN A PAN W/ DRAIN TO EXTERIOR. WATER HEATER SHALL HAVE APPROVED THERMAL EXPANSION DEVICE
  - DENOTES FLOOR SLAB OF PLANT MIX CONCRETE 2500 P.S.I., 3½" THICK W/ 6X6 10/10 GAUGE REINFORCING MAT. W/ MINIMUM 1" COVER. TERMITICIDE TREATED SOIL W/ 0.06mm (6 mil) POLYETHYLENE VAPOR BARRIER OVER COMPACTED CLEAN FILL. WUF SHALL BE PLACED IN THE MIDDLE TO UPPER 1/3 OF THE SLAB AND SUPPORTED BY APPROVED SLAB BOLSTERS.  
\*\*\*NOTE: FIBERMESH REINFORCEMENT MAY BE USED AS AN ALTERNATE TO WIRE MESH.
  - PAVERS MAY BE USED ILO CONCRETE IN PATIO, PORCH, DRIVEWAYS AND WALKWAYS. DELETE SLAB IN AREAS PAVERS ARE USED.
  - MECHANICAL EQUIPMENT LOCATIONS WILL BE DETERMINED BY COMMUNITY AND COUNTY CODES.
  - IN LIEU OF TERMITICIDE TREATING THE SOIL, TERMITICIDE MAY BE USED AS AN ALTERNATIVE.



**FOUNDATION PLAN A,B,C**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



FOOTING PAD SCHEDULE	
1	24" X 24" X 12" W/ (3) #5'S EACH WAY
2	30" X 30" X 12" W/ (4) #5'S EACH WAY
3	36" X 36" X 12" W/ (5) #5'S EACH WAY
4	32" X 32" X 16" W/ (4) #5'S EACH WAY
5	36" X 36" X 18" W/ (5) #5'S EACH WAY
6	30" X 30" X 20" W/ (4) #5'S EACH WAY
7	24" X 12" X 12" W/ (3) #5'S EACH WAY
C	FOOTING CHANGE / TRANSITION

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 2018 EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**LOI: 0000, COMMUNITY**  
 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.  
 COPYRIGHT 2021

<b>1501 DELIGHT</b> <b>THRIVE SERIES</b>	<b>FOUNDATION PLAN</b>				
<b>THRIVE PRODUCT</b> <small>THOMPSON ENGINEERING GROUP, INC.          5200 Vineland Road, Suite 200          Orlando, Florida 32811          Phone: (407) 529 - 3000</small>	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 80%;">REVISIONS</th> <th style="width: 20%;">BY</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS	BY		
REVISIONS	BY				



**LOAD INFORMATION**  
PER 8TH EDITION, 2023 FLORIDA BUILDING  
RESIDENTIAL CODE

**DEAD LOADS**

FLOOR: STRUCTURE	1 P&F
CEILINGS	3 P&F
MECH/ELEC	5 P&F
PARTITIONS	5 P&F
TOTAL	20 P&F
ROOF: SHEATHING	5 P&F
STRUCTURE	1 P&F
CEILINGS	3 P&F
MECH/ELEC	5 P&F
TOTAL	20 P&F

**FLOOR LIVE LOADS**

RESIDENTIAL FLOOR:	40 P&F
UNINHABITABLE ATTIC WITHOUT STORAGE:	10 P&F
UNINHABITABLE ATTIC W/LIMITED STORAGE:	20 P&F
ROOMS OTHER THAN SLEEPING ROOM:	40 P&F
SLEEPING ROOM:	30 P&F
STAIR LIVE LOAD:	40 P&F
BALCONIES:	40 P&F
PASSANGER VEHICLE GARAGE:	50 P&F

**ROOF LIVE LOADS**

MINIMUM ROOF LIVE LOAD (P&F) TRIBUTARY LOADED AREA (SQ. FT.) FOR ANY STRUCTURAL MEMBER

ROOF SLOPE	0-200	201-600	OVER 600
0:12 < 4:12	20	16	12
≥ 4:12 < 12:12	16	14	12
≥ 12:12	12	12	12



**WIND INFORMATION**  
PER 8TH EDITION, 2023 FLORIDA BUILDING  
RESIDENTIAL CODE

- BASIC WIND SPEED: 140 MPH
  - RISK CATEGORY: II
  - WIND EXPOSURE: B
  - BUILDING TYPE: V B
  - ENCLOSURE CLASSIFICATION: +/-1B, INCLUDED INTERNAL PRESSURE IN NOTE #6
  - COMPONENT / CLADDING: SEE PLAN DESIGN WIND PRESSURE:
    - + XXX DESIGN WIND PRESSURE IAW FLA
    - XXX RESIDENTIAL CODE, SECTION R301
- NOTE: DESIGN PRESSURES BASED ON BASIC WIND SPEED AND NOT ULTIMATE WIND SPEED.

**GENERAL NOTES**

- PROVIDE RECESS HOT & COLD WATER WITH DRAIN @ WASHER SPACE.
- VENT DRYER THRU ROOF.
- PROVIDE COLD WATER LINE FOR ICE MAKER LINE @ REF. SPACE.
- DO NOT SCALE PRINTS! CONSTRUCTION TO BE FROM CALCULATED DIMENSIONS ONLY. ANY DISCREPANCIES OR ERRORS TO BE REPORTED PROMPTLY TO SUPERVISOR FOR CLARIFICATION.
- MECHANICAL EQUIPMENT LOCATION TO BE DETERMINED BY COMMUNITY STANDARDS AND APPLICABLE COUNTY CODES.
- DENOTES CONC. BLOCK WALL HGT. @ 9'-4" AFF.
  - DENOTES CONC. BLOCK WALL HGT. @ X'-0" AFF.
- REFER TO TYPICAL DETAIL SHEET FOR EXTERIOR WALL FINISH SPECIFICATIONS
- REFER TO DETAIL SHEETS FOR FLASHING REQUIREMENTS AT ALL WOOD TO MASONRY INTERFACES
- ANCHOR THE CONDENSER UNIT TO SLAB PER CODE: M1307.1 - M1307.2
- ALL INTER FIRST FLOOR CEILINGS AT 9'-4" UNLESS NOTED OTHERWISE.
- ALL INTER SECOND FLOOR CEILINGS AT X'-X" UNLESS NOTED OTHERWISE.

NOTE: 1. DOOR FROM HOUSE TO GARAGE MUST BE SOLID WOOD DOOR NO LESS THEN 1 3/8" IN THICKNESS, SOLID OR HONEYCOMB CORE STEEL DOORS NOT LESS THAN 1 3/8" THICK, OR 20MIN. FIRE RATED IAW R302.5.1



**FLOOR PLAN W/ NOTES A, B, C**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: SEE COLOR SHEET FOR INTERIOR DOOR HEIGHT REQUIREMENTS

NOTE: SEE COLOR SHEET FOR FLOORING

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**LOI: 0000, COMMUNITY**

**THRIVE PRODUCT**

**1501 DELIGHT**



**THRIVE SERIES**

**THRIVE ENGINEERING GROUP, INC.**  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529-3000

REVISIONS	BY

DATE: 06-01-22  
SCALE: AS NOTED  
DRAWN: RDC  
JOB: 1501  
SHEET: 03.0 OF SHEETS

- EXTERIOR FINISH NOTES**
- LATH TO BE ATTACHED IAW R103.1.1 OF THE 8TH EDITION, FBCR. 2023
  - PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 8TH EDITION, FBCR. 2023
  - WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 8TH EDITION, FBCR. 2023
  - WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 8TH EDITION, FBCR. 2023
  - "ZIP SYSTEMS" WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**LOT: 0000, COMMUNITY**

**THRIVE PRODUCT**

RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without the express written permission from RDC, INC.

DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	1501
SHEET	04A.0
OF SHEETS	

**THOMPSON ENGINEERING GROUP, INC.**  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 734-1730  
 www.teng.com

**A DIVISION OF PARK SQUARE ENTERPRISES, INC.**  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000

**Park Square HOMES**

**EXTERIOR ELEVATION FRONT AND REAR**


**1501 DELIGHT**

**THRIVE SERIES**

**REVISIONS**

NO.	DESCRIPTION	DATE	BY

- EXTERIOR FINISH NOTES**
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 8TH EDITION, FBCR, 2023
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 8TH EDITION, FBCR, 2023
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 8TH EDITION, FBCR, 2023
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 8TH EDITION, FBCR, 2023
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**LOT: 0000, COMMUNITY**


© COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

THRIVE PRODUCT	
REVISIONS	BY
<b>1501 DELIGHT</b> <b>THRIVE SERIES</b>	
DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	1501
SHEET	
OF	

- EXTERIOR FINISH NOTES**
1. LATH TO BE ATTACHED IAW R103.7.1 OF THE 8TH EDITION, FBCR 2023
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.7.2 OF THE 8TH EDITION, FBCR 2023
  3. WEEP SCREED TO BE INSTALLED IAW R103.7.2.1 OF THE 8TH EDITION, FBCR 2023
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.7.3 OF THE 8TH EDITION, FBCR 2023
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER ON EXTERIOR WALLS.



**FRONT ELEVATION "C"**  
 1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



**REAR ELEVATION "C"**  
 1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH.  
**LOT: 0000, COMMUNITY**

THRIE PRODUCT  
 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without the express written permission from RDC, INC.  
 © COPYRIGHT 2021

REVISIONS	BY

**THOMPSON ENGINEERING GROUP, INC.**  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529-3000


**Park Square HOMES**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.

**EXTERIOR ELEVATION FRONT AND REAR**


**1501 DELIGHT**  
**THRIVE SERIES**

DATE 06-01-22  
 SCALE AS NOTED  
 DRAWN RDC  
 JOB 1501  
 SHEET 04C.0 OF SHEETS

- EXTERIOR FINISH NOTES**
- LATH TO BE ATTACHED IAW R103.1.1 OF THE 8TH EDITION, FBCR, 2023
  - PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 8TH EDITION, FBCR, 2023
  - WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 8TH EDITION, FBCR, 2023
  - WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 8TH EDITION, FBCR, 2023
  - 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.



**LEFT ELEVATION "A"**  
 1/8" = 1'-0" (11X17) 1/4" = 1'-0" (22X34)



**RIGHT ELEVATION "A"**  
 1/8" = 1'-0" (11X17) 1/4" = 1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOT: 0000, COMMUNITY**  
**THRIVE PRODUCT**

RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

REVISIONS	BY



**THOMPSON ENGINEERING GROUP, INC.**  
 5200 Vineyard Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 734-1750  
 Fax: (407) 734-1750  
 www.teg.com

**Park Square HOMES**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineyard Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000

**1501 DELIGHT**  
**THRIVE SERIES**

DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	1501
SHEET	05A.0
OF SHEETS	

- EXTERIOR FINISH NOTES**
1. LATH TO BE ATTACHED IAW R103.1.1 OF THE 8TH EDITION, FBCR 2023
  2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.1.2 OF THE 8TH EDITION, FBCR 2023
  3. WEEP SCREED TO BE INSTALLED IAW R103.1.2.1 OF THE 8TH EDITION, FBCR 2023
  4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.1.3 OF THE 8TH EDITION, FBCR 2023
  5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER, ON EXTERIOR WALLS.





THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOT: 0000, COMMUNITY**  
**THRIVE PRODUCT**

REVISIONS		BY
 A DIVISION OF PARK SQUARE ENTERPRISES, INC. 5200 Vineland Road, Suite 200 Orlando, Florida 32811 Phone: (407) 529 - 3000		
<b>1501 DELIGHT</b> <b>THRIVE SERIES</b>		<b>Park Square HOMES</b>
DATE	06-01-22	
SCALE	AS NOTED	
DRAWN	RDC	
JOB	1501	
SHEET	05B.0	
OF	SHEETS	

RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

**EXTERIOR FINISH NOTES**

1. LATH TO BE ATTACHED IAW R103.7.1 OF THE 8TH EDITION, FBCR 2023
2. PLASTERING TO BE WITH PORTLAND CEMENT, INSTALLED IAW R103.7.2 OF THE 8TH EDITION, FBCR 2023
3. WEEP SCREED TO BE INSTALLED IAW R103.7.2.1 OF THE 8TH EDITION, FBCR 2023
4. WATER RESISTANT BARRIER TO BE INSTALLED IAW R103.7.3 OF THE 8TH EDITION, FBCR 2023
5. 'ZIP SYSTEMS' WALL SHEATHING MAY BE USED AS AN ALTERNATIVE FOR WALL SHEATHING AND VAPOR BARRIER ON EXTERIOR WALLS.



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**LOT: 0000, COMMUNITY**

**1501 DELIGHT**

**EXTERIOR ELEVATION**

**Park Square HOMES**

**THRIVE PRODUCT**

05C.0  
OF SHEETS

SHEET

JOB 1501

DRAWN RDC

SCALE AS NOTED

DATE 06-01-22

**THRIVE SERIES**

**LEFT AND RIGHT**


**ENTERTAINMENT, INC.**

**A DIVISION OF PARK SQUARE**  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000

**ITEG**  
 THOMPSON ENGINEERING GROUP, INC.  
 3347 AS Orange, FL 32811  
 P: (407) 724-1450  
 F: (407) 724-1750  
 www.iteg.com

REVISIONS	BY


RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas, and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without the express written permission from RDC, INC.



## INTERIOR ELEVATIONS

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

NOTE: INTERIOR ELEVATIONS ARE CONCEPTUAL ONLY.  
SEE CABINET SHOP DRAWINGS FOR FINAL VERIFICATION.



**CROSS SECTION**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

- FIBERGLASS SHINGLES
- PRE-ENG. WD. TRUSSES SYSTEM @ 24' O.C.
- R-30 INSULATION
- EL. 9'-4" / FLT. HGT.
- EL. 8'-0" / HDR. HGT.
- EL. 0'-0" / FIN. FLR.

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 2018 EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

LOT: 0000, COMMUNITY

1501 DELIGHT  
THRIVE SERIES

DATE 06-01-22  
SCALE AS NOTED  
DRAWN RDC  
JOB 1501  
SHEET 06  
OF SHEETS

THRIVE PRODUCT

REVISIONS	BY

**THOMPSON ENGINEERING GROUP, INC.**  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529-3000


**Park Square HOMES**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529-3000

CROSS SECTION / INTERIOR ELEVATIONS

© COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without the express written permission from RDC, INC.

**MECHANICAL/GENERAL NOTES**

- PER 8TH ED. 2023 FLA BLD. CODE-RESIDENTIAL
- 1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1
  - 2.) APPLIANCES SHALL BE ACCESSIBLE FOR INSPECTION, SERVICE, REPAIR AND REPLACEMENT WITHOUT REMOVING PERMANENT CONSTRUCTION.
    - A) CHAPTER 13 OF THE FBC-R 2023 8TH SECTION M1305.1
  - 3.) AIR CONDITIONING SYSTEM SHALL BE COMPLETELY BALANCED. ALL ROOMS ISOLATED FROM THE RETURN AIR SHALL BE PROVIDED WITH MEANS TO COMPLY WITH SECTION M1602 OF THE FBCR CODE 2023 8TH EDITION.
  - 4.) IAW NEC 2020- 210.12-ALL 15A OR 20A, 120V BRANCH CIRCUITS SUPPLYING OUTLETS OR DEVICES IN THE FOLLOWING LOCATIONS REQUIRE AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING RMS, LIVING RMS, PARLORS, LIBRARIES, BEDROOMS, DENS, CLOSETS, SUNROOMS, RECREATION RMS, HALLWAYS OR SIMILAR AREAS SHALL BE PROTECTED BY A LISTED AFCI DEVICE OF THE COMBINATION TYPE.
  - 5.) IAW NEC 2020- 406.12, ALL 15A AND 20A, 125V RECEPTACLES SHALL BE LISTED AS TAMPER RESISTANT.
  - 6.) ALL OUTLETS IN BATHROOMS, KITCHEN, GARAGES AND LAUNDRY ROOM SHALL BE GFCI
  - 7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING AREAS, SHALL BE INTERCONNECTED, SHALL BE WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/ A BATTERY BACKUP. ALARMS MAY NOT BE CONNECTED WHERE ALARMS ARE WIRELESS & ALL ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3 & R314.4. MODEL\* TO BE USED ON THIS JOB TO BE: **BRK: SMOKE-9120B, C/O- SC9120B**  
**KIDDE: SMOKE-21007581, C/O 21006377-N**
  - 8.) ALL WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS WATER HEATER IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2023, 8TH ED. P2801.1
  - 9.) ALL EQUIPMENT & APPLIANCES, INCLUDING WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2023, 8TH ED.
  - 10.) THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH SHALL BE DETERMINED BY ONE OF THE METHODS SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3
  - 11.) ALL ELECTRICAL WORK TO BE DONE PER **NFP710-NEC 2020**
  - 12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN ACCORDANCE WITH NEC 250.53(A)2)
  - 12.) ALL DWELLING UNIT RECEPTACLE WILL BE IN ACCORDANCE WITH NFP710-NEC2020 - ARTICLE 210-52



**ELECTRICAL RISER DIAGRAM**  
NOTE: NTS.  
ELECTRICAL MATERIALS AND INSTALLATIONS SHALL COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL ELEC. CODE 250.52(A)1) TO (6), LOCAL CODES, AND THE LOCAL POWER COMPANY.


250.52(A)3) Concrete-Encased Electrode. Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

There are two types of concrete-encased electrodes: (1) steel reinforcing bars or rods which are not less than 1/2 inch in diameter and at least 20 ft. long, encased in 2 inches of concrete; (2) 20 ft. of bare copper conductor not smaller than No. 4 AWG encased in 2 inches of concrete.

The steel reinforcing rods must be in a location that is in direct contact with the earth. The reinforcing rods can be connected with tie wires, and a single length of rod can be used as the concrete-encased electrode. The reinforcing rods cannot be coated with non-conductive material.


Section 250.50 requires a concrete-encased electrode to be connected to the grounding electrode system if it is present. Several states have modified this requirement to say a concrete-encased electrode must be used as a grounding electrode only if it is available. In those jurisdictions, if the footings or foundations have been poured before the electrical contractor arrives at the site, and a reinforcing rod is not available for use as a grounding electrode, then a grounding connection to the reinforcing rod is not required.



**ELECTRICAL PLAN A,B,C**  
1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

**ELECTRICAL LEGEND**

⊕	SINGLE POLE SWITCH	◀	OUTLET, TV/CABLE
⊕	THREE WAY SWITCH	◀	OUTLET, PHONE
⊕	OUTLET 110-115	◻	INTERCOM
⊕	OUT. 110-115, SPLIT WIRED	◻	CHIMES
⊕	OUT. 110-115, W/ USB	◻	SMOKE DETECTOR/SMOKE
⊕	OUT. 110-115, CLG. MOUNT.	◻	CARBON MONOXIDE
⊕	OUT. 110-115, FLR. MOUNT.	◻	PUSH BUTTON
⊕	SPCL. PURPOSE 220-240	◻	EXHAUST FAN
⊕	LIGHT FIXT., CLG. MTD.	◻	EX. FAN/LIGHT COMBO
⊕	LIGHT FIXT., WALL MTD.	⊙	DISPOSAL
⊕	LED LIGHT FIXT., RECESSED	◻	ELECTRICAL PANEL
⊕	LIGHT FIXT., REC. ADJUST.	◻	CEILING FAN, PREWIRE
⊕	LIGHT FIXT., FULL CHAIN	◻	CEILING FAN, INSTALL
⊕	LED LIGHT FIXT., FLUORESCENT	◻	ELECT. JUNCTION BOX
⊕	LIGHT FIXT., EXT. FLOODS	◻	THERMOSTAT
⊕	LIGHT FIXT., EMERG. EXIT	◻	DISCONNECT SWITCH
⊕	LIGHT FIXT., EXIT/BACKUP	◻	ELEC. POWER METER



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOI: 0000, COMMUNITY**

**THRIVE PRODUCT**

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000


**Park Square HOMES**

**ELECTRICAL PLAN**

REVISIONS	BY
DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	150
SHEET	07.0
OF	SHEETS

**MECHANICAL/GENERAL NOTES**

- PER 8TH ED. 2023 FLA BLD. CODE-RESIDENTIAL
- 1.) COMPLETE DUCT DESIGN W/ SIZES & R-VALUE COMPLYING W/ THE FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION 610.1 ABC.1
  - 2.) APPLIANCES SHALL BE ACCESSIBLE FOR INSPECTION, SERVICE, REPAIR AND REPLACEMENT WITHOUT REMOVING PERMANENT CONSTRUCTION.
    - A) CHAPTER 13 OF THE FBC-R 2023 8TH SECTION M1305.1
  - 3.) AIR CONDITIONING SYSTEM SHALL BE COMPLETELY BALANCED. ALL ROOMS ISOLATED FROM THE RETURN AIR SHALL BE PROVIDED WITH MEANS TO COMPLY WITH SECTION M1602 OF THE FBCR CODE 2023 8TH EDITION.
  - 4.) IAW NEC 2020- 210.12-ALL 15A OR 20A, 120V BRANCH CIRCUITS SUPPLYING OUTLETS OR DEVICES IN THE FOLLOWING LOCATIONS REQUIRE AFCI PROTECTION- KITCHEN, FAMILY RMS, DINING RMS, LIVING RMS, PARLORS, LIBRARIES, BEDROOMS, DENS, CLOSETS, SUNROOMS, RECREATION RMS, HALLWAYS OR SIMILAR AREAS SHALL BE PROTECTED BY A LISTED AFCI DEVICE OF THE COMBINATION TYPE.
  - 5.) IAW NEC 2020- 406.12, ALL 15A AND 20A, 125V RECEPTACLES SHALL BE LISTED AS TAMPER RESISTANT.
  - 6.) ALL OUTLETS IN BATHROOMS, KITCHEN, GARAGES AND LAUNDRY ROOM SHALL BE GFCI
  - 7.) SMOKE ALARMS SHALL BE IN ALL SLEEPING AREAS, SHALL BE INTERCONNECTED, SHALL BE WITHIN 1' TO 3' OF PEAK & SHALL BE 3' FROM THE SUPPLY OR RETURN AIR- STREAM & EQUIPPED W/ A BATTERY BACKUP. ALARMS MAY NOT BE CONNECTED WHERE ALARMS ARE WIRELESS & ALL ALARMS SOUND UPON ACTIVATION IAW FBCR R314.3 & R314.4. MODEL\* TO BE USED ON THIS JOB TO BE:
    - BRK: SMOKE-9120B, C/O- SC9120B
    - KIDDE: SMOKE-21007581, C/O 21006377-N
  - 8.) ALL WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS WATER HEATER IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2023, 8TH ED. F2801.1
  - 9.) ALL EQUIPMENT & APPLIANCES, INCLUDING WATER HEATERS HAVING AN IGNITION SOURCE TO BE ELEVATED SUCH THAT THE SOURCE OF IGNITION IS MINIMUM 18" ABOVE GARAGE FLOOR UNLESS IT IS LISTED AS FLAMMABLE VAPOR IGNITION RESISTANT. IAW FBCR 2023, 8TH ED.
  - 10.) THE MAXIMUM ALLOWABLE EXHAUST DUCT LENGTH SHALL BE DETERMINED BY ONE OF THE METHODS SPECIFIED IN SECTIONS M1502.4.5.1 THROUGH M1502.4.5.3
  - 11.) ALL ELECTRICAL WORK TO BE DONE PER NFP710-NEC 2020
  - 12.) ADDITIONAL ELECTRODE MAY BE REQUIRED IN ACCORDANCE WITH NEC 250.53(A)2)
  - 12.) ALL DWELLING UNIT RECEPTACLE WILL BE IN ACCORDANCE WITH NFP710-NEC2020 - ARTICLE 210-52



**ELECTRICAL RISER DIAGRAM**  
 NOTE: N.T.S.  
 ELECTRICAL MATERIALS AND INSTALLATIONS SHALL COMPLY W/ APPLICABLE PROVISIONS OF THE NATIONAL ELEC. CODE 250.52(AX1) TO (6), LOCAL CODES, AND THE LOCAL POWER COMPANY.


250.52(AX3) Concrete-Encased Electrode. Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

Concrete-encased electrodes can be horizontal or vertical and must be at least 20 ft. long.

There are two types of concrete-encased electrodes: (1) steel reinforcing bars or rods which are not less than 1/2 inch in diameter and at least 20 ft. long, encased in 2 inches of concrete; (2) 20 ft. of bare copper conductor not smaller than No. 4 AWG encased in 2 inches of concrete.

The steel reinforcing rods must be in a location that is in direct contact with the earth. The reinforcing rods can be connected with tie wires, and a single length of rod can be used as the concrete-encased electrode. The reinforcing rods cannot be coated with non-conductive material.


Section 250.50 requires a concrete-encased electrode to be connected to the grounding electrode system if it is present. Several states have modified this requirement to say a concrete-encased electrode must be used as a grounding electrode only if it is available. In those jurisdictions, if the footings or foundations have been poured before the electrical contractor arrives at the site, and a reinforcing rod is not available for use as a grounding electrode, then a grounding connection to the reinforcing rod is not required.



**ELECTRICAL PLAN A,B,C**  
 1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

**ELECTRICAL LEGEND**

⊠	SINGLE POLE SWITCH	◀	OUTLET, TV/CABLE
⊡	THREE WAY SWITCH	◀	OUTLET, PHONE
⊞	OUTLET 110-115	⊞	INTERCOM
⊞	OUT. 110-115, SPLIT WIRED	⊞	CHIMES
⊞	OUT. 110-115, W/ USB	⊞	SMOKE DETECTOR/SMOKE
⊞	OUT. 110-115, CLG. MOUNT.	⊞	CARBON MONOXIDE
⊞	OUT. 110-115, FLR. MOUNT.	⊞	PUSH BUTTON
⊞	SPL. PURPOSE 220-240	⊞	EXHAUST FAN
⊞	LIGHT FIXT., CLG. MTD.	⊞	EX. FAN/LIGHT COMBO
⊞	LIGHT FIXT., WALL MTD.	⊞	DISPOSAL
⊞	LED LIGHT FIXT., RECESSED	⊞	ELECTRICAL PANEL
⊞	LIGHT FIXT., REC. ADJUST.	⊞	CEILING FAN, PREWIRE
⊞	LIGHT FIXT., FULL CHAIN	⊞	CEILING FAN, INSTALL
⊞	LED LIGHT FIXT., FLUORESCENT	⊞	ELECT. JUNCTION BOX
⊞	LIGHT FIXT., EXT. FLOODS	⊞	THERMOSTAT
⊞	LIGHT FIXT., EMERG. EXIT	⊞	DISCONNECT SWITCH
⊞	LIGHT FIXT., EXIT/BACKUP	⊞	ELEC. POWER METER



THRIE PRODUCT  
 THRIE COMMUNITY  
 1501 DELIGHT  
 THRIE SERIES  
 THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
 LOI: 0000, COMMUNITY  
 DATE 06-01-22  
 SCALE AS NOTED  
 DRAWN RDC  
 JOB 150  
 SHEET 07.0 OF SHEETS

**THRIE PRODUCT**

**THRIE COMMUNITY**

**1501 DELIGHT**

**THRIE SERIES**

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

LOI: 0000, COMMUNITY

DATE 06-01-22

SCALE AS NOTED

DRAWN RDC

JOB 150

SHEET 07.0 OF SHEETS

REVISIONS BY

**THRIE**  
 THOMPSON ENGINEERING GROUP, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 734-1170  
 www.thrie.com

**Park Square HOMES**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529-3000

**ELECTRICAL PLAN**

© COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

**ATTIC VENTILATION CALCULATIONS**

PER FBC2023 8TH EDITION R206: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{2,047\text{S.F.}}{300} = 6.82\text{S.F.}$  NET FREE VENT. REQUIRED


UPPER PORTION VENTILATION TOTAL: ----- 3.45F.  
 PROVIDED W/OFF RIDGE VENTS: 4 VENTS @ 855F. VENT.  
 (VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL: ----- 18,968F.  
 PROVIDED W/ VENTILATED SOFFITS @ EAVE:--  
 ( 218LF. @ 0.0875F. VENTING PER L.F.)

UPPER PORTION PERCENTAGE: 50%  
 LOWER PORTION PERCENTAGE: 50%

**NOTES**

1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 8TH EDITION (2023) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1 - Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1.



**TRUSS LAYOUT "A"**

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOT: 0000, COMMUNITY**  
**THRIVE PRODUCT**  
 © COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

REVISIONS	BY

**THRIVE PRODUCT**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000

**1501 DELIGHT**  
**THRIVE SERIES**

DATE: 06-01-22  
 SCALE: AS NOTED  
 DRAWN: RDC  
 JOB: 1501  
 SHEET: 08A.0  
 OF SHEETS:

**ATTIC VENTILATION CALCULATIONS**

PER FBC2023 8TH EDITION R206: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{2,047\text{S.F.}}{300} = 6.82\text{S.F.}$  NET FREE VENT. REQUIRED


UPPER PORTION VENTILATION TOTAL: ----- 3.4S.F. PROVIDED W/OFF RIDGE VENTS: 4 VENTS @ .85S.F. /VENT. (VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL: ----- 18.96S.F. PROVIDED W/ VENTILATED SOFFITS @ EAVE:-- ( 218L.F. @ 0.087S.F. VENTING PER L.F.)

UPPER PORTION PERCENTAGE: **50%**  
LOWER PORTION PERCENTAGE: **50%**

**NOTES**

1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 8TH EDITION (2023) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1 - Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1.



**TRUSS LAYOUT "B"**

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

**THRIVE PRODUCT**

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**Park Square HOMES**

TRUSS LAYOUT

LOT: 0000, COMMUNITY 1501 DELIGHT THRIVE SERIES

REVISIONS	BY

DATE: 06-01-22  
SCALE: AS NOTED  
DRAWN: RDC  
JOB: 1501  
SHEET: 08B.0 OF SHEETS

**ITEG**  
THOMPSON ENGINEERING GROUP, INC.  
3845 S. Orange Ave., FL 32811  
Orlando, FL 32811  
Phone: (407) 724-1450  
Fax: (407) 724-1750  
www.iteg.com

**ATTIC VENTILATION CALCULATIONS**

PER FBC2023 8TH EDITION R206: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{2,047\text{S.F.}}{300} = 6.82\text{S.F.}$  NET FREE VENT. REQUIRED


UPPER PORTION VENTILATION TOTAL: ----- 3.45F.  
 PROVIDED W/OFF RIDGE VENTS: 4 VENTS @ 855F. VENT.  
 (VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL: ----- 18,968F.  
 PROVIDED W/ VENTILATED SOFFITS @ EAVE:--  
 ( 218LF. @ 0.0875F. VENTING PER LF.)

UPPER PORTION PERCENTAGE: 50%  
 LOWER PORTION PERCENTAGE: 50%

**NOTES**

1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 8TH EDITION (2023) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1 - Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1.



**TRUSS LAYOUT "B"**

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOT: 0000, COMMUNITY**  
**THRIVE PRODUCT**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000  
 www.psq.com

REVISIONS	BY

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000  
 www.psq.com

**1501 DELIGHT**  
**THRIVE SERIES**

DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	1501
SHEET	08B.0
OF SHEETS	

**ATTIC VENTILATION CALCULATIONS**

PER FBC2023 8TH EDITION R206: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{2,047\text{SF.}}{300} = 6,825\text{SF.}$  NET FREE VENT. REQUIRED


UPPER PORTION VENTILATION TOTAL: ----- 3,45F.  
 PROVIDED W/OFF RIDGE VENTS: 4 VENTS @ .855F. VENT.  
 (VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL: ----- 18,968F.  
 PROVIDED W/ VENTILATED SOFFITS @ EAVE:--  
 ( 218LF. @ 0.0875F. VENTING PER LF.)

UPPER PORTION PERCENTAGE: 50%  
 LOWER PORTION PERCENTAGE: 50%

**NOTES**

1. TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
2. TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
3. PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 8TH EDITION (2023) FLORIDA RESIDENTIAL CODE.
4. ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
5. TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1 I.
6. REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
7. SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1 - Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
8. OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE
9. ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1.1



**TRUSS LAYOUT "C"**

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOT: 0000, COMMUNITY**  
**THRIVE PRODUCT**  
**THRIVE SERIES**

REVISIONS	BY

**THRIVE PRODUCT**  
**THRIVE SERIES**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000  
 www.psq.com

**1501 DELIGHT**  
**THRIVE SERIES**

DATE	06-01-22
SCALE	AS NOTED
DRAWN	RDC
JOB	1501
SHEET	08C.0
OF SHEETS	

**ATTIC VENTILATION CALCULATIONS**

PER FBC2023 8TH EDITION R206: MIN. 40% - MAX. 50% OF REQUIRED VENTILATION TO BE IN UPPER PORTION OF ATTIC SPACE AND THE BALANCE TO BE IN LOWER PORTION (EAVES).

THE MINIMUM NET VENTILATION AREA SHALL BE 1/300 OF VENTED SPACE:

TOTAL VENTED SPACE:  $\frac{2,047\text{S.F.}}{300} = 6.82\text{S.F.}$  NET FREE VENT. REQUIRED


UPPER PORTION VENTILATION TOTAL: ----- 3.4S.F. PROVIDED W/OFF RIDGE VENTS: 4 VENTS @ .85S.F. /VENT. (VENT TYPE: LOMANCO MODEL T10-D OR MILLENNIUM METAL)

LOWER PORTION VENTILATION TOTAL: ----- 18.96S.F. PROVIDED W/ VENTILATED SOFFITS @ EAVE:-- ( 218L.F. @ 0.087S.F. VENTING PER L.F.)

UPPER PORTION PERCENTAGE: 50%  
LOWER PORTION PERCENTAGE: 50%

**NOTES**

- TYPICAL ROOF GABLE OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
- TYPICAL ROOF EAVES OVERHANG TO BE 12" UNLESS OTHERWISE NOTED.
- PROVIDE AND INSTALL FLASHING AND ROOFING AS PER NATIONAL ROOFING AND SHEET METAL ASSOC. STANDARDS AND/ OR ACCEPTABLE INDUSTRY PRACTICE AND IN ACCORDANCE WITH THE 8TH EDITION (2023) FLORIDA RESIDENTIAL CODE.
- ALL ROOF TRUSSES, GIRDERS, BEAMS, HEADERS, ETC. TO BE SIZED BY TRUSS MANUFACTURER OR FL. REG. ENG.
- TRUSSES SHALL BE BRACED TO PREVENT ROTATION & PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR BUILDING & ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH TPI/WTCA BCS1 I.
- REFER TO TRUSS MANUFACTURER'S DRAWINGS FOR TRUSS PLACEMENT & TRUSS TO TRUSS CONNECTIONS.
- SHINGLE ROOF: UNDERLAYMENT TO BE INSTALLED IAW FBCR 2023, 8TH EDITION R905.1.1 - Underlayment materials required to comply with ASTM D226, D4869 or Type IV shall bear a label indicating compliance to the standard designation and, if applicable, type classification indicated in Table R905.1.1. Underlayment shall be applied and attached in accordance with Table R905.1.1.
- OFF RIDGE VENTS MAXIMUM OPENING SIZES :
  - LOMANCO : (2) 9 1/4" DIA. CIRCLES
  - MILLENNIUM METAL : 2 1/2" X 46" HOLE
- ROOF UNDERLAYMENT TO BE USED IS 2 LAYERS OF 30 LBS. SYNTHETIC FELT OR ANY OTHER METHOD LISTED PER FBC R905.1.1.



**TRUSS LAYOUT "C"**

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8TH EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH  
**LOT: 0000, COMMUNITY**  
**THRIVE PRODUCT**  
 A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000  
 www.psq.com

REVISIONS	BY

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000  
 www.psq.com


**1501 DELIGHT**  
**THRIVE SERIES**

DATE: 06-01-22  
 SCALE: AS NOTED  
 DRAWN: RDC  
 JOB: 1501  
 SHEET: 08C.0  
 OF SHEETS: 0

CAST CRETE / LOTT'S / WEKIWA / FLORIDA ROCK LINTEL SCHEDULE			
LINTEL NO.	LENGTH	TYPE	COMMENTS
L 1	4'-6"	8F12-0B/IT	3080 FRONT DOOR
L 2	4'-6"	8F16-0B/IT	SH25
L 3	11'-4"	8F34-1B/IT	GARAGE DOOR
L 4	4'-6"	8F16-0B/IT	SH25
L 5	4'-6"	8F16-0B/IT	SH25
L 6	4'-6"	8F16-0B/IT	SH25
L 7	4'-6"	8F16-0B/IT	SH25
L 8	4'-6"	8F16-0B/IT	3/2X1/4 FG.
L 9	7'-6"	8F16-0B/IT	6/0X8/0 SGD.
L 10	7'-6"	8F16-0B/IT	FR SH25
L 11			
L 12			
L 13			
L 14			
L 15	7'-6"	8F16-0B/IT	LANAI
L 16	13'-4"	8F8-1B/IT	LANAI
L 17	8'-0"	8F8-0B/IT	FRONT ENTRY
L 18	5'-4"	8F16-0B/IT	FRONT ENTRY
L 19			
L 20			
L 21			
L 22			
L 23			
L 24			
L 25			
L 26			
L 27			

**PRE CAST LINTEL LAYOUT A,B,C**

1/8"=1'-0" (11X17) 1/4"=1'-0" (22X34)



THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

LOT: 0000, COMMUNITY

DATE 06-01-22  
SCALE AS NOTED  
DRAWN RDC  
JOB 1501  
SHEET 09 OF 10  
SHEETS

1501 DELIGHT  
THRIVE SERIES

PRE CAST LINTEL LAYOUT

Park Square HOMES

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
5200 Vineland Road, Suite 200  
Orlando, Florida 32811  
Phone: (407) 529 - 3000

**ITEG**  
THOMPSON ENGINEERING GROUP, INC.  
3345 AS Orange, FL 32811  
PH: (407) 724-1450  
FAX: (407) 724-1770  
www.iteg.com

REVISIONS	BY

THRIVE PRODUCT


These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

© COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.


# SAFE LOAD TABLES FOR GRAVITY, UPLIFT & LATERAL LOADS

## 8" PRECAST & PRESTRESSED U-LINTELS

LENGTH	TYPE	RUB	GRAVITY																	
			8F8-0B	8F12-0B	8F16-0B	8F20-0B	8F24-0B	8F28-0B	8F32-0B	8F36-0B	8F40-0B	8F44-0B								
2'-10" (34')	PRECAST	2302	3166	4413	6039	7526	9004	10472	11936											
3'-6" (42')	PRECAST	2302	3166	4413	6039	7526	9004	10472	11936											
4'-0" (48')	PRECAST	2079	2646	4413	6039	7526	9004	10472	11936											
4'-6" (54')	PRECAST	1651	2110	4071	6039	7526	9004	10472	11936											
5'-4" (64')	PRECAST	1184	1665	2889	5091	6039	8400	6424	7450											
5'-10" (70')	PRECAST	912	1459	2464	4144	5458	4431	5280	6122											
6'-6" (78')	PRECAST	931	1259	2101	3326	4260	5134	5995	6850											
7'-6" (90')	PRECAST	161	1029	1675	2610	3839	5596	6613	8041											
9'-4" (112')	PRECAST	573	632	1049	1468	2100	2839	3571	4297											
10'-6" (126')	PRECAST	456	658	1029	1514	2081	2714	3350	4004											
11'-4" (136')	PRECAST	445	658	1029	1514	2081	2714	3350	4004											
12'-0" (144')	PRECAST	414	555	864	1254	1633	2211	2832	3500											
13'-4" (160')	PRECAST	362	485	748	1076	1438	1855	2343	2920											
14'-0" (168')	PRECAST	338	381	648	919	1190	1462	1801	2260											
14'-8" (176')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											
15'-4" (184')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											
17'-4" (208')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											
19'-4" (232')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											
21'-4" (256')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											
22'-0" (264')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											
24'-0" (288')	PRESTRESSED	NR	NR	NR	NR	NR	NR	NR	NR											



### TYPE DESIGNATION



### MATERIALS

1. f'c precast lintels = 3500 psi.
2. f'c prestressed lintels = 6000 psi.
3. f'c grout = 3000 psi w/ maximum 3/8" aggregate.
4. Concrete masonry units (CMU) per ASTM C90 w/ minimum net area compressive strength = 1900 psi.
5. Rebar provided in precast lintel per ASTM A615 GR60. Field rebar per ASTM A615 GR40 or GR60.
6. Prestressing strand per ASTM A416 grade 270 low relaxation.

### GENERAL NOTES

1. Provide full mortar head and bed joints.
2. Shore filled lintels as required.
3. Installation of lintel must comply with the architectural and/or structural drawings.
4. Lintels are manufactured with 5-1/2" long notches at the ends to accommodate vertical cell reinforcing and grouting.
5. All lintels meet or exceed L/360 vertical deflection, except lintels 17'-4" and longer with a nominal height of 8' meet or exceed L/180.
6. Bottom field added rebar to be located at the bottom of the lintel cavity.
7. 1/32" diameter wire stirrups are welded to the bottom steel for mechanical anchorage.
8. Cast-in-place concrete may be provided in composite lintel in lieu of concrete masonry units.
9. Safe load ratings based on rational design analysis per ACI 318 and ACI 530.

### SAFE LOAD TABLE NOTES

1. All values based on minimum 4" bearing. Exception: Safe loads for unfilled lintels must be reduced by 20% if bearing length is less than 6-1/2". Safe loads for all recessed lintels based on 8" nominal bearing.
2. N.R. = Not Rated.
3. Safe loads are total superimposed allowable load on the section specified.
4. Safe loads based on grade 40 or grade 60 field rebar.
5. Additional lateral load capacity can be obtained by the designer by providing additional reinforced masonry above the precast lintel.
6. One #7 rebar may be substituted for two #5 rebars in 8" lintels only.
7. The designer may evaluate concentrated loads from the safe load tables by calculating the maximum resisting moment and shear at a-d away from the face of support.
8. For composite lintel heights not shown, use safe load from next lower height.
9. All safe loads in units of pounds per linear foot.


### 8" PRECAST W/ 2" RECESS DOOR U-LINTELS

LENGTH	TYPE	RUB	GRAVITY										LATERAL							
			8R16-0B	8R20-0B	8R24-0B	8R28-0B	8R32-0B	8R36-0B	8R40-0B	8R44-0B	8R48-0B	8R52-0B	8R56-0B	8R60-0B	8R64-0B	8R68-0B				
4'-4" (52')	PRECAST	1488	1591	3053	2982	3954	4929	5904	6880											
4'-6" (54')	PRECAST	1351	1821	3412	4982	6472	7941	9416	10878											
5'-8" (68')	PRECAST	785	832	1602	1550	2098	2566	3075	3585											
5'-10" (70')	PRECAST	735	1053	2051	3811	6472	6516	5450	6411											
6'-8" (80')	PRECAST	822	901	1671	2933	2576	3223	3872	4522											
7'-6" (90')	PRECAST	665	901	1671	2933	4100	6130	8171	6701											
9'-8" (116')	PRECAST	311	420	834	1253	1071	1342	1614	1886											


LENGTH	TYPE	RUB	UPLIFT										LATERAL							
			8R16-IT	8R20-IT	8R24-IT	8R28-IT	8R32-IT	8R36-IT	8R40-IT	8R44-IT	8R48-IT	8R52-IT	8R56-IT	8R60-IT	8R64-IT	8R68-IT				
4'-4" (52')	PRECAST	1244	1513	2415	3260	412	4961	5825												
4'-6" (54')	PRECAST	1192	1507	2311	321	3931	4756	5571												
5'-8" (68')	PRECAST	501	524	1435	1741	2357	2878	3409												
5'-10" (70')	PRECAST	469	506	1338	1742	2352	2965	3581												
6'-8" (80')	PRECAST	330	378	1099	1630	2288	2891	3497												
7'-6" (90')	PRECAST	210	248	697	1025	1420	1820	2220												
9'-8" (116')	PRECAST	124	156	433	608	808	1028	1248												

### CONNECTOR SCHEDULE


CONNECT. TYPE	SIMPSON		USP		MAX. UPLIFT	LAT. LDS. FI / F2
	DESCRIPTION	FASTENERS PER CONNECTOR	DESCRIPTION	FASTENERS PER CONNECTOR		
4	HETA20	14-10d x 1 1/2"	ETA20	14-10d	1810	65 / 960
5	DETAL20	18-10d x 1 1/2"	N/A	N/A	2480	2000 / 1370
20	H3	RFT: 4-8d / PLT: 4-8d	RT3	RFT: 4-8d / PLT: 4-8d	455	125 / 160
21	HI	RFT: 6-8dx1 1/2" / PLT: 4-8d	RT15	RFT: 5-8dx1 1/2" / PLT: 5-8d	475	485 / 165
22	HI09	RFT: 8-8d x 1 1/2"	RT16	RFT: 8-8d x 1 1/2"	930	585 / 525
23	LUS26	HDR: 4-10d / JST: 4-10d	JUS26	HDR: 4-10d / JST: 4-10d	935	N/A
24	H1	RFT / TR6: 4-8d	RT20	RFT / TR6: 9-10d	985	400 / N/A
26	H25	RFT: 5-8d / PLT: 5-8d	RT1	RFT: 5-8d / PLT: 5-8d	415	150 / 150
34	A34	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	MP34	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	365	280 / 303
35	A35F	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	MPAIF	H: 6-8dx1 1/2" / P: 6-8dx1 1/2"	440	440 / N/A
37	MTS12	14-10d	MTW12	14-10d	1000	N/A
38	MTS16	14-10d	MTW16	14-10d	1000	N/A
39	MTSM16	BLK: (4) 1/4" X 2 1/4" T.C. TRUSS: (7) 10d	MTW16	BLK: (4) 1/4" X 2 1/4" T.C. TRUSS: (7) 10d	860	N/A
43	LSTA12	10-10d	LSTA12	10-10d	905	N/A
45	ST18	14-16d	ST18	14-16d	1200	N/A
47	LSTA24	18-10d	LSTA24	18-10d	1295	N/A
71	MSTA36	26-10d	MSTA36	26-10d	2135	N/A
72	MSTC66	64-16d SINKERS	N/A	N/A	5,495	N/A
79	SF1	STD: 6-10d / PLT: 4-10d	SPT22	STD: 4-10d / PLT: 4-10d	535	560 / 260
80	SF2	STD: 6-10d / PLT: 6-10d	SPT224	STD: 6-10d / PLT: 6-10d	605	560 / 260
81	SPH468	12-10d x 1 1/2"	TP46,48	12-10d x 1 1/2"	885	N/A
88	CBSQ88	12 SDS 1/4X2"	TP46,48	12-10d x 1 1/2"	3975	N/A
89	CB66	(2) 5/8" BOLTS	PA8X8	4-10d	2,300	985
90	ABU66	12-16d	PAU66	12-16d	2,240	N/A
91	CBSQ66	14 SDS 1/4X2"	PAU66	12-16d	3,190	N/A
92	ABU44	12-16d	PAU44	12-16d	2,200	N/A
93	AC6 (MAX)	28-16d	PBS66	24-16d	1,815	1,070
94	AC4 (MAX)	28-16d	PBS44	24-16d	1,815	1,070
95	HTS20	20-10d	HTW20	20-10d	1,450	N/A
96	HD8A	SILL: 3/8" BOLT STUD: (3) 1/8" X 5 1/2" BOLTS	HH8A	SILL: 3/8" BOLT STUD: (3) 1/8" X 5 1/2" BOLTS	7,910	N/A
97	MTT28B	24-16d	MTS27B	24-16d	4,455	N/A
99	A35	H: 4-8dx1 1/2" / P: 4-8dx1 1/2"	MFAI	H: 6-8dx1 1/2" / P: 6-8dx1 1/2"	440	440 / N/A
101	HTT4	5/8" BOLT / 18-16dx2 1/2"	N/A	N/A	3,640	N/A
102	HTT5	5/8" BOLT / 26-10d	N/A	N/A	4,275	N/A
103	VGTR/L	32-SDS 1/4" X 3" / (2) 5/8" BLT	N/A	N/A	3,990	N/A
104	HDU8-SDS25	1/8" BLT / 20-SDS 1/4" X 2 1/2"	N/A	N/A	5,020	N/A
110	HCP2	12-10d x 1 1/2"	HHCP2	20-10d x 1 1/2"	520	260 / N/A
167	HHU846	H: 14-16d / J: 6-16d	THD46	H: 8-18d / J: 12-10d	1,550	N/A
168	U46	H: 8-10d / J: 4-10d	SUH46	H: 8-16d / J: 4-16d	710	N/A
181	HUS26	20-16d	THD26	H: 20-16d / J: 10-10d	1,550	N/A
184	HUC28-2	H: 14-16d / J: 4-10d	N/A	N/A	1,085	N/A
212	HUC410	HD: 18-1/2" X 1 3/4" LAG SCR. BM: 10-10d	N/A	N/A	1,810	N/A
214	HUC412	BLOCK: 10-1/4" X 1 1/2" TC JOIST: 10-16d	HUS412	BLOCK: 10-1/4" X 1 1/2" TC JOIST: 10-16d	1,895	N/A
215	HGU8210-2	HDR: 46-16d / JST: 10-16d	EHU8210-2	HDR: 40-16d / JST: 16-10d	2,720	N/A
216	HUC8412	BLOCK: 10-1/4" X 1 1/2" TC JOIST: 10-16d	HUS412	BLOCK: 10-1/4" X 1 1/2" TC JOIST: 10-16d	3,240	N/A
217	HUS212-2	BLOCK: 10-1/4" X 1 1/2" TC JOIST: 10-16d	HUS212-2	BLOCK: 10-1/4" X 1 1/2" TC JOIST: 10-16d	2,630	N/A
219	MBHA412	H: 1-ATR3/4 X 8 TOP FACE JOIST: 18-10d	NFM35X12U	H: 1-1/2" J-BOLT J: 5-1/2" BOLTS	3,145	N/A
2						




3 DETAIL (BRG. W/ UPLIFT)  
 1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



1 DETAIL (BEARING POST W/ HIGH UPLIFT)  
 1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



4 DETAIL  
 1/2"=1'-0" (11X17) 1"=1'-0" (22X34)



2 DETAIL  
 1/2"=1'-0" (11X17) 1"=1'-0" (22X34)

THRIVE PRODUCT

THIS STRUCTURE IS DESIGNED TO WITHSTAND 140 MPH WINDS PER THE 8th EDITION, 2023 OF THE FLORIDA BUILDING CODE RESIDENTIAL AND IS CERTIFIED AS SUCH

LOT: 0000, COMMUNITY 1501 DELIGHT THRIVE SERIES

REVISIONS	BY

© COPYRIGHT 2021 RDC, INC. hereby reserves its common law copyrights and other copyrights in these plans, ideas, and design. These plans, ideas and designs are not to be copied or changed in any manner or form whatsoever, nor are they to be assigned to any third party without first obtaining the express written permission from RDC, INC.

**ITEG**  
 THOMPSON ENGINEERING GROUP, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 734-1730  
 Fax: (407) 734-1730  
 www.iteg.com

A DIVISION OF PARK SQUARE ENTERPRISES, INC.  
 5200 Vineland Road, Suite 200  
 Orlando, Florida 32811  
 Phone: (407) 529 - 3000

**Park Square HOMES**

TYPICAL DETAILS / CONNECTOR SCHEDULE

DATE 06-01-22  
 SCALE AS NOTED  
 DRAWN RDC  
 JOB 1501  
 SHEET 11  
 OF SHEETS